A WEEKLY JOURNAL OF PRACTICAL INFORMATION, ART, SCIENCE, MECHANICS, CHEMISTRY, AND MANUFACTURES.

Vol. LXIX.--No. 22. Established 1845.

NEW YORK, NOVEMBER 25. 1893.

ELECTRIC LAUNCHES AT THE COLUMBIAN EXPOSITION.

No electrical feature at the World's Columbian Exposition was entered upon with more uncertainty than the introduction of electric launches on the lagoons, as up to this time such launches had not been made use of in this country except in an experimental way. In spite of these uncertainties, however, the launches were among the first electrical features that were ready and they have fulfilled their requirements during the entire period that the Exposition has been open, with gratifying results, carrying over one million passengers and earning \$314,000.

There are fifty of these launches that did service for the public, all of the type shown in our first page illustration. Each boat is 35 feet 10 inches over all in length and 31 feet 6 inches on the water line. The beam is 6 feet 21/2 inches and the draught 27 inches. The lines are as near perfection as they well can be. At whatever rate the launch runs there is practically no wake, so that the wash on the shore, even in such narrow waterways as the lagoons, is of no consequence. The hulls of these boats were constructed of white oak frames, with white cedar planking. The inner paneling, decks and other parts are of mahogany. All the woodwork is finished in its natural color, thus giving a very rich appearance. Cut No. 4 shows the launch complete, with the pilot in the forward end controlling the supply of electricity and steering. The passengers are scattered about, the full seating capacity being 30 people. Cut No. 5 gives an idea of how the launches looked when laid up. Their berths were at the southeastern corner of the Agricultural building, in the South Pond, 30 boats being on the left in the picture and 20 on the right. When the boats were station can be fitted up at little expense, and there is

The charging was all done at night, so as not to interfere with regular trips during the day.

Cut No. 1 gives a sectional view of a launch. It will be noticed that the motor is placed low down and in the center of the boat. This motor was designed and made especially for this use by the General Electric Company for the Electric Launch and Navigation Company, whose offices are at 44 Broad Street, New York City, which holds and owns the patent rights for the launches.

The motor is protected by a box which rises flush with the main deck of the boat, and is so set that all working and wearing parts can be readily reached. The storage batteries are placed around the sides of the boat, under the seats and entirely out of sight. The motor is nominally of four horse power, and is coupled direct to the propeller shaft. The type of this motor is shown in cut No. 3, while cut No. 2 illustrates the thrust ball bearing in which the shaft runs. By this combination of direct coupling and thrust bearing, all gearing and loss of power, as well as unnecessary noise and jar, are done away with.

The batteries used are of the Consolidated Electric Storage Company's type, of 150 ampere hours' capacity. Each boat has 66 cells, and these cells can be arranged in three groups of 22 cells in series or in two groups of 33 cells in series. Several improved devices have been brought out to adapt these cells to this use, so that hour, but they have a reserve speed of from eight to there shall be no danger of the liquid spilling or of the efficiency of the cells being unnecessarily impaired. The cells are readily charged. The manner in which this is done is shown in the illustration. A charging

to be charged they were laid up here, and whenever probably no lake, river, or harbor in the country with a boat needed repairs it was hauled up in its berth. sufficient water to float a launch where such a station could not be readily had. A current of 18 amperes per group is the one generally used to charge after a run of fifty or sixty miles at nominal speed, and from six to seven hours time is required. In case of necessity. however, a current of 30 amperes can be used, when the batteries can be charged in four or five hours. The plant which provided the current at the Exposition comprised a direct current shunt-wound Edison generator, giving a current of 110 volts. Any form of electric energy, however, arc or incandescent, can be used. Even when only an alternating current is to be had, a charging station can be arranged with not very great expense. When the station is once completed, all that is necessary is to connect the charging wires to a set of binding posts on the boat, as shown in the illustration, and turn on the current.

The operation of one of these boats is exceedingly simple, as shown by the experience of the Electric Launch and Navigation Company at the Exposition. Not one of the pilots or guards that managed the fleet had ever before handled an electric launch, yet they experienced no trouble whatever from the first. The control is by means of a small lever switch at one side of the steering wheel, which is located in the forward part of the boat. This lever allows of four speeds forward and two backward. The nominal speed at which the boats are run is from six to seven miles an ten miles. At the ordinary speed the launches at the Exposition have been in constant use from twelve to fourteen hours a day on one charging, and the cost of this charging has never exceeded sixty cents per day per (Continued on page 343.)

Hillian Contraction of the Contr manpugananananan matati

ELECTRIC LAUNCHES AT THE COLUMBIAN EXPOSITION.

Scientific American.

ESTABLISHED 1845.

MUNN & CO., Editors and Proprietors. PUBLISHED WEEKLY AT

No. 361 BROADWAY, NEW YORK.

A. E. BEACH.

TERMS FOR THE SCIENTIFIC AMERICAN.

The Scientific American Supplement

is a distinct paper from the Scientific American Supplement is issued weekly. Every number contains 16 octavo pages, uniform in size with SCIENTIFIC AMERICAN. Terms of subscription for SUPPLEMENT, \$5.00 a year, for the U. S., Canada or Mexico, \$6.00 a year to foreign countries belonging to the Postal Union. Single copies, 10 cents. Sold by all new-sdealers throughout the country. See prospectus, last page.

Combined Rates.—The SCIENTIFIC AMERICAN and SUPPLEMENT will be sent for one year, to one address in U. S., Canada or Mexico, on receipt of seven dollars. To foreign countries within Postal Union, apht dollars and fifty cents a year.

Building Edition.

Building Edition.

The Architects and Builders Edition of the Scientific American is a large and splendid illustrated periodical, issued monthly, containing floor plans, perspective views, and sheets of constructive details, pertaining to modern architecture. Each number is illustrated with beautiful plates, showing desirable dwellings, public buildings and architectural work in great variety. To builders and all who contemplate building this work is invaluable. Has the largest circulation of any architectural publication in the world.

Single copies 25 cents. By mail, to any part of the United States, Canada or Mexico, \$2.50 a year. To foreign Postal Union countries, \$3.00 a year. Combined rate for Building Edition with Scientific American, to one address, \$5.00 a year. To foreign Postal Union countries, \$6.50 a year. Combined rate for Building Edition, Scientific American and Supplement, \$3.00 a year. To foreign Postal Union countries, \$1.00 a year.

Spanish Edition of the Scientific American.

Spanish Edition of the Scientific American.

1.4 America Cientifica E Industrial (Spanish trade edition of the Scientific American) is published monthly, uniform in size and typography with the Scientific American. Every number of Lamerica is profusely illustrated. It is the finest scientific, industrial trade paper printed in the Spanish language. It circulates throughout Cuba, the West In lies, Mexico Central and South America, Spain and Spanish possessions—wherever the Spanish language is spoken. \$3.00 a year, post paid to any part of the world. Single copies \$5 cents. See prospectus.

MUNN & CO., Publishers,
361 Broadway, New York, draft or bank check. Make all remittances payable to order of MUNN & CO.

Readers are specially requested to notify the publishers in case of any failure delay, or irregularity in receipt of papers.

NEW YORK, SATURDAY, NOVEMBER 25, 1893.

Contents.

(Illustrated articles are marked with an asterisk.)

 Fish, freezing.
 343
 graphing.
 340

 Fluorine.
 343
 Victoria, the loss of the.
 344

Aluminum, reduction in price of 345
Balloon accident, singular. 338
Bees, how many to a pound 339
Birds, leaving us. 344
Bookcase, Stimson's metallic* 342
Building, rapid 346
Clistern construction (5523) 349
Chicken beheader, Denham's* 341
Color among fishes. 339
Colors action of light on dyed. 347
Columbia, the new war steamer' 340
Disinfectant, peroxide of hydrogen 348
Disinfectant, peroxide of hydrogen 349
Disinfectant, peroxide of hydrogen 349
Electrical inventions, recent. 348
Electrical inventions, recent. 349
Electrical inventions, rece

TABLE OF CONTENTS OF

SCIENTIFIC AMERICAN SUPPLEMENT

No. 934.

For the Week Ending November 25, 1893.

Price 10 cents. For sale by all newsdealers

1. Blography.—Marcchal de MacMahon.—The famous French Marshal of France, lately deceased.—Notes of his life, with por-BIOGRAPHY.—Marcula de Marshal of France, lately deceased.—Notes of his life, with portrait.—I illustration.
The John Hunter Centenary.—The life of the most famous British surgeon of the last century.—7 illustrations. . 14930

other low forms of hig lying on the ocean each continuous time. The following of the ocean each continuous in anthropology at the Exposition.—In illustrations.

Old Locomotives at the Columbian Exposition.—Interesting exhibit of a number of early locomotives marking the development of American practice.—Illustrations.

The Exhibition of Paintings at Chicago.—A valuable review of the pictures shown at the great Exposition.—Notes on the different artists, and the national characteristics of their work.

IV.—EDUCATION.—Technological Schools.—Their purpose and its accomplishment.—By ROBERT H. THURSTON.—A great need of the United States discussed by a leading educator......................... 14920 V. GEOGRAPHY.—The War in Africa.--By ARCHIBALD R. Col-QUHOUN.—Scene of the war in Matabeleland and character of

the natives and king.—3 illustrations...... VI. HYGIENE.—Of the Pleasures of Eating and of the Means that may be Employed for Increasing Them.—Extract from an essay by Count RUMFORD, being a plea for the utility of enjoyment of eating.

eating.

VII. MEDICINE.—Pilocarpine—Its Physiological Action and Therapeutic Uses, with Exhibition of Specimens showing change in the Color of the Hair.—By D. W. PIENTISS, M.D.—Conclusion of this interesting article, treating of the changes in the color of the hair produced by this alkajoid and by other causes.

Therapeutical Superstition.—By GEORGE T. WELCH.—Curious instances of medical practice and extraordinary remedies.—Interesting instances of old and new medical practices.

VIII. MISCELLANEOUS.—In the Bank of England.—Interesting objects to be seen in the famous institution.

The New Congressional Library.—One of the greatest buildings in the United States. now under process of construction...... 14925

IX. PHOTOGRAPHY.—Electrical Action of Light upon Silver.—By Colonel J. WATERHOUSE.—Some interesting researches on photo-chemistry—Observations on the reversal of the photographic image.
The First Photo-Mechanical Reproduction.—By JULIUS F. SACHSE.—A disputed point in the history of this art.—A famous question discussed.
Varnishes and Varnishing.—Formulæ and directions for photographic varnishes. 14921

X. RAILROAD ENGINEERING.—The Motive Power will Stay at the Head of the Train.—The possbillity of electric motors in rail-way service reviewed.—Their disadvantageous features.—Ad-vantages of concentrating power.

MORE ENGINEERS NEEDED FOR THE NAVY.

The annual report of Geo. W. Melville, Engineer-in-Chief, Chief of Bureau of Steam Engineering, shows that the repairs of machinery and steam vessels during the past year have cost something over \$600,000. The lack of competent engineers to man the rapidly increasing number of war vessels has become a serious matter. On the active list there are only 180 commissioned officers in the engineer corps, namely, 70 chief engineers, 66 passed assistants, and 44 assistants.

The chief says: "Unless something is soon done, our navy, now practically an engineering one, will be crippled for want of engineers.

"This question of the sufficiency of engineers in the service is one of paramount importance, and no other, if left in abeyance, will so vitally affect the efficiency of the navy as a fighting organization. It must be remembered that the efficiency of the modern war ship, either as a fighting machine or as a commerce destroyer, depends wholly and absolutely upon her machinery, and the efficiency of this machinery upon the skill of her engineers, and upon the diligence exercised by them in its care and management. Be her armor and armament the most powerful and her commander the most capable and intrepid, if her machinery fails, she is helpless, and no ships of the British navy. Among these, at present, amount of seamanship and gunnery will avail against the enemy.

"Were the navy a mercantile concern, the present state of affairs would not last beyond the time necessarv to change it, for men with capital invested in machinery see to it that there is a force sufficient to keep it in proper maintenance; and surely if business people find such a course economical, the government cannot do better than follow their example. The value of the naval machinery now owned by the gov ernment and in process of construction is about \$24,000,000, and it has now come to the point where Congress must decide whether it is more economical to properly care for this machinery and keep it always in an efficient condition or to let it run as long as it will and then replace it, taking meanwhile the risk of having it fail when most needed. As an illustration of the increased work thrown on the members of the engineer corps by the acquisition of the new navy. I can state that the New York has added 17 per cent to the horse power of the machinery of vessels in commission; the Columbia will add 17.3 per cent more; and when the ships now authorized and building are finished, the horse power of the propelling machinery of the navy will have increased to nearly two and a half times its present amount—and yet we are asked to run it with the same number of engineer officers that we now have.

"The officers of the engineer corps at sea on the new vessels have altogether too much work to do now, and it is merely a question of time before the strain will tell. The result of this hard work is being seriously felt: retirements are increasing, and the government thus subjected to an expense greater than would be involved in now granting a fair increase of numbers, while some of those who manage to complete a cruise in one of the high-powered ships only await a favorable opportunity to resign. Many of our young officers who have resigned to accept lucrative and responsible positions would have preferred to remain in the service if they could have seen any chance of advancement in it."

THE COLUMBIA, THE NEW COMMERCE DESTROYER.

The new American navy has become a popular subject with the people at large. The records of the trial trips are given place in the papers, and much congratulation is expressed over the results obtained. Yet the fact is apt to be forgotten that a few hours' run of a new ship under the most favorable auspices does not tell what she will do in the service. To-day no satisfactory method of keeping an iron ship's bottom free from barnacles and seaweed is known, and the slightest deposit reduces speed. The duration of the engines and boilers under service conditions is problematical. The warship certainly seems to deteriorate or to develop weakness in her boilers or machinery in ery short periods.

From the old sailing vessel, through auxiliary steamships, the development has at last brought us to triple screw ships without sail power enough to be of more than the slightest service. It is perhaps true, as ex-Secretary Tracy says, that we have in the Columbia, New York and Olympia three ships unapproachable in good qualities. But admitting this, the question has to be answered of how long these ships will retain their qualities. Will they hold their present efficiency for years, or even months? Time and repeated speed trials can alone show this.

An attempt was made on Thursday, November 16, to subject the new cruiser Columbia to an official trial over a 44 knot course. Buoys were placed along the course, vessels were anchored near each buoy, and the ship started on her trial run. On the trip from Philadelphia to Boston, she had already shown very high speed. On attempting the trial, however, the sea was 14924 so high that the buoys were displaced, and the attend- to Turin.

ant vessels could not lie at anchor, so the trial was abandoned. Sufficient, however, was done to show that the vessel does possess very high powers, reaching a rate of speed, for a short run, from 28 to 29 statute miles an hour. This speed of course she could not long maintain, but for a ship of her size to reach it was very extraordinary. Not only was her rate of travel very high, but the Columbia is designed to have a very long radius of action, being able to steam around the world without recoaling.

While the above sounds very satisfactory, and the ship is apparently a triumph of American construction, experience has shown that it is not safe to judge a war vessel from these trials. A vessel designed for use as a warship, when put in charge of the navy and kept in such service, never is able to hold her original record. The English government has all its ships of war rated, each one at its specific speed, but it has time and again been shown that the rating is far too high, and the ships, owing to deterioration of the propelling apparatus or to marine growth on their bottoms, always show a greatly reduced speed.

The Columbia is built for a commerce destroyer. She may be able to run away from any heavy fighting ship. In war her competitors would be the fastest are the reserve ships Campania and Lucania, of the Cunard line, ships which day in and day out maintain speed approximating to the highest obtainable by the Columbia on her trial trip, ships which from the conditions of their service are always kept in the best possible condition for instant service. Each regular trip consists of a run of some 3,000 miles, in which runs a gain of five or ten minutes over the record is eagerly striven for. It is not improbable that the Columbia, driven under forced draught, straining every fiber under the action of the machinery, stripped and in the most perfect condition for a few hours' run with selected coal, will earn for her builders a premium of \$400,000. After all this she will not have been properly tried. She should be manned with a crew from the American navy, she should be coaled under ordinary conditions of quality of fuel, and her trial course should be the same as that of the Cunard ships or of the German or American line vessels—the course of about 3.000 nautical miles across the ocean. Then we could establish her true rating, and the trial would show whether she could compete in war with the Lucania and Campania. with the Furst Bismarck or the Paris. In the present system of trial trips everything is subordinated to making the highest possible speed over the short course of forty to fifty miles.

While her trial has been in progress or preparation, Mr. Charles H. Cramp, of Philadelphia, who represents the firm which built her, presented before the Society of Naval Architects and Marine Engineers of this city a paper on the "Evolution of the Atlantic Greyhound." In about a year the two ships of the American line built at the Cramp yard will be in commission. In them he proposes to go back to the old American idea of high initial stability and make ships which will stand on their own bottoms without the use of 1,000 tons of ballast. These ships will be in continual service and will be driven at full speed under the regular conditions of their work. In such vessels as these enrolled as a naval reserve would seem to be the greatest hope of our navy for the really efficient commerce destroyer.

A Singular Balloon Accident.

A Rome correspondent of the London Daily Graphic says: Captain Charbonnet and his wife recently met with an extraordinary balloon accident in the Alps. Captain Charbonnet was a well known Italian aeronaut. He was recently married in Turin, and, in accordance with a previous decision, the couple set out immediately in a newly constructed balloon—the wedding present of the bridegroom to his bride. Their intention was to spend their honeymoon in making a series of aerial trips across the Alps. They were accompanied by a male friend named Giuseppe Ponta. The first day's trip proved successful. On the following day, however, when near the Cairainella Peaks, the balloon was caught in a hurricane, dashed violently against a glacier, and broken up. Strangely enough, the occupants escaped this mishap with trifling injuries. The balloon, of course, was useless. The unfortunate trio remained on the snow and ice until the following morning, when a descent of the mountain was attempted. It was during this descent that Charbonnet lost his life, disappearing suddenly in a crevasse. His unfortunate wife and Signor Ponta, who were forced to spend the rest of the day and the following night on the mountain, suffered terribly from the cold. Signor Ponta fell and sustained serious injuries, Signora Charbonnet having thus to make her way alone. She managed at length to reach a mountaineer's hut. Here, acting upon her instructions, a party of men discovered Ponta and brought him safely back. The remains of Captain Charbonnet were recovered on the following day. Two days later Signora Charbonnet and Signor Ponta were sufficiently recovered to be removed

Natural History Notes.

Discovery of an Egg of the Æpyornis.—A large specimen of the egg of the fabled "roc" of the "Arabian mals like the modern marsupials, rudiments of the Nights," or *Epyornis*, as the extinct gigantic bird of Madagascar is called, has recently been secured by Mr. them. Dr. H. Klaatsch has just made the interesting J. Proctor, of Tamatave and London. It was discovered by some natives about twenty miles to the southward of St. Augustine's Bay, on the southwest coast of Madagascar. It was floating on the calm sea, within twenty yards of the beach, and is supposed to have been washed away with the foreshore, which consists of sandhills, after a hurricane in the early part of the vear. The child-like longshoremen of the antipodes. thinking that the egg might have a value, showed the unusual piece of flotsam about, with a view to the sale of it, and it thus came into the hands of Mr. Proctor, who has brought the curiosity to London. The egg, which is whity-brown in color and unbroken, is a fine specimen, 331/2 inches by 28 inches, and an even higher value is placed upon it than upon the egg of the great auk, which lived within the memory of man. The Brobdignagian proportions of the egg are better demonstrated by comparison with the eggs of the ostrich and crocodile. An ostrich's egg is about 17 the dark shadowed tank remained practically uninches by 15 inches, and the contents of six such are only equal to one egg of the Æpyornis. The measurements of the egg of the crocodile are normally 9 inches intensity of coloring. The beautiful gold bronze luster by 6\% inches. It would require the contents of 16\% emu's eggs to equal the contents of this great egg, or the backs were mottled black and white, contrasting 148 eggs of the homely fowl, or 30,000 of the humming strangely with the nearly unbroken yellowish black bird. The last egg of the kind disposed of in London sold for £100, though cracked.

A Plant with Anomalous Position of Flowers.--In the Journal de Botanique for July 1 and 16. Mr. Hua describes, as a new genus, a plant from west tropical Africa, in which the flowers are borne along the midrib on the back of the leaf. This anomalous position of the flowers is only of rare occurrence, appearing in a few almost or quite monotypic genera, such as the Japanese Helwingia of the Araliace, the saxifragaceous Phyllonoma of the New World, and Polycardia (Celastrineæ) from Madagascar. The common lime recalls, in a small degree, the same phenomenon, the stalk of the inflorescence adhering to the lower ning of the experiment. The whole of these color part of the bract and appearing to spring from the changes were effected within the remarkably short middle of that organ. Tropical West Africa boasted period of a week. already two genera with epiphyllous flowers, both belonging to the family Bixineæ, and Mocquerysia, the new one established by M. Hua (named after its discoverer. M. Mocquerys) resembles these in some points. and is placed by its author in the same natural order.

Fishes at High Temperatures.—Dr. Lawrence Hamilton has recently forwarded to Natural Science some interesting statistics that he has collected in reference to the existence of fishes in water of a high temperature. Some of the cases are very striking. Spallanzani, it appears, observed river carp living at a temperature of 106° F., and exhibiting no signs of uneasiness, though at 109° they began to struggle, and died at 116° F. Dr. John Davy (1835) showed that the bonito had a temperature of 99°, while the water of the Mediterranean, in which it was, had only a temperature of 80°. Saussure stated that he found eels in the hot springs of Aise, in Savoy, at a temperature of 113° F. In 1882, Dr. Davy found that water at 85° F. killed trout by convulsions. A trout and a minnow were put use it more or less in feeding, whether or not sight aids in water at 70° at night, which by the next morning them in the process. Some further experiments on had sunk to 67°, when the trout was dead, though the minnow had not suffered. A salmon parr at 80° became convulsed and torpid, dying at 84°. Several fishes were deposited in water at 53° F.; the temperature of the water was gradually raised, and none showed signs of failing vitality till the thermometer rose to 82°, when the perch became prostrated, roach succumbed at 821/2°, salmon at 83°, minnow at 85°, gud-91°. Brandy restored all the fishes except the dace,

In India fishes at noon day in their natural water remain in health at 92°: at 4 P. M., 86°; and at 6 P. M., repentance, after it had swallowed clams that had poses as a protective measure during any epidemics Gunther states that cyprinodonts live in briny springs even at a temperature of 91° F.

Sir Emerson Tennent collected the following observations, which seem to require further proof or veri-

the Apogon thermalis, and the Ambassis thermalis, instance, appears to pay much more attention to smell, in water at 115° F.; a roach, Leuciscus thermalis, at and, as a rule, turns about and withdraws on approach-

water at 210° F. but this is, of course, an absurdity lead baits are successfully employed in cod fishing in twenty-five thousand individuals; but some swarms which nowadays, it is to be hoped, no one will believe. the Moray Firth and off the Northern Islands, while have double this weight and number of bees.

Rudiments of a Pouch in Placentals.—If ordinary placental mammals have evolved from pouched anipouch ought certainly to be recognizable in some of announcement that such rudiments can actually be observed in most placentals. Something of the kind has already been found in the lemurs, and one author has supposed that rudiments of the pouch can also be detected in the sheep. The detailed account of Dr. Klaatsch's extension of the evidence will be awaited with interest.

Color Assimilation among Fishes. - We already know a good deal about this, says Mr. James Hornell. in Natural Science, especially among the flat fishes; so the following instances but go to swell an already long list. Still, these are so striking as to be worthy of permanent record.

Two tanks were used for experiment, one with dark background and bottom, well shadowed; the other bright, with a white mottled sand bottom. Several of than by day; which suggests that it, too, not only the marine stickleback (Gasterosteus spinachia) were placed in each. To sum up the result briefly, those in changed in color, but those in the light colored tank had in greater or less degree lost their brightness and so characteristic of these sticklebacks was lost, and of the dorsal surface of their friends in the dark

In the dark tank had also been placed a number of wrasses (Labridæ), and these showed fading all round, most marked in the bright greens and scarlets. As these colors are usually in combination with brownish marking, the fading of the bright hues meant a close approximation to the brown appearance of the bare conglomerate forming the rockwork of the tank. One fish especially beautiful at first (of a most brilliant scarlet and brown) faded to a dirty combination of pale olive green and brown, scarcely recognizable had the fish not been marked in a distinctive manner at the begin-

It may be that these instances of color assimilation carry the key to the problem of color variation or rather mimicry in the prawn Hippolyte (Virbius) varians.

Plaice (Pleuronectes platessa) have also shown rapidity of color change much more marked than I was prepared for. Some that were placed in a large shallow tidal pond where the color of the bottom varies considerably and where a portion is often in deep shadow, show change from a uniform gray to a well marked and intensely dark blotched appearance within a few seconds. Indeed, it is quite chameleon-like, so quickly is the transformation effected. In ordinary tanks, where the light and color of the sand are stable, the plaice soon take the exact coloring requisite, and retain it without alteration so long as they remain in the particular tank.

the sense of smell in fishes is very keen, and that all the subject have been made by Mr. Gregg Wilson in the Plymouth Marine Biological Association, and the 24 hours, is usually sufficient to sterilize a water. following observations from his recent report to the British Association will be read with interest:

"So far as I could determine, fish that are not very hungry habitually smell food before taking it. The pollack seems usually to be ready for a meal, and on almost all occasions when anything eatable is thrown organisms were destroyed after 24 hours by this progeon at 851/2°, dace at 86°, tench at 88°, and carp at into the tank in which it is swimming it rushes toward it and bolts it. It does not hesitate to take stale food or over, specially mentions that he found this addition in food that has been steeped in strong smelling fluids; and no way interfered with the dietetic value of the water; time after time I have been amused to see its too-late and he recommends its application for household purbeen saturated with alcohol, chloroform, turpentine, of typhoid fever and cholera. Traugott also testifies etc. It is only when it is satiated with fresh food or to the innocuous character of this material, even when disgusted with what is nauseous that it takes the pre-| swallowed in large doses. Care must, however, be caution to smell before eating. On the other hand, taken that it is as pure as possible; moreover, it is im various fish that are equally keen-sighted, and habitu- portant that the sample should be freshly prepared, In the hot springs of Ceylon, living carp, Nuria ally recognize their food by the use of their eyes, are as its strength and consequently bactericidal action is thermoicus, at 114° F.; members of the perch family, more prudent. The whiting (Gadus merlangus), for reduced when preserved for some time. ing within a few inches of high-smelling objects that In a hot spring at Pooree (in the province of Ben- the pollack would take without hesitation. Even whitgal), with the thermometer in the water standing at ing, however, cease to be delicate if they are very hun-112° F., carnivorous fishes have been discovered, which gry, and if other fish are present to compete for the would indicate that these must have found and fed on food that is thrown to them. In such circumstances living prey at the same high temperature. Further bait that is very distasteful may be taken by even the loaded bee, when he comes in fresh from the fields and accounts, moreover, declare that in hot springs in most cautious of sight feeders; and likewise, in such Barbary, in North Africa, living fishes have been taken | circumstances, a quite smell-less artificial bait may be in water at 172°, while in Manila (one of the Philippine | successfully employed. Where large shoals of fish are, | his own weight. Of loaded bees there are only about Islands) in water marking 187° F. While traveling in there are likely to be many that are very hungry, and South America, Humboldt and Koupland stated that the consequent keen competition will lead to hasty they saw fishes thrown up alive from a volcano in feeding by sight alone; and hence it is probably that pounds of bees, or between twenty thousand and

they are of no avail among the scanty fish further south.

"It may be said that in these cases the fish actually search for their food by sight alone, and merely test the quality of what they have found by smelling it; and Bateson quite recognized this. But more is possible, habitual sight-feeders can be induced to hunt by smell alone. The pollack, which is such a pronounced sight-feeder that it will take a hook baited with a white feather or a little bit of flannel and trolled along the surface, is vet able, when blinded, to get his food with great ease. Several blind specimens in the Plymouth tanks were carefully watched by me; and I had no difficulty in deciding that it was by smell alone that they found their food. Their conduct was exactly such as was seen in the smell-feeders, to which I shall presently refer.

"Again, the cod (Gadus morrhua), which Bateson puts among the sight feeders, is generally believedand with good reason, I think—to feed more by night tests its food, but actually hunts by smell.

"Lastly, in this connection, I would state the results of my experiments. I worked with a number of fish, and always with the same success, but I shall here refer only to one case—that of the dabs (Pleuronectes limanda). That they were sight-feeders was evidenced by their behavior when I lowered a closed tube full of water, and with a worm in the middle of it, into the tank; time after time they bumped their noses against the glass at the very spot where the worm was situated. That they could also recognize the smell of food, apart from seeing it, was demonstrated in various ways.

"First, if instead of a closed tube, as in the last mentioned experiment, one open at the bottom was used, after a short interval the nosing at the part where the worm was seen ceased, and the lower end of the tube, from which, doubtless, worm juice was diffusing, was vigorously nosed. If, again, instead of putting worms into a tube, I placed a number of them in a closed wooden box with minute apertures to let water pass in and out, there was a similar excitement produced, and the dabs hunted eagerly in every direction. When water in which many worms had lain for some time was simply poured into the tank through a tube that had been in position for several days, and by a person who was out of sight of the dabs, the results were most marked. In a few seconds, hunting began, and in their excitement the dabs frequently leaped out of the water, apparently at air bubbles, and, on one occasion, one even cleared the side of the tank, which was about two inches above the water, and fell on to the floor of the aquarium. Yet there was nothing visible to stimulate this quest."

Peroxide of Hydrogen as a Disinfectant.

The disinfecting properties of peroxide of hydrogen have long been known; but considerable additions have recently been made to our more exact information as to its bactericidal action. Its hygienic importance, especially in regard to its action upon bacteria in water, has been shown by the interesting experi-The Sense of Smell in Fishes.—It is well known that ments of Van Tromp and Altehoefer, to which reference was made in a recent number of Nature. According to the former, an addition of peroxide of hydrogen in the proportion of 1 part in 10,000 parts of the water, when shaken up and allowed to stand for Altehoefer, however, found that, to insure sterility, it was advisable to use larger quantities—viz., 1 part in 1,000 parts of the water. Experiments made with waters purposely infected with cholera and typhoid bacilli, respectively, showed that in both cases these portion of peroxide of hydrogen. Altehoefer, more-


How Many Bees Make a Pound?

This question is answered in a recent number of the American Apiculturist. Careful weighing shows that an ordinary bee, not loaded, weighs the one fivethousandth part of a pound, so that it takes fivethousand bees, not loaded, to make a pound. But the flowers loaded with honey or bee bread, weighs nearly three times more, that is to say, he carries nearly twice 1,800 in the pound.

An ordinary hive of bees contains from four to five

AN IMPROVED ROTARY ENGINE.

This engine, recently patented by Mr. O. E. Morse, of Dillon, Montana, is designed to utilize the steam to the fullest advantage, and the engine is readily reversed by simply shifting the lever to change the position of the slide valve. Fig. 1 is a view in perspective and Fig. 2 a side sectional view. On the driving shaft, within the cylinder, is secured the hub of a wheel containing a series of four pistons fitted to slide in the rim of the wheel, the opposite pistons being connected in pairs at their inner ends by a slotted frame through which the shaft passes, so that the pistons have free radial movement, one moving inward as the other moves outward, and vice versa. The outer ends of the pistons engage the inner surface of part of the cylinder and part of an abutment in the cylinder, an inverted plan view of which is shown in Fig. 3. The abutment is preferably made in two parts, bolted at their outer ends to the cylinder, and connected with each other at their inner ends by bolts and intervening packing strip, and the abutment serves to press an outermost piston inward, so that its opposite mate slides outward into contact with the peripheral inner surface of the cylinder. In the abutment are two openings into which lead four ports opening into a steam chest containing a slide valve having a single port adapted to connect with the two inner ports, the side ports connecting with compartments from which lead the exhaust pipes. The valve stem of the slide valve is pivotally connected with a lever adapted to be locked in any desired position on a segmental arm. As shown in Fig. 2, the slide valve port admits steam through only one of the live steam ports of the cylinder, and the exhaust takes place through the exhaust port at the right, but when the engine is reversed, by swinging the lever outward, the



MORSE'S ROTARY ENGINE.


ports and open the other, and the exhaust then takes base piece are adapted to support a plate-containing place through the exhaust port at the left.

IMPROVED CROSS-CUTTING SAW.

The cross-cutting sawing machine which we illustrate on this page, from Engineering, has been constructed by Messrs. F. W. Reynolds & Co., Southwark, London, S. E. As will be seen, it is belt-driven, and can accordingly be worked by any portable engine, thus allowing trees to be cut to length in the forest in which cess of M. E. J. Marey, of the Institute of France. He they are felled. The saw is fixed at one end of a crosshead working in guides. This cross-head is driven by ated, either by a solar ray, or by an electric arc light, a connecting rod which couples it to a disk crank as or a magnesium light. shown. The saw is long, and when driven at the rate timber while it is being cut is steadied by a dog, coupling it to the framework of the machine.

A READILY ADJUSTABLE CAMERA STAND.

The illustration represents a metal telescopic stand, which can be readily knocked down to be shipped, and the only tool needed in setting it up is a hand wrench. It has been patented by Mr. John H. Green, of No. 604 Pine Street, Ishpeming, Mich. The trian-



GREEN'S CAMERA STAND

gular base piece has three permanent legs, two of them having casters to facilitate moving the stand, while a socket is provided in which may be inserted another leg having a caster, as shown in dotted lines in Fig. 1. Tubular standards near each corner of the slide valve is shifted to close one of the live steam | base piece are adapted to receive depending guide


> rods whose upper ends are affixed to a carrier plate, a bottom plan view of which is shown in Fig. 2. Centrally in the base piece is vertically supported a coarse screw cut rod adapted to be rotated by a crank and bevel gear and pinion, the screw engaging a nut in a guide tube centrally dependent from the carrier plate, whereby, on turning the crank, the carrier will be raised and lowered, a pivoted locking arm being swung into engagement with the bevel gear when the carrier has been raised to the required height, and is to be locked in fixed position. A leaf with ledges or flanges on three sides. and adapted to support the camera case, is hinged on the upper surface of the carrier plate, the leaf being raised as desired, at the edge opposite the hinges, by means of an adjusting screw having a crank handle. As will be seen, with this improvement, the camera may be quickly raised or lowered, as necessary to suit the height of the person or object to be photographed, and the case or lens readily adjusted to any desired degree of inclination. Frame pieces on the

box, as indicated in dotted lines in Fig. 1, while the operator is adjusting the camera.

Photographing the Vibrations of Tall Buildings.

Professor Steiner, of Prague, has perfected a method of accurately measuring bridge and floor vibrations by the aid of photography. His process is a delicate one, and is an application of the chrono-photographic prouses little glass balls, and these are strongly illumin-

These balls give upon a photographic negative a of 150 double strokes per second, will cut through a log clear and well-defined point. To register vibrations 4 ft. in diameter in from 7 to 8 minutes. It cuts on the one of these glass balls is fixed at the point to be examreturn stroke only, and the feed is given by the worm ined, and the photographic apparatus is then so set up and sector shown behind it in our engraving. The that the image of the ball falls on the right edge of the plate. The plate is exposed at the moment the movement commences, and at the same time the camera



IMPROVED CROSS-CUTTING SAW.

is turned from right to left on a pivot. The negative then shows an undulating line which is the vibrations of the ball point in amplitude and duration.


To obtain a scale with which to read this undulating line, a second ball is suspended to a fixed point, to which is given a known rate of oscillation. The position of these two balls is such that their images coincide in a state of rest, and a comparison of the trace of the second ball as printed upon the line of the first on a negative gives the number of vibrations of the latter in a given time.

It is possible then to place near the first ball a fixed scale brilliantly illuminated like the ball itself, and as this scale appears on the negative the amplitude of the oscillations can be measured at a glance. The measurements may be made either directly upon the print or from an enlargement made in the usual manner. To avoid the practical difficulty of making the images of the two balls coincide at the beginning of the operation, Professor Steiner says a pendulum may be made to oscillate before the source of illumination of the ball.

The ball of this pendulum will pass before the light at regular and determined intervals and the undulating line on the negative will be broken at distances corresponding to the duration of an oscillation of the pendulum. It is not important that the camera turns upon its axis with a uniform motion, and the speed of turning is likewise of little importance. The relations of the curves traced by the two balls will always remain the same. It is suggested that an apparatus of this kind would be useful in studying the vibrations of the floors of buildings resting for some years on iron beams, especially when these floors are submitted to the rhythmic shock of dancing.—Le Genie Civil.

AN EXTENSIBLE ELECTRIC LIGHT SUPPORT.

This improvement, patented by Mr. Alvin Rivenburgh, of Greenfield, Iowa, consists of a tube containing strips of conductive metal connected with the wires of the house circuit, a tube of insulating material sliding therein, and having contact springs contacting with conductors leading to the lamps through the sliding tube. Fig. 1 shows the electrolier complete, Fig. 2 being a transverse section, and Fig. 3 the top portion of the sliding tube. The hole in the main tube is preferably rectangular, and the metallic strips in its opposite sides are flat. The springs contacting with the



RIVENBURGH'S ELECTROLIER.


strips, on the upper end of the sliding tube, are insulated from each other and connected with the wires extending down the inner tube and leading to the lamps. Additional strips of insulation are inserted in the walls of the main tube to prevent the springing of the metallic strips, and, to hold the sliding tube in any desired position, a spring and a set screw which may be made to bear upon it are arranged in the side of the main tube.

Artificial Diamonds.

At the Academy of Sciences, M. Moi cently that, in continuing his researches on the synthesis of the diamond by means of the electric furnace, he has just obtained two compounds well worthy of attention. These bodies are silicide of carbon and boride of carbon. They are of excessive hardness, and cut rubies, steel or diamonds. M. Berthelot asked M. Moissan if in the researches made previous to his own on the subject of artificial diamonds, chemists had not sometimes mistaken for diamonds very dense compounds similar to those to which reference had just been made. M. Moissan replied that he believed errors of the kind might easily occur when analysts are not exactly acquainted with all the characteristics of diamonds. By only bearing in mind their density and property of cutting all other gems, errors may frequently have been made. But, being at present aware of the characteristic of diamonds to burn in oxygen, and to produce four times their weight of carbonic acid, it is now difficult to confound them with any other body.

A COIN HOLDING AND DELIVERING DEVICE.

A convenient means for carrying assorted pieces of money, and delivering the coins one by one as required, is shown in the picture, the device being adapted for suspension upon the person by means of a strap, or to be fixed in position for store use. The improvement has been patented by Mr. Ernest Berrini, of Seattle, Wash. The case has a forwardly inclined, hopper-like bottom, with an outwardly swinging door, an upwardly extending key or lever, by which the



BERRINI'S COIN HOLDER AND CHANGE MAKER.

door may be opened, terminating in a finger piece, the key being normally pressed outward by a spring, which and dispatch. also holds the door closed. In the removable cover of the case are slots, through which coins may be passed to the coin tubes, which are removable, and any desired number of tubes may be used. Each tube has a vertical slot on one side, through which the coin may be seen when the tube is removed, and at the side of the slot is a graduated scale, by means of which the asking for help actuated a bell and a clockwork that amount of money in the tube may be determined gave a signal at the engine house along with the numwithout counting. Beneath each tube is a slide moving horizontally between two base plates, each slide

tube, so that the bottom one of the coins placed in the tube will drop into and occupy the hole in the slide and lie flatwise on the lower base plate. Each slide is normally pressed back beneath the tube by a spring, but when a slide is moved forward by pressing upon the key connected with it, it carries with it a coin, which is dropped into the hopper, from which it may be removed by pressing upon the lower finger piece. Upon a plate at one side of the tubes are fulcrumed tilting keys connected with the slides, and whose upper ends are bent outward through a slot in the case, where they terminate in finger pieces, which should be appropriately marked to indicate the denomination of the coin in the tube with which they are respectively connected. When the device is arranged for use in a store, a bell crank adapted to sound a gong is connected with the key by which the door in the hopper is opened, thus giving notice when the door is opened or any money is withdrawn.

Ebonite Packing Rings.

The pistons of the high pressure air compressors of the pneumatic tramway of Bern are packed with ebonite rings, which, like cast iron rings, fit in grooves, and are pressed against the cylinder sides by a double brass spring. Pistons thus packed are said to be tight, to last from three to four months, and to be cheap, and there is no wear of the cylinder sides.

A QUICK AND SURE CHICKEN BEHEADER.

The illustration shows a device for severing the head from the body of a chicken by simply pulling a trigger, without torturing the chicken or trying the nerves of the sensitive. The improvement has been patented by Mr. J. C. Denham, editor of the Journal of Agriculture, 1120 Pine Street, St. Louis, Mo. The barrel of the implement incases a main spring, and at its rear end is clamped by a breech block having upwardly extending flanges, forming guides for the knife, the flanges being recessed in the center to afford space for placing the neck of the chicken, and the beheading knife sliding across this space between the flanges. The knife is inclined, and its lower end slides in a slot in the top of the barrel, where it is secured to a sliding plunger, to which one end of the main spring is attached, the other end of the spring being secured to the barrel. In the front end of the barrel is a cushion, against which the extended shank of the plunger strikes, absorbing shock and limiting the forward movement of the plunger and knife. The plunger and knife are pulled back against the tension of the spring by handles on the sides of the plunger, the handles projecting through side slots in the breech block and barrel. A notch in the bottom of the plunger receives a pawl on the front end of a curved trigger, by which the knife and plunger are held in a rearmost position when the device is to be used. A depending hook or flange on the front end of the barrel may be hooked upon some object to facilitate pulling back the plunger, or to steady the implement when it is used. When the neck of the chicken is placed in the space provided therefor, and the trigger is pulled, the plunger is instantly released and the knife drawn rapidly forward, the cut being effected with certainty, neatness,

NEW FIRE ALARMS.

A few years ago we described the fire alarms that were being put in service in the streets of Paris. It was a question of an alarm upon a column, due to Mr. Petit, and in which a button pressed by a person ber of the alarm brought into play. While offering decided advantages, this system was defective in some having a hole of the same diameter as the bore of the points. The firemen always had to proceed to the removed, since it gives rise to mistakes. Let us strike

alarm whence the signal came in order to ask exactly where the fire was, and they did not know its nature.

So, while installing the Petit apparatus, the fire department, and particularly its eminent engineers, Commandant Krebs and Captain Cordier, set about to find something better. The ideal was to be able to permit the public to telephone to the engine houses all the details of the location, extent and nature of the fire. Unfortunately, the practice of telephony is still unfamiliar to many persons, and consequently what was necessary was an absolutely automatic apparatus that would attract the attention of the station by a bell, making known to the person calling that the indications given were understood. A very ingenious apparatus, due to Mr. Digeon, has been under trial for some time,




DENHAM'S CHICKEN BEHEADER.

and, having proved successful, has been rapidly put in service in a large number of quarters.

As to external aspect, this new apparatus differs but little from the Petit system. Like it, it comprises a square box painted red, mounted upon a column in the shape of a lamp post. The alarm and telephone, inclosed in the box, communicate, through wires running to the interior of the column, with two cables coming from the central station through the sewers. Let us walk around the apparatus: Here is the door, into which is set a small glass. At the top of the door we read: "In case of fire, break the glass and then cry out distinctly in the mouthpiece of the telephone the nature of the fire, the street, and the number" (Figs. 1 and 2). The normal type of alarm is provided with a small hammer like a door knocker, which permits of effecting the breakage of the glass, but this has been

> hard, as another inscription tells us to, and, according also to these same instructions, the door will open and reveal the mouthpiece of the telephone placed in the interior. This opening, in fact, reveals itself to us at the bottom of the box, surrounded by the inscription in exergue: "Mouthpiece of the telephone." The directions are intelligently multiplied throughout the apparatus, and the most excited person cannot fail to see them. When the door opens, a ringing occurs that attracts the attention of passers-by and points out jokers. If we take a look at the enameled iron plate at the bottom of the box, we see that, as soon as the ringing ceases, we must shout in the telephone the fire that it is necessary to fight, and repeat this information until a roaring sound is heard, and which signifies that the firemen have started. After following these instructions to the letter, we can leave the apparatus, whose door re mains persistently open. There is nothing more simple than all this, even for a child.

When a person breaks the glass he bears at the same time upon a metallic plate that swings upon a horizontal hinge above, and this motion disengages $\,$ the bolt of the door, which opens through the pressure of three springs. A very simple play of levers frees the alarm bell, which is analogous to that of the old apparatus; but, at the same instant, this opening of the door sets in motion








Fig. 2.-MANEUVER OF THE APPARATUS.




Fig. 3.-RECEIVING APPARATUS IN AN ENGINE HOUSE,

the automatic transmitter of the indications of the letter of the alarm and of the name by which it is recognized. This transmitter, which is not very complicated, comprises, in the first place, a cam wheel carrying three times upon its circumference, in Morse characters, the indicating letter, and secondly, a motive weight whose card is wound around the axis of the wheel, and causes it to make an entire revolution when the door opens. The play of a lever is controlled by the cams. At rest this lever communicates with the ground through a movable arm and a special spring. Every passage of a cam lifts a tappet and brings the lever in contact with a special screw for a greater or less length of time, according as it is a question of a dot or a dash. The circuit is completed by the earth, and a Morse receiver located at the engine house inscribes a dot or a dash, and finally the letter (or rather the letter three times) characteristic of the alarm

At the engine house, at the moment at which the first emission of the current occurs, as a consequence of the opening of the door of the box, a bell is heard to ring to call the foreman. At the same time, through an original mechanism that we cannot describe, the Morse receiver is freed automatically, and inscribes the indicative of the calling alarm. After the triple inscription of the letter A (- -), if it is a question of the apparatus of Chateau-des-Rentiers Street, the fireman unhooks his telephone, and this movement interrupts the bell of the alarm. The person who is calling knows then that he can signal the fire in the telephone. At this moment a pin fixed upon the cam wheel has lifted the movable arm, made it tilt, and put the tele phone in circuit. The fireman inscribes the indications given, and when they are very clear he depresses a special lever, introduces the current of the battery upon the line, and, thanks to an interrupter, the telephone of the alarm renders a sound announcing to the person interested that the firemen are apprised (Fig. 3).

All the maneuvers are, therefore, very simple. But the Digeon apparatus has other advantages. It permits notably of keeping the men who have started for the fire in communication with the house, in order to ask for re-enforcement, for example. In fact, every alarm is provided at the side with a door that is opened with a special key and exposes a jaw into which are introduced the wires of a movable telephone and a Morse key to effect calls. We must not omit to mention particularly the movable telephone that is employed in this case. It is due to Commandant Krebs, like the one that is arranged in the alarm. It is a question in both cases of a remarkable magnetic transmitter. The vibrating plate is 98 millimeters in diameter in the stationary apparatus and 77 in the movable. For the latter, it is coupled with the Ader receiver mounted through a slide upon the junction rod.

Let us say further that Mr. Digeon has devised a low priced alarm designed for private houses. It is of wood, is fixed against a wall and is wound up through the opening of the door. Besides, the telephone is accompanied with two receivers that permit of communicating with the engine house. These apparatus can be connected gratuitously with the municipal system.

It is opportune at the moment in which Paris is thus improving its fire service, to remark that Brussels, our closeby neighbor, possesses a very remarkable installation of electric alarms. Forty bureaux of communal administration are subscribers to the telephone system. There are fifty automatic electric fire alarms connected with twelve receiving stations. Twenty-one telegraphic stations connect the police offices and stations with the central office, and at the latter there end eighteen telegraph lines coming from the police stations of the seven faubourgs. It is necessary to add to this thirty-seven microphone and eighteen telephone stations putting the services of the external administration in communication with the City Hall. It will be understood that these are so many stations capable of serving to send out alarms of fire.— $La\ Nature.$


Determining the Densities of Gases.

notice of a convenient modification of the hydrometer by M. Meslans, whose apparatus is described and illustrated in the Comptes Rendus. It consists of two hollow spheres hung to the arms of a balance. Each sphere, which is made of glass, aluminum, or gilt copper, hangs in a separate compartment, the suspending thread being introduced through a hole in the lid. The compartments are inclosed in a box, and surrounded by water in order to keep them at equal temperatures. They are at first filled with air to determine the position of equilibrium. The gas of which the density is to be determined is then introduced through a long tube immersed in the water, and enters one of the compartments, having previously been dried. It is passed through in a slow and continuous stream; and if its density differs from that of air, the made in the Journal). As regards fire-proof doors, necessary to re-establish equilibrium is noted, and the thin sheet iron, between which and the wood there density calculated according to a simple formula. Thus should be a layer of asbestos cloth. Seeing how many regard; a solution of a nickel salt exerts a similar action.

the density of a particular gas is found by a single weighing; and by keeping the current continuous, variation in its density is easily observed. A fairly high accuracy is attainable, depending upon the sensitiveness of the balance and upon the perfection of gauge of the spheres. One important application of the apparatus is that for determining the density and composition of the products of combustion in furnaces. The scale of the balance is graduated so as to show at a glance the percentage of carbonic acid, and hence the degree of efficiency of the furnace in question. This percentage, which is about 21 theoretically, never exceeds 18 in practice, except in gas generators. In a great number of works it varies between 6 and 8. The apparatus is being applied to the study of the various methods of heating. Another application is that by which the presence and percentage of marsh gas is indicated. With spheres of 1 liter capacity and a balance sensitive down to 0.5 milligramme, it was found possible to detect 0.1 per cent of methane in the air of a

A METALLIC BOOKCASE.

The illustration shows a simple form of bookcase or stand adapted to rest upon a bureau, desk or table, and contain a set of works or books of reference in frequent use, the number of volumes being regulated by the length of the stand. The improvement has been patented by Dr. James Stimson, of Watsonville, Cal. In its simplest form the base may be formed of a single piece of metal and struck up with a die, a single piece of metal also forming each of the end pieces. Near each end of the base is a transverse slot, along the outer edge of which the metal is sunk or depressed to form a step or recess, as shown in the small view. The clamping arms forming the end pieces are essentially L-shaped, but with a stepped angular portion connecting the horizontal and vertical portions, the arms



STIMSON'S BOOKCASE.

when not in use folding down upon the base and upon each other, enabling the stand to be compactly folded and stored away. In use, the upper members of the arms are brought to a vertical position, as shown in the large view, the inner members then engaging the under face of the base.

Fire-Resisting Glass.

An interesting test of fire-resisting materials and construction was recently carried out in Berlin, under the auspices of the fire brigade and the insurance companies of the city. The idea of the tests was mooted as far back as 1889; but there was considerable difficulty in arranging for a series of "fires," which were intended to be as "natural" as possible, and yet should not be dangerous. Finally, the municipality gave the experimenters the use of an old warehouse for their purpose; and this building, having been fitted up to represent various types of fire-resisting struct ures, was duly set on fire. Care was taken to subject the exhibits to the temperatures, irregularities of heating, sudden shocks by falling weights or jets of water, A recent number of Nature contained the following etc., which generally occur at conflagrations; and it was found possible to take fairly exact observations method of determining the densities of gases, devised | Among the most satisfactory results obtained were with the fire-resisting glass made by Messrs. Siemens, of Dresden. The assessors declare it to be most suitable for any skylight or window necessary in a division between separate risks, as it will resist a temperature of 1,300° C. for half an hour and more; bearing all manner of shocks and strains without suffering appreciable damage. Care is required in fixing this glass, however, as the iron frames generally used for the purpose buckle under heat, and show, between the glass and iron, openings through which flame can pass. Some of the so-called fireproof floors made of iron girders and con crete came to speedy grief in these tests; while iron and brick floors stood very well, as did the "Monier" construction (as to which reference has been already equilibrium of the balance is disturbed. The weight nothing stood better than double oak covered with

warehouse fires are propagated through windows, the assessors attach great importance to their demonstration of the capability of Siemens glass for withstanding flame.

No Oxygen in the Sun.

At the recent annual meeting of the five academies in Paris, M. Janssen read a paper on his observations at Mont Blanc Observatory on September 14 and 15. as to the absence of oxygen in the solar atmosphere. This discovery, he said, revealed a fresh harmony in the constitution of the universe.

"We already knew the chief features of the constitution of the sun and the admirable conditions realized for insuring both the abundance and the durability of the radiation diffused by it over the planets surrounding it. We knew that this incandescent surface of such a slight thickness which surrounds the sun and in which resides this virtue of radiation renews itself by reserves of heat drawn by it from the central mass. We also knew that this radiating surface is protected from contact with the icy celestial space by several gaseous envelopes. Among these envelopes or atmo $spheres \, the \, uppermost \, and \, doubtless \, most \, effective \, as \, to \,$ protection is the so-called corona, which in total eclipses produces the splendid phenomenon of the 'glories' and of the crown. This atmosphere is mainly composed of hydrogen, the lightest and most transparent of known gases. The chief function of radiation, the very purpose of the central orb, is thus insured by this transparent and protecting atmosphere. But we now see that by a not less admirable arrangement the body which might some day jeopardize this function has been carefully excluded. Thus science as it advances constantly reveals to us new laws and harmonies in the constitution of the universe."

Prizes for Electrical Inventors.

It can hardly be doubted, says the *Electrical Review*, that there will be a good number of American competitors for some of the following named prizes which are offered by the French Society. A prize of \$2,280 will be made in 1898 for the discovery that is most useful to French industry. A prize of the same amount is given every three years by the society (the next award will be made in 1895) to the person making the most useful industrial discovery. The Henry Giffard prize of \$1,140 is awarded every six years (the next award will be in 1896) for services of signal value to French industry. The Metzen's prize of \$95 is awarded every three years (the next award will be in 1896) to the discoverer of a valuable chemical or physical application in electricity, ballistics or hygiene. The special prizes for 1894 are: \$380 for a motor whose weight is not less than 50 kilogrammes per horse power; a prize of \$570 for an apparatus that shall decrease materially the smoke of furnaces, especially those under boilers; a prize of \$190 for a heavy oil engine; a prize of \$570 for a steam engine consuming at the maximum speed, under average load, seven kilogrammes of steam per horse power per hour; a prize of \$570 for the discovery of a substance that can be substituted completely for guttapercha in at least one of its applications, or for work that will continue to develop the production or improve the cultivation of the gum. The following prizes are to be awarded in 1895: A prize of \$380 for a small motor designed for use in a shop located in a house; a prize of \$380 for the preparation industrially of ozone and means for its application; a prize of \$380 for an apparatus or a process which shall make it possible to measure or determine the insulation of the different parts of an electric installation while the current is on; a prize of \$570 for investigations which shall contribute to the discovery and application of the best means in domestic and general product for the purification of drinking water. Competitors must submit their proofs by the 31st of the December preceding the year on which the prize will be awarded.

Hydrogen.

An interesting example of the capacity of some of the oldest and most hackneyed chemical reactions for improvement is supplied by a communication of Mr. John Ball, of the Royal College of Science, South Kensington, to the Chemical News, upon the prepara tion of hydrogen by the ordinary zinc and acid laboratory apparatus. Mr. Ball states that he has recently observed that, by the addition of a few drops of a solution of nitrate of cobalt to the acid and zinc, the rate of evolution of hydrogen is enormously accelerated, especially at the beginning of the reaction. The effect is the same with either hydrochloric or sulphuric acid; and a couple of drops of solution of nitrate of cobalt will suffice for a large quantity of acid. The action does not seem to have been noticed before; and it should be useful in the rapid preparation of hydrogen in the laboratory. Most, if not all, of the cobalt salt is quite unaltered. There appears to be a very thin film of cobalt deposited on the zinc, which probably acts with the zinc as a voltaic couple: but the amount of cobalt deposited appears to be too small to weigh. There is no particular virtue in the cobalt in this

ELECTRIC LAUNCHES AT THE COLUMBIAN EXPOSITION.

(Continued from first page.)

boat. All the electrical parts except the switch are protected, so that there is no possible danger of shock, and there is no report at the Exposition of any mishap of this kind. The boats are operated by a heavy current at low pressure, so that there could be no harm even were it possible for a full charge to be received. No boat could be much more easily managed and be more free from possibilities of mishaps, such as explosion or escape of steam or oil. In addition, the launches are clean and free from all noise, smoke, ashes, and other disagreeable features.

The greatest test the launches had during the period of the Exposition was on Chicago day, when 622 trips, each trip of three miles, were made by the fifty boats. Six of these boats averaged fifty miles each, while twenty of them averaged over forty miles, carrying on each trip about forty people. These long runs did not by any means consume the stored energy, as an experimental test made some time ago on one boat at a speed of a little over five miles an hour demonstrated that it had a storage capacity of making ninety miles at that speed on one charging. Very few accidents have occurred to any of the launches, and nine out of ten have been caused by the propeller becoming entangled in wires or other debris in the bottom of the lagoons, and thus springing the shaft or bending the propeller blades. One bunch of wire is shown in the office of the company that was gathered up by a propeller that would require nearly a bushel basket to contain it. The batteries have proved highly efficient. No embarrassing or costly breakdowns have occurred, and during the entire period of the Exposition there have been only about 14 per cent of renewals in spite of the steady and uninterrupted work that the launches have been called upon to perform.

An economic feature of the electric launch that has been demonstrated at the Exposition is the fact that the instant the motor stops the expenditure of energy ceases, and after a boat has lain idle for many days its maximum power is to be had upon a moment's notice and without any waiting to fire up and get up steam. By placing the motor and storage batteries low down, they aid to properly ballast the boat, and at the same time they provide nearly 50 per cent more space to accommodate passengers than is to be had on the ordinary steam or naphtha launch of

The question of a proper kind of signal came up for consideration before the Exposition opened. At first an electric whistle was used which was a French invention. This was a device in which a diaphragm was caused to vibrate by electric energy, but it was more expensive and did not give as much volume of sound as the simple air whistle operated by a hand pump, which has been used on each one of the boats of the fleet during the Exposition.

be congratulated upon the success these launches have attained. They have been one of the most attractive features at the Exposition, and they have more than fulfilled the expectations of them. The contrast between these launches and the gondolas, which have also plied on the lagoons, was so marked that a syndicate of Italians purchased a launch in September and forwarded it to Venice with a view to introducing these boats in the "City of the Doges." Such an innovation is startling, and yet this syndicate is so certain of its proving a success that it has taken an option of twenty-five launches of the World's Fair fleet, with the privilege of purchasing more if it

Under ordinary circumstances, boats finished as beautifully and equipped as completely as these Exposition boats sell for \$2,700, without extras, but most of this fleet has been disposed of at \$2,000 apiece.

The following extract from the report of the engitober. If it did, it would be still more favorable.

Believing that a concise statement of the actual deep interest to the electrical fraternity, since the by the violence of the reaction, stops up the discharge launches are operated under novel and severe condi- tube, which is the size of a clay pipe stem, Dr. Meslans tions, the writer presents the following data, which was constantly applying his Bunsen to heat the tube. are computed from records carefully kept from the lodine at once combined with the fluorine under exbeginning of this unique business enterprise:

APRIL 13 TO OCTOBER 1, 1893.

Mileage and Passenger Traffic.

Passenger trips of three miles each	47,787
World's Fair special launch trips	6,750
Special trips of regular launches	1,220
Trial trips	270
Experimental trips	180
Total number of trips	56,207
At three miles per trip, total miles	168,621
Average miles per launch to October 1	3,122
The total number of days the 54 electric launches have been	
in service on the lagoons of the World's Fair is	6.594

25'57
14
$37\frac{1}{2}$
54
301,000
464
40
55½c.
43c.
41c.
9c.
1017
1.481/2

When it is understood that already the launches have run on an average four times the number of miles a launch owned by a private individual would ordinarily cover during a regular season, and that, as all who have been connected with this glorious Fair will vouch for, the operating expenses are decidedly heavier than under ordinary circumstances, it will be acknowledged that the cost per launch mile is exceedingly low. Judging from the experience of six months with the fifty-four launches, the writer believes the expense can and will be, in the near future, brought down to as low a figure as three cents per electric launch mile where at least thirty launches are operated under like conditions—less World's Fair extra expenses. Though the electric launches have carried over 801,000 passengers, not a single accident has occurred, and it was exceedingly rare that a boat had to be towed in except through injury to the propeller or shaft by the floating and sunken debris in the lagoons of the World's Fair.

Fluorine.

The "Demonstration of the Preparation and Properties of Fluorine by Moissan's Method," by Mr. Moissan's assistant, Dr. Meslans, was the popular event of the proceedings in the chemical section of the recent meeting of the British Association, and is described by *Engineering* as follows: Some years ago Mr. Moissan isolated fluorine, which so far had baffled all attempts at separation, and in a measure remained a hypothetical element. Dr. Thorpe, of South Kensington, failed in the repetition of these experiments, which were doubted by some chemists. At the request of Professor Emerson Reynolds, Mr. Moissan, regretting his inability to come himself, sent over his assistant with the full plant, which was exhibited. Mr. Meslans contented himself with demonstrating, making brief remarks in French, and converted all doubters, if any were present, into enthusiastic believers. Fluorspar is decomposed in a platinum retort by means of sulphuric acid, and the anhydrous hydro-The Electric Launch and Navigation Company is to fluoric acid, dried and purified, brought into a U-tube for electrolytical decomposition. The vessels and tubes are of platinum; the stoppers of fluorspar. The hydrofluoric acid is an insulator, and resisted all electrolytical attacks until Fremy suggested the addition of a fifth of fluoride of potassium. The U-tube stood in a cooling vessel of about a quart capacity, containing condensed methyl chloride, which reduces the temperature to -23° Cent. As soon as the current of 70 volts and 25 amperes was turned on, minor explosions were heard, and fumes began to issue from the fine platinum tube through which the fluorine was to escape into the air. It did so; and, although it did not appear so vicious as it has been described, soon set the crowded audience coughing and longing for fresh air. Nobody was any the worse for it, however. As the fluorine at once decomposes, with the moisture in the air, into hydrofluoric acid and ozone, these two substances were practically what was smelt and felt; ammonia was passed round instead of eau de Cologne. neer in charge shows that the cost of maintaining an The experiment had to be temporarily interrupted the same rail is turned over and the head put in comelectric launch of average size is less than six cents a after some minutes, as the stock of methyl chloride pression it will bend without fracture. Again, if before mile. The report does not include the month of Oc- gave out; Mr. Meslans had been experimenting the conducting a test, about 1-16 in. of metal is planed off day previous. The low temperature is necessary on account of the high volatility of the hydrofluoric acid. work and operating cost of these launches will be of As, however, some of the potassium salt, carried over plosion: sulphur burned with its well known blue flame; phosphorus as in oxygen; silicon and boron glowed like burning coal; carbon itself would not catch fire. It does so under proper conditions. On the motion of Sir Henry Roscoe, the thanks of the and the head of the rail is as good as the base. association were conveyed to Mr. Moissan by wire. Dr. Thorpe said that Mr. Moissan had been kind enough to examine his apparatus, which he had sent over to Paris; but that he, however, had not been able vet to repeat the experiment. On the request of the president, he gave a summary of the properties of Greely's expedition reached is incorrect. The furthest

to its appearance, even Moissan can hardly speak, as it cannot be brought into transparent vessels, and fumes so badly. It seems to be a greenish-yellowish gas, like chlorine. Its atomic weight Moissan has determined by filling two exactly equal platinum jars with nitrogen, and replacing in the one the nitrogen by fluorine; since the atomic weights of nitrogen (14) and fluorine (19) do not differ much, however, this determination is not very reliable. Mr. Meslans also exhibited one of Moissan's latest products, uranium carbide obtained in his electrical furnace. This is a dull blackish mass, which, when shaken in the stoppered bottle, sparks most energetically; the carbide, or its combustion product, has a peculiar smell.

Freezing Fish.

Science has conquered nature and has demonstrated that to preserve fish it is not necessary to salt them. Freezing is the thing in the future, and Sandusky, Ohio, is the place where the first attempt has been made to carry on the business in a general way. Frozen fish are taking an important place in commerce and in the cuisine, and as the industry becomes more general the demand for salt fish will probably drop off to a great extent.

About three years ago A. J. Stoll, a fish commission dealer in Sandusky, began to experiment with freezing fish, and soon found that the invention of the icemaking machine would be his salvation. Last year he completed his scheme and now he has a plant in full operation, employing twenty-five men and a capacity of freezing and preserving twenty tons of fresh fish each year. In a year Mr. Stoll expects to double the capacity of the plant.

The method used is very simple, yet interesting. The fish are unloaded from the schooners and placed in the dressing vats, where the refuse matter is removed and the fish sorted and graded according to the species. This is only done with the larger fish, but the small ones are not mutilated. The fish are placed in pans made of metal that will not rust, being placed in layers and the pans carried to the cooler. This cooler is a sort of a vault filled with pipes arranged in tiers and compartments like the shelves of a pantry, and made to fit so perfectly that no space is wasted. These pipes are filled with freezing fluid and the temperature is kept at zero. From here, after freezing twenty-four hours, the pans are removed to the preserving vaults, where they are placed on pipes arranged as in the first mentioned vaults.

Just step in once, after standing around in the hot sun of a July day. Of course overcoats are neglected in the summer, but in two minutes you discover your. self in the atmosphere of the Arctic regions, and, glancing at a thermometer, you will see the mercury registered at eighteen below zero. A massive door is opened and before your eyes is a big stack of block wood—no things are what they seem, for you find the wood very cold. It is the fish that will be distributed to your market man, perhaps many years hence, and the meat is so frozen that when emptied from the pans the fish appear like chunks of wood, and are so solid that they must be thawed several hours before the fish can be separated.

It has been demonstrated already that flesh kept frozen at such a low degree of temperature will remain perfect for a period of years, and it is believed that the fish may be preserved ten years, and then be turned over to the fish dealer fresh as the day they were caught.

Brine is circulated by the pumps through every foot of the pipes, and returns to the tank for cooling for redistribution in the space of one minute. The Sandusky plant cost \$25,000.—Detroit Journal.

Interesting Rail Tests.

In tests conducted at the Watertown arsenal it has been found that old steel rails when submitted to a bending test in which the head of the rail is put in tension and the base in compression, will invariably fracture, making a clean break across the rail, while if the head of the rail, there will be no fracture, no matter which part of the rail is in tension. But if, in planing this head, care is not taken to remove 1-16 in of metal from the corners as well as the top of the head, the rail will fracture as before. The explanation of the matter is that a thin layer of metal on the head of the rail has been greatly hardened by the contact and pressure from the wheels passing over it, and fractures when put in tension. When once started, the fracture, of course, extends entirely across the rail. If this hard material is removed, the fracture cannot make a start,

WE are indebted to Mr. J. N. Knowlton, manager of the Steam Whaling Company, San Francisco, for the information that the reported sailing of one of the company's vessels to a point further north than the now fairly settled refractory element. It attacks north the company's ship made was between 72° and everything—even the platinum-iridium electrodes. As 73°.

IMPROVEMENTS IN SHAPERS.

Among notable exhibits at the World's Columbian Exposition at Chicago there was an improved shaper, which attracted attention in consequence of the enormous chips of metal which it cut from iron and steel. To the casual observer the machine does not appear to be different from the ordinary shaper, but to the mechanic who is used to tools of this kind it is a matter of surprise to see a shaper remove from a solid block of iron such chips as are shown in Fig. 1. This engraving is a truthful representation of the ma-

chine doing actual work; and Figs. 2 and 3 show respectively a very wide but comparatively thin chip and a narrower and much thicker chip, the first being one-sixteenth of an inch thick and one and three-fourths inch wide, the other being oneeighth of an inch thick and one inch wide.

The explanation lies in the fact that the tool does its work with a drawing cut. This insures great steadiness in the moving bar of the cutter, and as the tool holder is arranged, it also secures great rigidity and firmness in the holding of the tool without the necessity of heavy clamping devices, as the tool practically clamps itself as it is drawn forward. The up and down and cross feeds are not materially different from those of other shapers, and the cutting bar is moved by reversible gearing, with a quick outward movement and a slow return. By making use of the drawing cut instead of pushing the tool, less pressure is required in clamping the work and all chatter of the tool is avoided.

This machine is made by the Morton Manufacturing Company, of Muskegon Heights,

Michigan, who also make other machines on the same principle.

The Loss of H. M. S. Victoria.


The vessels upon which we now rely for bearing the brunt of the fighting in a future naval war, which are styled by the imposing title of battleships, may, it moment by a blow which is much less heavy than an

against gun-fire, but the structure upon which this costly armor is placed is apparently so frail that a mere touch suffices to send the whole mass to the bot-

We have always understood that the division of a warship into separate watertight compartments was so minute and complete that she would be safe against sinking, even if many of these were damaged. The Victoria could, however, hardly have been sunk quicker if there had been no division at all into what are called watertight compartments. Sir E. J. Reed, whose knowledge and capability of judging cannot be seriously questioned, named twelve other battleships in the House of Commons that he asserted would have the same fate under similar circumstances. We know of nothing which gives reasonable ground for supposing that Sir Edward Reed is wrong; but, whether he be right or wrong, it is not only the duty, but the interest, of the Admiralty to have this grave question inquired into by an independent and im partial committee of qualified judges. We would like to know why the numerous watertight compartments of the Victoria failed so completely to serve the purpose for which they were devised, i. e., to keep the ship from sinking when injured below water. Was it because, as has been often stated, her stability is so small that the filling of one or two of


these compartments is sufficient to overcome the float- order to make existing ships satisfactory in these reing power of the remainder? Or was it a question spects, if they be not satisfactory now, and would be of watertight doors being left open, or not acting when in danger of meeting the fate of the Victoria under like attempts were made to close them? Captain Bourke's circumstances. - Engineering. evidence before the court-martial shows that all was tight in the engine room and boiler rooms, and the room bulkhead. It appears, therefore, that the watertight doors were very soon closed, although they may have been open before the fatal blow was given.

Lord Armstrong stated in his recent speech at Elswick that the loss of such a ship "calls for very grave reflection as to the policy of devoting so large a proportion of our naval expenditure to the construction of with Lord Armstrong upon this point, if it be the fact the gun to fire over the mountain from Pre St.-Didier. that our battleships are in reality so frail and unreliable as the sinking of the Victoria would indicate. It would be absurd to glory in their "might" if it rested



HEAD OF THE MORTON SHAPER SHOWING HEAVY CUT.

constructed in fact; whether other of our principal of its prevention, the fact that very few people applied appears—at least some of them—be sunk almost in a battleships are in the same case with the Victoria; for disinfection of material after deathfrom this cause, enemy might be expected to give in action. Enormous and were capable of being readily closed from a safe such precautions in the case of the various fevers.



THE MORTON DRAWING CUT SHAPER.

A COAST gun built by Krupp, when being tested at

of 2,099 ft. It is estimated that the projectile reached an altitude of 21,456 ft., and its flight occupied 70°2 seconds. The Krupps have had a drawing made showing the flight of the projectile relatively to Mont Blanc, those mighty vessels called battleships." We agree from which it is evident that it would be possible for

Tuberculosis and its Prevention.

Dr. Anderson, the medical officer of health of Dunupon such an insecure basis as that. There is little, dee, delivered an interesting address recently, so says however, at present upon which to form a definite the Lancet, with the view of quickening public interest

on this important topic. After referring to the history of our knowledge of the specific germ and of the manner of its propagation, he mentioned the fact that tuberculosis had been calculated to cause one-seventh of the total mortality of the human race. It was remarkable that, notwithstanding this important fact, little practical interest had been taken in the matter by the state, local authorities, or individuals. An assumed theory of its unavoidable nature seemed to lie at the root of this baneful fatalism. Dr. Anderson main: tained that all tubercle bacilli were derived from predecessors of the same character, and pointed out the facility with which this bacillus adhered to moist surfaces and propagated itself under insanitary conditions such as prevailed in the overcrowded houses of the poor. He also mentioned the opinion, held by bacteriologists, that the expired breath of those suffering from the disease was comparatively innocuous, while their sputum swarmed with bacilli, and on evaporation and desiccation was apt to become a fruitful source of infection. Hence the paramount necessity for a syste-

opinion upon the question, and no sign of the neces- matic destruction of the sputum, disinfection of apartsary information being furnished. We desire to know | ments occupied by those suffering from tuberculosis whether it be not practicable to build a battleship in and disinfection or destruction of articles of clothing watertight compartments so that no single blowwould likely to retain the germ. Referring to the large morsend her to the bottom; whether the Victoria was not tality from tuberculous disease, Dr. Anderson menbelieved to be so constructed, and whether she was so tioned, as an instance of public apathy in the matter whether the watertight doors were thoroughly efficient, in comparison with the numbers of those who took sums are spent in providing armor to protect them position above water; and what is the best to be done in Passing to the subject of the disease in cattle, he

pointed out the large mortality among these animals from this cause and also the relation of milk supply to infant mortality from tuberculosis. The proportion of deaths from this cause in children under five years of age in Dundee was found to be 1 in 11. All these facts pointed to the necessity for the householder to safeguard his own interests. Dr. Anderson concluded his instructive address by mentioning in detail the preventive and disinfectant measures necessary to secure the highest possible immunity from the

Our Birds are Leaving Us.

In Harper's Susan Fenimore Cooper sings a gentle dirge over the departure of the birds from our forests and hedgerows. Selecting a typical region in the Northern Alleghanies, she shows how the birds have gradually become silent, first the great white pelican on the mountain lake, then the beautiful wild swan, and finally even the myriads of wild pigeons. This iastoira is one of the most curious ex amples of the sudden destructive blows to whole species that man's presence can give. Seemingly one of the most numerous and prolific of birds—flocks estimated to be 240 miles long have been seen in this century—it is now practically a thing of the past.

And as for the songsters, and the smaller feathered tribe:

"The friendly red-breasted robins, the beautiful bluebirds, the gay, musical goldfinches, those charming song birds the wrens, the gorgeous orioles, the purple finches, the dainty greenlets, the pretty cedar birds, the merry gold crests, and their cousins the rubycrowns, those dainty sprites the humming birdswater was all confined to the fore side of the boiler the Meppen proving grounds recently, threw the these and other bird families never failed in past years projectile 65,616 ft., or nearly 13 miles, the gun having to bring joy with them to our lawns and meadows. an elevation of 44 deg. The projectile weighed 474 lb.; Many of them are now rare visitors. The sturdy robins the charge of powder 253 lb.; giving an initial velocity are much less numerous than they were formerly."

FOUR HUNDRED HORSE POWER MILL ENGINE.


The engines which we illustrate below are of the inverted marine type, and are designed for driving ing at them for any length of time; but the worst discement and other mills, shop machinery, and for general land purposes. The chief advantages claimed for this type of engine over the ordinary horizontal land | may be made from any stereoscopic negatives, are engine are economy in floor space occupied and greater balance of working parts. In the engine illustrated, this latter point has been especially studied, the cranks nary way with the naked eyes, they appear as a being [placed opposite to each other, instead of at | blurred, out-of-focus picture, in which the subject may | its dynamo capacity to 4,000 horse power, and some right angles, as usual. The engines are designed to be but barely distinguishable, for they are thrown develop four hundred horse power, the cylinders being from lanterns with prisms in front of the objectives 19 in. and 33 in. in diameter by 48 in. stroke. The fly-

use. The throwing of the images on the screen side by side necessitated great straining of the eyes in lookadvantage is the loss of light through the colored glasses. In Anderton's lantern the two images, which thrown upon the same part of the screen, so that there is no trouble in seeing them. Looked at in the ordito polarize the light, and as the slides are the two announces that the price from January next will be 45

perfectly startling. The glass used by Mr. Anderton for viewing the images is like a very short opera glass on a handle, and with two small prisms suitable for his purpose cannot be a very expensive instrument.-Practical Photographer.

Reduction in the Price of Aluminum.

The Aluminum-Industrie-Actien-Gesellschaft, Neuhausen, in Switzerland, owing to the increase of improvements in the processes employed, enabling it to increase largely the production of aluminum, wheel is 16 ft. in diameter, and weighs 12 tons. The halves of a stereoscopic picture they could not be made cents per pound. It must be remembered that, owing



FOUR HUNDRED HORSE POWER COMPOUND MILL ENGINE.

makers are Messrs. Ross & Duncan, Whitefield Works, | to coincide, even if it were desirable. The prism used | to the low specific gravity of aluminum, if equal bulks, Govan, Glasgow. We are indebted to Engineering to polarize the light is placed horizontally in one lanfor our illustration and the foregoing particulars.

A Stereoscopic Lantern.

Anderton's stereoscopic lantern, recently shown at the Pall Mall Exhibition, and demonstrated at one of the technical meetings of the P. S. G. B., is the most horizontally or vertically, one image is plainly seen notable novelty that the lantern world has seen for many years. It has long been possible, in an experimental way, to show lantern pictures in stereoscopic relief by throwing the images from two lanterns through red and blue glasses respectively, and viewing them through opera glasses or spectacles in which image from the two lanterns seeming about as well the glasses are red and blue. This system has one or two disadvantages that have prevented its practical them. The stereoscopic effect, from good slides, is land has come up to that scratch.

tern and vertically in the other. Practically either image is only visible when viewed by the naked eyes, or through a prism held parallel to the original prism through which it is thrown. Thus, when one looks at the blurred image on the screen through a prism held and the other is practically invisible, and when a glass is used containing a horizontal prism for one eye and a vertical prism for the other, each eye sees one image only, and the stereoscopic effect is given by the blending of the two. The illumination is very good, the lighted as the ordinary projection from either one of.

not weights, of the different metals are taken, this price is really lower than that of copper as recently as 1890, and is less than that of tin at the present time. At present, 75 cents a pound is the ruling price for aluminum.

IT is now pretty well understood that the contemplated race between the champion English and American locomotives, that were exhibited at Chicago, will not take place. Our British cousins decline to join in a contest in which they know, beforehand, they would come out second best. No. 999, of the N. Y. Central, is said to have made the rate of 1121/2 miles per hour, and no locomotive as yet produced in Eng-

The La Grange Dam.

overflow dam in the world.

It is called the La Grange dam, and is being constructed for the Modesto and Turlock Irrigation Districts. Its location is in the canyon of the Tuolumne River, three miles from the town of La Grange. Work on the project was commenced in June, 1891, and has been prosecuted continuously ever since. A force of 200 men has been employed on the work, the total cost of which will be \$600,000.

The annals of engineering have hitherto recorded as the highest the Vyrnwy dam, which retains the water supply for the city of Liverpool, England. Its height, from base to summit, is 127 feet, but the La Grange will be two feet higher. Other celebrated dams, such as the Bear Valley, in San Bernardino County, and the Sweetwater, near San Diego, are properly known as reservoirs, and the protection of their basins as retaining walls.

The La Grange is being built by R. W. Gorrill, and will be 360 feet long on top, the plan being curved on a radius of 320 feet. Its maximum height above the foundation will be 127 feet 9 inches. The front face of the wall is made to conform to the curve described by the water in overflowing, and to deflect it into the basin in front of the dam.

The dam is built of "cyclopean rubble," and is a model of solidity. Huge rocks, weighing from six to ten tons, were first laid on the bottom. All their projecting pieces were cut off, and a flat but rough surface was prepared for the lower bed. Before being placed in the bottom, all stones, whatever their size, were scrubbed, and subjected to the action of numerous jets of water under pressure of seventy-five feet.

The process of construction was as follows:

"A level bed was first prepared in the rock and cov ered with a two-inch layer of cement mortar, which was beaten to free it of air. A large stone was then lowered into position by a steam crane, and was beaten down into the mortar by blows from heavy handmauls. Other large stones were similarly placed, but so as not to touch each other. The spaces left between them were filled with concrete, which was thrust into the narrow spaces with tampers.

"The work within the reach of each crane was brought up from six to eight feet before the crane was moved. In each course the immense stones were laid so as to bind with those in the course below. No horizontal joints passed through the wall, as the top of each course was left with projecting stones and hollows, which permit it to be well bound with the next course. To make the back face thoroughly watertight, the vertical joints were filled with mortar alone and into this broken stone was forced."

The La Grange dam will distribute water over a territory embracing 276,000 acres. The Turlock district comprises about 198,000 and the Modesto district 78,000 acres. The water will flow over the dam into two ditches. One will be 30 miles long and 100 feet wide, the other 28 miles long and 80 feet wide. The waters of the Tuolumne River will be banked up by the dam in the rocky canyon. A lake will thus be formed four miles long and a half mile wide. An idea of the solidity of the dam may be gathered from the fact that at its base it is 117 feet 9 inches thick, and that of solid stone, forming an indestructible barrier to the lake of water behind.—Pacific Lumberman.


Rapid Building.

Chicago has made a new record for rapid building operations by the manner in which work has been pushed on the New York Life Insurance Company's building, now in course of erection at La Salle and Monroe Streets. This building is of the so-called Chicago construction. On July 19 excavation was commenced, and as there had been no cellar under the structure which had previously occupied the site and been torn down, the work was from the surface. In nine days the curb wall was completed. On August 17 the entire foundation had been laid, and on the day following the first iron column was set in the Thirty-six working days thereafter—Sep the days had been lost in waiting for delayed iron. On October 5, besides the skeleton framework, two stories of granite and three of terra cotta exterior walls had been laid, four floor arches of fireproofing had been set in place, the entire system of steam mains throughout the building set, and the basement floor laid in concrete. Ten days were consumed waiting for cut stone. Thus in ten weeks and one day—sixty-one working days-the entire framework for a building twelve stories in height and covering an area of 80 by 140 feet had been set, and a week later five stories of outer wall, composed of granite and terra cotta, had been laid. For four weeks double relays of men were emremainder of the time eight hours constituted a day's ninety-five working days from the day on which the letters.—Philadelphia Ledger.

first dirt was removed from the site. It is expected to Stanislaus County, Cal., will soon have the highest have the structure ready for occupancy by February 1, 1894.

A SIMPLE GAS METER CONNECTION.

To save time in setting meters, and afford an efficient and inexpensive connection with the street service pipe and also with the distributing gas pipes in a house, is the design of this improvement, which has been patented by Mr. Albert H. Gindele, of No. 228 Second Street, Jersey City, N. J. On the end of the lead pipe to be connected to a meter is placed an exteriorly threaded sleeve, and the end of the pipe is then upset to form a flange against which the sleeve abuts. A cylindrical junction nut, preferably of brass, screws upon the threaded sleeve, and has a hub-like extension which bears against the flange and also screws upon a thimble screwing into the bore of the lead pipe, the




GINDELE'S GAS METER CONNECTION.

thread of the thimble producing a mating thread in the soft metal of the pipe. The thimble also has an external flange which is engaged by and has gas-tight contact with an inwardly radial flange on a union nut of the usual form, the nut screwing upon the end portion of the hollow meter post. The improvement is designed to afford a simple and reliable connection and dispense with solder joints.

SECURING PROPELLER BLADES TO THE HUB.

The illustration represents an improved means of securing propeller blades to the hub, recently patented by Mr. Martin Davies, Jersey City, N. J.

According to this improvement, screw belts are inserted through the hub from the inner side, and then through the bases of the propeller blades, when nuts are applied to their projecting outer ends. Fig. 1 is a view in perspective; Fig. 2 a horizontal section at one side of the hub; and Fig. 3 is a section through the hub and opposing blades, the heads of the bolts being countersunk in the interior of the radially bored hub and arranged to form part of a smooth hub bearing for the propeller shaft. The hub has four faces, each adapted to receive a propeller blade, and having a circular recess in one wall of which is a feather, the base of each blade having a boss entering the recess, and



DAVIES' PROPELLER.

recess to receive the feather. In s entire completion of the iron framework, and five of with great force, whereby the blade is securely clamped and fastened in place, but so that it may be removed with convenience and dispatch. This invention has been practically tested in actual use, and its value has thus been demonstrated.

There is a bill pending in Congress providing for the issuing of postal fractional currency, in denominations of 5, 10, 25 and 50 cents. This is intended to furnish the public with a convenient form of money for transmission through the mails. It is to displace the postal notes, which are to be withdrawn from sale on January 1, 1894. This fractional postal currency would be furnished at its face value and without the formality ployed, sixteen hours being counted a day; for the now necessary to get a postal note. There are branches of business involving small transactions which would work. Taking this into account, the work occupied be sensibly aided by such a currency for inclosure in

A Steam Carriage for Road Use.

C. L. Simonds, of Lynn, Mass., has made a steam carriage for his own use that will make ten miles an hour. The carriage weighs only 400 pounds and can carry two persons at a time. It has the appearance of an ordinary carriage in front, except there are no provisions made for a horse. The wheels are of cycle make and are four in number. The hind wheels are 43 inches and the front wheels are 36 inches, with rubber tires. The boiler and engine set just in the rear of the seat and give the carriage the appearance of a fire engine. The steam generates in what is called a porcupine boiler, which weighs 100 pounds. The steam is made by naphtha flames from three jets. The naphtha is kept in a cylinder, enough to last for seven hours, and there is a water tank that will hold 10 gallons. There is a pump that is automatic in action directly connected with the engine. The steering part consists of a crank wheel on the footboard, so that the engineer can steer and attend to the engine at the same time. The body of the carriage rests on a cradle and three springs. It is easy riding, and allowance has been made for every movement. The shafts are of steel, and can stand all of 1,000 pounds. Mr. Simonds has given the steam carriage a trial already, and it has proved a success. It started off at a ten-mile gait; there was no noise, smoke or trouble whatever.—Springfield Republican.

Photographic Notes.

Photographing upon Fabrics.—Mr. August Villain, a dyer of Aubervilliers, recently communicated to the Societe d'Encouragement the processes that he employs for obtaining photographic prints upon fabrics. He recalled the researches of Messrs. Kopp, Willis, Green, Cross, and Bewan, and the application made by these chemists of alkaline bichromates, chromates of copper and aniline, solution of aniline in benzine, and denitrated primuline. In order to obtain the negatives, the process that has given Mr. Villain the best results consists in sensitizing the fabric with the following mixture:

Water	1,000	parts.
Bichromate of potash	35	"
" ammonia	15	"
Motovanadate of ammonia	5	66

The fabrics impregnated with this solution are dried in the dark at a low temperature, and exposed to the light under a negative. They are afterward thoroughly washed. In this state they have fixed enough mordant to dye the print in baths prepared with the most varied artificial colors.—Annales Industrielles.

Photographing upon Marble.—In order to photograph upon marble there is applied to an unpolished slab of the latter a solution composed of:

Delizine	300	paru
Spirits of turpentine	5 00	"
Asphalt	50	"
Yellow wax	5	"

After the solution is dry an exposure to the sun is made under a negative. The developing is effected with turpentine or benzine. The slab is then thoroughly washed, and those parts of it that are to remain white are covered with an alcoholic solution of gum lac. The slab is then immersed in a tincture of a coloring substance soluble in water.

After a short time the coloring material will have penetrated the pores of the stone, which is then removed from the bath and polished. The effects thus obtained are, it is said, very beautiful.—Annales Industrielles.

The Snow Sheds of the Union Pacific.

A correspondent of the N. Y. Observer says: "With two and sometimes three engines, our heavy train, now divided into two sections, climbed up the giant wall of the Sierra Nevada. We passed through the magnificent scenery of Shady Run, Blue Canyon and Giant and Emigrant Gaps. In running one hundred and seven miles we had climbed nearly seven thousand feet, sometimes over very steep grades. Before we reached the summit, snow sheds began to appear, and soon became practically continuous. It was the nonth of May, and the mountains were tember 28—a flag waved from the top, announcing the curing the blade to the hub, the nut is turned down deep with snow. We rode through forty miles of these wooden tunnels, from whose windows we could now and then catch glances of wild wastes of snow-covered mountains, and at other times of forests of pine and fir trees. Without these sheds it would be impossible to operate the road in winter. They are built in the most thorough manner, often upon solid foundations of masonry, and are separated by iron plates into sections, to guard against the spread of fire. There are automatic electric fire alarms in one of the longest sheds, and an engine with a tank close at hand is kept ready to flood any section that should catch on fire. The sheds are patrolled and guarded in a careful manner. Such attention is due not only to the passenger and freight traffic which the road conducts, but to the value of the sheds, which average from eight to twelve thousand dollars per mile. Several miles, where bridges and precipices made the construction difficult, cost as much as thirty thousand dollars per mile."

THE TRIPLE-SCREW WAR SHIP COLUMBIA.

war vessel took place November 18, a previously attempted trial on November 16 having been given up on account of bad weather, although the engines were said to have worked smoothly, developing more than the power called for by the contract. The course was almost directly north from a point off Cape Ann, Mass., a distance of 43.96 nautical miles, the vessel crossing the line at full speed, making a long turn, and taking another run over the course in the opposite direction. According to the arrangements made, the times of passage over the course alone were to be taken, the time of turning being eliminated, but during the turn and displaces 7,350 tons. Her power consists of three no change in engines or boilers was to be permitted, and not a valve or link was to be touched.

The starting line was crossed at 9:54:40, and at 11:49:48 the ship dashed across the finish line, completing the first half of the trial, the average speed having been 22.92 knots. During this run the steam pressure had risen to 158 pounds, and revolutions 136 each on the twin screws and 131 on the midship screw, and the last seven miles were said to have been | ter knot the vessel makes over the required twentymade at the rate of 25'3 knots an hour. After turning in a circle of about four miles diameter, the

tation and correction of the resulting speed, there were The official speed trial of this our most recently built | yet a host of subjects concerning which the government officers were deputed to gather numerous and thorough data. Indicator diagrams were taken at close intervals from every engine on board, and from these will be determined pressures, horse power, and other information of great value to the navy department, not only for use in relation to the Columbia herself, but as a guide and assistance in future engine designing. Temperatures of fire rooms, fuel, water, etc. were also carefully noted.


> The Columbia is 412 feet long on the load water line. 58 feet extreme beam, 22 feet 6½ inches normal draught, three-cylinder vertical inverted triple expansion engines, having about 22,000 collective indicated horse power and driving three screws, one on the middle line, as in single screw ships, and the other two under the counters, as in twin screw vessels. This power is calculated to produce a speed of 21 knots an hour, which the contract for the vessel calls for, but the builders will receive a bonus of \$50,000 for every quarone knots. Our engraving is from Once a Week.

The engines are in three separate water-tight comrun back was commenced, the line being crossed at | partments, the two driving the counter screws be- | tirely oxidized, and physiological tests, in which frogs,

engines would not do, because of their size and the fact that they would be very extravagant in the use of steam at the ordinary cruising speed. Besides this the space that could be given up to machinery was restricted, and would not be satisfactory for twin screw engines. Mr. Melville then decided that triple screw engines were the only ones that would do, and at once set about the preliminary design. Through the course of her construction he has watched the machinery carefully, and the success which she has achieved marks a new era in marine propulsion.

Potassium Permanganate as an Antidote,

Schlagdenhauffen and Reeb refer to the fact that J. Antal has found permanganate of potassium act as an antidote to phosphorus, muscarine, strychnine, colchicine, oil of savin, and oxalic acid, when administered to frogs, rabbits, and dogs, with or directly after the poisons, and then proceed to describe the result of experiments conducted by themselves to ascertain the effect of the permanganate upon coronillin, C11H12O5, a poisonous bitter principle isolated by them some years ago from the leaves of Coronilla scorpioides. They find that when the salt is placed in direct contact with the glucoside the latter is decomposed, being en-



THE NEW UNITED STATES WAR SHIP COLUMBIA.

12:14:58, with a steam pressure of 160 pounds, the twin | ing placed abreast the same as in twin screw ships, | pigeons, and guinea pigs were used, seemed to prove screws making 136 revolutions each, and the midship and the one driving the center shaft just abaft them

of the boilers at one time, and the speed between two weight of all propelling machinery, including water in of the stations on the course dropped to the rate of the boilers, is 1,950 tons. The coal supply on her 21 11 knots, but the total backward run was made at normal displacement is 1,200 tons, but her maximum the average rate of 22.71 knots. The mean of the two have earned a premium of \$350,000 for attaining a of about 16,000 knots. speed of seven quarter knots over that called for by their contract. The naval officers aboard are said to have expressed the highest satisfaction with the performance of the vessel throughout.

The board conducting the trial consisted of Rear Admiral George E. Belknap, Commodore J. G. Walker, Capt. Edmund W. Matthews, Chief Engineer Edward Farmer, Commodore Philip H. Cooper, Commander F. A. Cook, Lieut. Commander Joseph N. Hemphill, and Naval Constructor Joseph Feaster, with Lieut. L. L. Reamy as recorder. These officers had also numerous assistants, the total government inspection force numbering no less than 36 officers—13 of the line, 20 of the engineer corps, and 3 of the construction corps of the navy. While the determination of the speed alone rethe passage of certain ranges, and the careful compu- and boilers. It soon became apparent that twin screw visited the Fair.

and lapping each for one-half its width. Steam is sup-During the backward run there was some priming plied by eight four-furnace double-ended boilers. The the latter.—Journ. der Pharm. von Elsass-Loth. bunker capacity is 2,200 tons, which will give her at

The application of power through triple screws in large ships is an innovation, and its results in the Columbia are watched with intense interest by the entire civilized world. Essentially and avowedly a commerce destroyer, and not a fighting ship, the armament of the Columbia will be comparatively light.

The Columbia has been in a special degree the work of Engineer-in-Chief G. W. Melville, U. S. N., of the Bureau of Steam Engineering, under whose direction the designing of her machinery was done. When the estimates were made for this ship, the speed fixed was twenty knots, but after the naval appropriation bill was passed, it was found that in conference the speed had been raised to twenty-one knots, and Mr. Melville decided that the ship should have from 20,000 to 21,000

that the permanganate is a true antidote to the poison when administered within a sufficiently brief time after

Seeing the World's Fair at Home.

Many as were the visitors to the great Columbian Exposition just closed, they include runs was therefore figured as 22.81, and the builders the most economical cruising speed a radius of action small percentage of those who would like to have gone but were unable to do so. To the most of the stay-athomes, however, there will now be offered, for many months to come, opportunities of acquiring a very near and pleasurable acquaintance with the best features of the memorable show, through the means of the excellent magic lantern and stereopticon views taken. T. H. McAllister, of New York, who received an award on his exhibit of magic lanterns and stereopticons, and who has long made a specialty of lantern slide views, has a wonderfully complete and varied collection of such views of the Exposition itself, by means of which one can obtain a most vivid portrayal, not only of the buildings, but a large proportion of the exhibits. One set of these lantern slide views is also accompanied by an original descriptive lecture thereon, in pamphlet form, whereby entertainment and instrucquired nothing save the accurate marking of time at horse power, and at once began to lay out the engines tion may be given to an audience by one who never

RECENTLY PATENTED INVENTIONS. Engineering.

FURNACE.—Wardell Guthrie, Chicago, Ill. Air pipes arranged alongside the furnace, according to this improvement, have openings into the furnace above the fire surface, and the furnace is fed by a screw conveyor in a trough lengthwise and centrally of the bottom, the fuel being fed back and upward as a projecting crank on the end of the screw is turned. The air is fed by force directly on the surface of the fire, as the fuel is fed up from the bottom. A dump or grate, for removing cinders or ashes, is placed at one or both sides of the

DRAG FOR STEERING VESSELS.—Louis Boucher, West Superior, Wis. This is a device designed for use only when a ship's rudder becomes disabled, and it is so made that it may be conveniently stowed away and set up in a very short time when needed. The drag is an air-tight cylinder with pointed forward end, in which is a ring, there being annular flanges or fins on the cylinder. Attached to the ring is a chain which connects with two chains, one leading to each side of the vessel near the stern, where the chains are passed around pulleys in the outer ends of projecting beams, and thence over pulley blocks and a central capstan, whereby the drag may be easily moved to one side or the other in the

PROPELLER.—Frank J. Leisen, Woodbridge, N. J. This propeller has cylindrical, spirally formed and diagonally opposing exterior surfaces, and hollow interior formed with two pockets, one pocket visible from each side, and both pockets uniting to form a circular opening at the outer end. There are spiral exte rior blades or ribs, each rib above a pocket. This improvement has been practically tested in a 16 inch propeller, demonstrating its superiority to an 18 inch fluke wheel, and a 36 inch pattern has been furnished the owners of Yankee Doodle, of Philadelphia, from which a propeller is to be made and given a public trial on that famous yacht.

Railway Appliances.

CAR COUPLING.-Edward N. and Jacob J. Byers, Cameron, Mo. This invention provides a safety attachment for couplers of the Janney type, where by, should the drawbar be drawn from its proper seat, the device acts automatically to uncouple the loosened draw head from the opposing car. An uncoupling lever connected with the drawbar has one end located beneath the coupling pin, and a guide is so connected with a fixed support that the lever will be elevated beneath the pin as the drawbar or drawhead is carried outward from the proper position.

PNEUMATIC SIGNAL.—George V. Steeb. Brooklyn, N. Y. The utilizing of air pressure to operate signals or semaphores is the object of this improvement, which provides for bringing the air pressure into action by the passing of a train over the track. The air under pressure is supplied by a pipe from any suitably located compressing source to a cylinder located in a suitable chamber beneath or adjacent to the track, this cylinder being connected with another cylinder in which is a piston, the movement of which operates the semaphore rod, the action being controlled by a valve in a third cylinder, actuated as the wheels of the car pass over inclined planes at the side of the track. The apparatus may also be used to ring alarm bells, move crossing gates, etc.

Electrical.

CARBON HOLDER.—Clark C. Hill, New port, R. I. This holder is formed of a cylindrical, longitudinally slotted socket with thickened ends, and having near one end a circumferential groove to which is fitted a circular spring. With this improvement the upper and lower carbons of electric lamps may be held in the position of use without the employment of screw clamps or adjusting screws. The sections of the socket formed by slotting may also be made to clamp the carbons sufficiently without employing the circular spring.

ELECTRIC REGULATOR AND SWITCH. Walter N. Jones, Jr., Petersburg, Va. This is an improvement for use on electric cars, in which the same adjusting devices serve to regulate the current to both the motor and the brake magnets, without allowing the current to be on the motor and the brake magnet at the same time from any inattention or forgetfulness of the motor man. Combined with two concentric rheostats, and two concentric series of segmental plates leading thereto, is a central shaft with insulated metal tubes bearing separate contact arms playing respectively upon the series of plates, the central shaft and metal tube forming two independent paths for the current centrally through the rheostats. The power increases in the motor by the movement of the crank in one direction, and in-creases in the brake by the mere reversal of the movement of the crank.

Mechanical.

HOOP SAWING AND SHAPING MACHINE. -Ephraim O. Hall, Marshfield, Oregon, This machine is designed to cut two hoops from a round log each time the log is fed to the machine, the hoops being perfectly formed, their upper sides planed, the edges scarfed, and the under side, in the direction of the heart of the log, left rough, the machine requiring but a single attendant. A diagonal saw at the rear of a vertical saw produces a kerf meeting that formed by the vertical saw, a planer being operated in conjunction with the latter saw, while an adjustable planer and an adjustable saw are also diagonally located, the latter saw being held to cut beneath the surface planed smooth by the planer.

HOOP CUTTING MACHINE .-- Alban H. Adams, Fort Meade, Fla. According to this invention a roller cutter is applied to an ordinary rotary veneer cutting machine, to score the log or make longitudinal incisions in it, making also perforations between the incisions, so that when the veneer is turned from the log it will fall apart at the places of the incisions, forming a series of hoops, the grain of which runs lengthwise and which are already perforated to receive the nails. The hoops thus made are especially adapted for use on orange boxes and similar packages.

PRINTER'S FURNITURE.—Jacob C. Wolfe, New York City. The design in this furniture is to present the maximum of bearing surface with the least weight, while it may be quickly and conveniently cast, and will afford a facing of uniform thickness. It consists of a hollow block with top and bottom recessed to form a marginal rib, the bottoms of the recesses inclining from the side ribs to the center of the block. while it has also a longitudinal central wall and trans verse partitions forming pockets in each side.

WIRE BENDING MACHINE.—Cyrus M. Suter, Ashton, Ill. This is a machine for making stays especially adapted for placing the strands of wire fences and holding them the desired distance apart. The construction of the machine is such that the operation of forming a stay is entirely automatic, the stays being made successively from a length or coil of wire.

Agricultural.

CULTIVATOR.—August Leineweber. De Witt, Neb. This invention provides an improvement in cultivators of the disk type, and the cultivator shank is carried by and has vertical adjustment in a slide having movement upon the beam, there being a gear connection between the slide and the shank whereby the latter is revolved. Any desired number of cultivators may be placed upon a beam, and the cultivator disks are of peculiar construction, each disk being more or less cupped or rendered concave upon its inner face and convexed upon its outer face.

Miscellaneous.

APPARATUS FOR LIGHTING BUILDINGS. -John W. Davis, New York City. The lighting of interior rooms, basements and lofts, not readily lighted by windows, is the design of this improvement, the apparatus first condensing the beams of light, then carrying them to the desired locality and diffusing them, by a pe culiar arrangement of mirrors operated by clockwork A concave paraboloidal mirror is supported and adapted to travel above a light conduit, a convex paraboloidal mirror being held at the focus of the concave mirror and adapted to throw beams of light through an aperture in the latter, a plane deflecting mirror being held to receive the beams of light and throw them into the conduit.

VEHICLE BRAKE.—Eugene W. Cleveland, Rounthwaite, Canada. This is a strong and simple device, more especially designed for use on portable engines and other heavy vehicles. It comprises a frame on which is a windlass, chains attached to and wound upon the windlass being extended in opposite directions and hooked upon spokes of the wheels of the vehicles.

GLASS STRUCTURE -- Edgar W. Cun ningham, Jersey City, N. J. This improvement pertains to an improved construction of skylights and the roofs and sides of greenhouses or conservatories, combining with aligned panels a joining piece of two metal binding strips having straight abutting sides which are soldered together, and parallel flat upper and lower flanges which closely embrace the adjacent opposite ends of the panels the lower flanges being extended and curved to form a

SPIRIT LEVEL AND INCLINOMETER. James P. Famous, Norristown, Pa. This device comprises an adjustable level tube in an elongated level stock. there being a grade indicating slide block at each end and a fixed transverse level tube on the top of the stock, in combination with a swiveling sight tube on the stock The implement is adapted to determine whether objects are level, plumb, or inclined, and exactly determine the degree of inclination from a horizontal plane, the device being adapted for use in building and engineering work of all kinds

ROCK DRILL - William O. Higgins, Kingwood, Ind. This is an implement which may be conveniently worked by hand and easily handled by one man to place it in the desired position. In a suitable upright frame are mounted a vertically movable drill shaft and a driving shaft, an eccentric on the latter ope rated by a pivoted lever, there being a sliding ratchet wheel on the drill shaft and a pawl pivoted to a centrally pivoted lever, and a link connecting the two levers The drill is steadily fed downward, to be able at every stroke to deliver an effective blow.

WRITING TABLET AND MANUSCRIPT HOLDER.-Barton W. Scott, San Jose, Cal. This improvement is more especially designed for the use of stenographers, public speakers, type setters, and others, to permit of readily writing matter on a continuous sheet, and conveniently displaying the written matter The invention comprises a casing having two winding drums for the paper, a main shaft being journaled in the casing and actuating two gear wheels, which are adapted to be geared with the winding drum.

COAL SCREEN. -Frank L. Sackett, Fredonia, N. Y. To facilitate the screening of broken coal for retail purposes is the object of this invention, and the device provided therefor is simple and inexpensive. It consists of an oblong proper is stretched, and having an end wall and discharge opening, and whose bottom slides on side bars of the screen, the hopper being adjustable and removable The device may be attached to the side of a cart or inclined against an upright support.

BICYCLE WHISTLE.—John F. Hylan and Robert L. Sinley, Brooklyn, N. Y. This is a simple and practical device, which may be readily attached to a safety bicycle, and comprises an air pump, to be actuated by the rotary motion of the front wheel, to afford a copious supply of air, and, on the movement of a lever, blow a loud blast on a whistle connected to the pump. The lever is projected below the handle bar, and the blast may be prolonged for as long a time as the lever is held gripped with the handle bar.

THILL SUPPORT.—Adolph Meyerhoff, New York City. A pair of keepers on the thill or pole is provided for by this improvement, and a slide bolt in allied subjects. the forward keeper has a head engaging the keeper, while a chain secured to the rear end of the bolt runs through the rear keeper, and a hook on the running gear of any Architectural Publication in the world. Sold by engages the chain. The device is very simple and inex- all newsdealers. pensive, and may be attached to the thills or pole of any

vehicle to hold them at the necessary height for conve nience in storing, or to hold them up to take their weight from the horse's back.

FOLDING BED.—Hugh Stevenson, New York City. This is an improvement upon a formerly patented invention, according to which, when the beds are folded, the bedding is suspended, both the covers and mattress, to permit a free circulation iof air between the covers, that they may be thoroughly ventilated. The present patent provides an improved construction, whereby, when the bed is folded, the covers may be separated and held perfectly straight, the covers and mattress being also so held that the bed may be very easily made up when necessary

SHOE. - William T. Loyd, Hiawatha, Kan. The sole of this shoe is formed of a single sheet of metal, with a metallic counter, and a flange around the toe and ball, a flexible top toe piece being fastened to the front flange and a flexible lining at the heel. Beneath the ball and heel are also attached plates having serrated flanges, adapting the shoe especially for use as an ice creeper. The shoe is held on the foot by a strap

BOX FASTENER. - Thomas Cole, St. Mary's, Mo. A safe and simple fastener, which will per mit crates on which it is used to be packed on top of each other and slid about without disturbing the fastening, has been provided by this inventor. The fastening hasps are secured to staples made with spring coils, and the free ends of the hasps engage pins in recess the upper face of the lid, the spring tension holding the fastening firm, while the pressing up of the staple loosens the hold of the hasp on the pin.

SWEATERS.-William T. Pitchers, Godalming, England. Five design patents have been awarded this inventor on this article of apparel. In the first the sleeves and body are ornamented with panels having adiacent angular figures alternately embossed and in intag lio, and in the second are decorative panels of diamond ape, with sunken body and embossed margin. In the third are intersecting figures of serpentine character. with interposed series of ribs; in the fourth, rectangular figures inclose grouped circular figures, and in the fifth the body and sleeves have a surface finish of embossed ribs arranged spirally or diagonally.

Note.—Copies of any of the above patents will be furnished by Munn & Co., for 25 cents each. Please end name of the patentee, title of invention, and date of this paper.

SCIENTIFIC AMERICAN BUILDING EDITION.

NOVEMBER, 1893.-(No. 97.)

TABLE OF CONTENTS.

- 1. Elegant plate in colors showing a residence at Bridge port, Conn., recently erected for Mr. Thos. C. Woodin, at a cost of \$4,600 complete. Floor plans and two perspective elevations. An excellent design. Mr. Henry A. Lambert, architect, Bridgeport, Conn.
- Plate in colors showing the residence of Clarence M. Burch, Esq., at Philadelphia, Pa. Two perspective views and floor plans. A very attractive design. Messrs. Moses & King, architects, Philadelphia.
- A dwelling erected at Joliet, Ill. Perspective views and floor plans. An excellent design. Cost \$6,000 complete. Mr. J. C. Weece, architect, Joliet, Ill.
- 4. A suburban cottage erected at Glenbrook, Conn., at a cost of \$3,500 complete. Floor plans, perspective view, etc. Mr. E. H. Waterbury, Stamford, Conn., architect. An excellent design.
- 5. Engravings and floor plans of a suburban residence erected for Mr. George H. Barton, at Hartford, Conn. Messrs. Hapgood & Hapgood, architects, Hartford, Conn. A very attractive design. Very excellent design for a two-family house,
- erected at Bridgeport, Conn., at a cost of \$4,500. Floor plans and perspective elevation. Mr. A. H. Beers, architect, Bridgeport, Conn.
- St. Peter's Chapel at Springfield, Mass. Perspective and ground plan. Cost \$7,100 complete. Mr. W. P. Wentworth, architect, Boston, Mass.
- Engraving showing some city dwellings of modern design at Washington Heights, New York City. Plans and perspective views. Mr. W. E. Mowbray, architect, New York.
- 9. Residence of Mr. C. T. Hemsteadat Glenbrook, Conn Plans and perspective. An excellent design.
- 10. Moving of the Normandy apartment building at Chicago. Supposed to be the largest building ever moved and turned around on rollers. Numerous illustrations
- 11. The World's Columbian Exposition. A general view.
- 12. Sketches at the World's Columbian Exposition 13. Miscellaneous Contents: Causes of fire in dwellings.

-An improved brace, illustrated.—Steel ceilings, illustrated.—A large day's sawing.—The new mode of constructing foundations.-Sheathing quilt, illustrated.-A cap for the obelisk.-Interior woodwork for buildings, illustrated.—Electrical injuries to gas and water pipes.—An improved scraper, illustrated.-Linseed oil for paint and polish.-Improved circular sawing machine, illustrated.

The Scientific American Architects and Builders Edition is issued monthly. \$2.50 a year. Single copies, 25 cents. Forty large quarto pages, equal to about two hundred ordinary book pages; forming, practically, a large and splendid MAGAZINE OF ARCHITEC TURE, richly adorned with elegant plates in colors and with fine engravings, illustrating the most interesting examples of Modern Architectural Construction and

The Fullness, Richness, Cheapness, and Convenience of this work have won for it the LARGEST CIRCULATION MUNN & CO., PUBLISHERS,

361 Broadway, New York.

Business and Personal.

The charge for Insertion under this head is One Dollar a line for each insertion; about eight words to a line. Adverements must be received at publication office as early as Thursday morning to appear in the following week's issue

For mining engines. J. S. Mundy, Newark, N. J. "U. S." metal polish. Indianapolis Samples free.

Improved iron planers. W. A. Wilson, Rochester, N.Y.

The new material, "linenoid." Westfield, Mass. Cataogue free.

Microbe Killer Water Filter, McConnell Filter Co.,

Patent for Sale-Big savings. Cable grip. Address No. 2123 Eastern Ave., Baltimore, Md.

Steam Hammers, Improved Hydraulic Jacks, and Tube

Expanders. R. Dudgeon, 24 Columbia St., New York Will purchase patent of meritorious small article. Give particulars. Manufacturer, box 2238, New York.

Estimates furnished for moving, raising, or shoring ouildings. W. K. Clynes, Jersey City, N. J. Estab. 1853. Screw machines, milling machines, and drill presses. The Garvin Mach. Co., Laight and Canal Sts., New York.

Centrifugal Pumps. Capacity, 100 to 40,000 gals. per ninute. All sizes in stock. IrvinVan Wie, Syracuse, N. V. Wanted to manufacture, new machinery of real merit. John M. Kramer & Bro. Machine Works, Maria Stein, O.

Wanted-Novelty manufacturing companies to send their address to Fred. Beaumont, 1307 Franklin Street, Kansas City, Mo.

Model dynamo motor. Ingenious machine for students and experimenters. Elbridge Electrical Mfg. Co., Elbridge, New York.

Guild & Garrison, Brooklyn, N. Y., manufacture steam pumps, vacuum pumps, vacuum apparatus, air pumps, acid blowers, filter press pumps, etc

For the original Bogardus Universal Eccentric Mill, Foot and Power Presses, Drills, Shears, etc., address J.S. & G. F. Simpson, 26 to 36 Rodney St., Brooklyn, N. Y.

The best book for electricians and beginners in electricity is "Experimental Science," by Geo. M. Hopkins. By mail, \$4; Munn & Co., publishers, 361 Broadway, N. Y.

Readers of the Scientific American can obtain, free of charge, a copy of the American Shipbuilder by addressing Bradley & Howell, 7 Coenties Slip, New York.

Competent persons who desire agencies for a new popular book, of ready sale, with handsome profit, may apply to Munn & Co., Scientific American office. 361 Broadway, New York.

Send for new and complete catalogue of Scientific nd other Books for sale by Munn & Co., 361 Broadway, New York. Free on application.



HINTS TO CORRESPONDENT'S.

Names and Address must accompany all letters, or no attention will be paid thereto. This is for our information and not for publication.

References to former articles or answers should give date of paper and page or number of question.

Inquiries not answered in reasonable time should be repeated; correspondents will bear in mind that some answers require not a little research, and, though we endeavor to reply to all either by letter or in this department, each must take his turn.

Buyers wishing to purchase any article not advertised in our columns will be furnished with addresses of houses manufacturing or carrying the same.

Special Written Information on matters of personal rather than general interest cannot be expected without remuneration.

Scientific American Supplements referred to may be had at the office. Price 10 cents each.

Books referred to promptly supplied on receipt of price.

Minerals sent for examination should be distinctly

price.

Minerals sent for examination should be distinctly marked or labeled.

(5502) H. E. W. asks how to run a 70 volt motor of 1/2 horse power on a 110 volt circuit. A. Connect your motor across a pair of 12 light leads or larger, and place in series with it a resistance of 8 ohms. For the latter use No. 15 wire, or if you have them, 30 lamps in parallel with each other and in series with the

(5503) J. R. N. says: Suppose a tank at an elevation of 250 feet in height, 10 feet in width, and 15 feet in height, with a pipe attached to bottom of tank 3 inches in diameter, 250 feet in length, perpendiculars. Suppose said tank to be filled with water. How many gallons of water will flow through said pipe per minute and what horse power would be required to keep this tank full of water, there being a constant discharge 3 inches in diameter? A. The pipe will discharge 1,275 gallons per minute and will require 80 horse power to

(8504) E. A. S. says: Kindly inform me through the columns of your paper of a process forcuring small skins, such as squirrel, etc. A. Mix bran and soft water sufficient to cover the skins. Immerse the latter and keep them covered for twenty-four hours, then remove, wash clean, and carefully scrape off all flesh. To 1 gallon of water (hot) add 1 pound of alum and 1/4 pound of salt. When dissolved and cool enough to admit entrance of the hand, immerse the skins for twenty-four hours, dry in the shade and rub. Stir the liquor again, immerse the skins for twenty-four hours, dry and rub as before; immerse for twenty-four hours in oatmeal and warm water, partially dry in the shade, and finally rub until entirely dry. This leaves the skin like white leather, and fit for immediate use.

(5505) L. M. asks: What is the best method to preserve pneumatic tires for bicycles from one season to another, that is, to keep them from cracking and keep them soft? A. Wash the rubber tires perfectly clean and dry. Warm them by a stove and rub melted paraffine over the surface with a warm cloth. A very thin coat answers the purpose. If rubber cement can be obtained, such as sold by the rubber trade, a thin wipe of it with a woolen rag over the surface of the tires will keep them in good order.

(5506) S. B. W. asks: What the power of an ordinary man would be equal to in horse

power. A. With a horse power equal to 33,000 foot pounds? Oil can be obtained for 5 cents per gallon or pounds per minute, the power of an average strong man working to the best practical advantage for 10 hours is 4,200 foot pounds per minute. On short spurts can accomplish from two to three times as much, or half a horse power.

(5507) G. W. T. says: In this valley the coal is let down from the openings on the hills by wire cables and large drums and the speed is controlled by iron bands or brakes applied to the outside of the drums Why is it that the bands or brakes wear faster than the iron plating on the drums? They are all the same kind of iron, and the band reaches nearly around the drum, but the plating on the drums will outwear three bands of the same thickness. A. Brake bands are generally much thinner and have less wearing surface than the drum band; besides the motion of the drum band tends to keep it cool, while the friction on the thin brake band makes it hot, and hot iron wears faster than cold iron.

(5508) G. E. P. writes: Can the simple electric motor described in Supplement, 641, be run an hour or so a day by three storage battery cells which are charged the rest of the twenty-four hours by six cells of gravity battery? A. Yes; but you will need eight cells or more of gravity batteries for charging.

(5509) W. A. P. asks: How to hard solder one of those aluminum World's Fair sonvenirs and also how to soft solder on the same. A. For hard solder for aluminum, use an alloy of 6 parts aluminum, 4 parts copper, 90 parts zinc. Use Canada balsam forflux. For soft solder, an alloy of 95 parts of tin, 5 parts bismuth, or 5 parts cadmium, 2 parts zinc, 3 parts tin, using paraffine or vaseline for flux.

(5510) M. W. S. asks: In what proportion should air and ordinary illuminating gas be used in a gas engine to produce the best results? A. The constituents of ordinary illuminating gas vary somewhat in different cities and require a variable amount of air for perfect combustion; 8 to 12 volumes of air to 1 volume of a good quality of gas will produce the best result.

(5511) A. C. McG. says: Will you please inform me what chemicals are used to perform the trick of smoking from two clay pipes, by holding the bowl of one over the other? A. Hydrochloric acid and ammonia are used for this purpose.

(5512) W. W. Brown, Culbertston, Neb., writes: Under Notes and Queries (No. 5356) B. C. W asks if there is any kind of a flux that can be used better than borax. I have a patent on a flux that will do the work he desires and will be pleased to be placed in communication with him.

(5513) R. E. B. asks: How is the power determined to drive a boat of a given size at a certain speed? This is for small boats of from 18 feet to 40 feet long. A. So much depends upon the lines and build of boats, together with the varying weight of the power, that computation of the power required for stated speed becomes somewhat complicated. The approximate formula

 $\Lambda_3 D_{\frac{3}{3}}$ $\frac{2}{C}$ = 2 H. P. In which V² is the cube of the re-

quired velocity in knots per hour, $D^{\frac{3}{3}}$ is the cube root of the square of the displacement in tons, C is a coefficient for the water lines of the boat, which for launches and small steam yachts may vary from 500 for medium lines to 530 for sharp lines. The displacement should be computed for the total load, boat, machinery, water, fuel and

(5514) E. S. McI. says: It is stated by the highest engineering authorities that the passage of impure water through sufficient gravel or sand will remove the impurities and make even sewage water wholesome and well tasting. Can you inform me what value as a filterer have the cinders from anthracite coal taken from under a boiler? A. The statement of engineers may be true in regard to the insoluble elements of sewage, but the soluble salts, urates, etc., have been traced a long way through the waterways of the ground, less through the loams and quicksand, but to an almost unlimited extent through the coarser gravels forming the principal underground waterways. When sewage is filtered through thick beds of material, so as to maintain the nitrifying organisms, which are supposed to be supported by a proper supply of sewage, there are possibilities of potable water being a product of such filtration. Gravel bed surface filtration has been found very efficacious in purifying sewage. Drinking the effluent is hardly to be recommended. Clean ashes from under a boiler should make a fairly good stratum in a filter after the soluble salts of the coal and wood are removed. The ash stratum should be protected by sand.

(5515) J. B. says: I am at present experimenting with a toy balloon. For a certain purpose I would like to have this balloon carry a weight from 3 to 4 ounces. The common toy balloon filled with coal gas has no lifting capacity. What I wish to know is whether this same balloon could be filled with some other kind of a gas, to give satisfaction. If this is possible, please let me know. A. If hydrogen gas were used, it would lift more than the coal gas. But it would require a balloon of say 6 cubic feet capacity filled with hydrogen to lift 4 ounces weight.

(5516) B. S. says: Will cedar or cypress tanks (or leach tubs) for tan liquors last the longest without rotting and how long will they last if well taken care A. There is very little difference in the lasting qualities of cedar and cypress for tan bark leach vats.

(5517) C. R. — Clean celluloid collars and cuffs with saleratus and water, using an old nail

(5518) F. De T says: Kindly give rule: How heavy should the joist be under a tank holding 18,000 gallons water, 40 feet from the ground, and are 12 x 12 heavy enough for uprights and plates, if properly braced? A If your tank is circular, 15 feet diameter by 15 feet high, the joists should be 4 x 12, 2 feet apart. Uprights and plates 12 x 12 inches.

 $(5519)\,$ F. M. says : Will you please state the difference of cost (used for cooking and furnace heating) against anthracite coal at \$4.75 per ton of 2,000

less, delivered in the tank. Would not two barrels of oil contain as much fuel as one ton of coal, taking combustion and advantage in controlling the use in consideration? A. The cost of petroleum at prices named is more than twice as much as coal for a given number of heat units for a constant fire. The only advantage in favor of petroleum at the price named is for the intermittent use of heat, such as for cooking in summer and the generation of steam for sudden and special use.

(5520) J. E. L. Co. asks: In a cylinder 20 inches long by 6 inches diameter, with a piston at one end, we find if subjected to 300 degrees, the volume of air will increase about 1/3. I would like to know the expanding force of the air thus heated, or how much will it move the piston and resist one pound pressure to the square inch? A. By heating the air from 60° to 300° it expands approximately 50 per cent, or 1 volume become nearly 11/2 volumes, and if confined to the original volume it will have a pressure of 6 pounds per square inch, and will push a piston in a continuous cylinder from 20 inches, as above stated, to 271/2 inches under 1 pound pressure per square inch.

(5521) W. A. W.—To make heel ball: Hard suet and beeswax, of each 4 ounces, powdered gum, sugar candy, and Venice turpentine, of each 1 ounce, ivory black and lamp black, of each 2 ounces The coloring matter and sugar must be in fine powder. Dissolve the candy in as little water as possible. Melt the suet and the beeswax and add the sirup and the coloring matter, stir thoroughly, then pour into moulds.

(5522) K. S. asks: Is there any difference between an injector and an inspirator? A. There is no difference in principle between an injector and an inspirator. See an interesting illustrated article on injectors in Scientific American Supplement, No. 356

(5523) J. M. says: I have a cistern that was sunk in heavy clay, then boarded up with inch lum ber, leaving a space of 3 inches behind the boards; into this space I packed soft clay and rammed it down tight as I boarded it up. I thought this would hold water and make an inexpensive cistern. I find that it will not hold water. Is there any way in which I can plaster it up with water lime over the boards to make it hold? Or is there anything you could suggest whereby I can fix it to hold in without going to much expense? The cistern is 5×5 and 6 feet deep. To settle a dispute, will you please say how many feet of timber in a stick 12×12 inches at one end and 24×24 inches at other end and 40 feet long and give figures showing how to obtain the proper answer A. You cannot do better than to take out the wood and clay tamping of your cistern and make the bottom and sides of Portland cement concrete, 1 part of cement 3 parts clean sharp sand, then plaster the entire inside surface with pure Portland cement. Your cistern must be circular. For the taper timber. Rule: To the sum of the areas of the two ends add four times the area of the center and multiply this sum by one-sixth of the length. The piece of timber as stated contained 93.26 cubic feet.

(5524) D. F. V. asks: What would be the temperature at points 10, 20 and 40 feet below surface of ground in ordinary soil and does it vary much winter or summer? Also what force per square inch will air confined at ordinary temperature exert if heated from 300 Fah. to 600° Fah.? If compressed to 15 pounds per square inch before heating, would pressure be doubled when heated? A. The temperature of the earth at from 10 to 20 feet below the surface is nearly the same as the mean annual temperature on the surface. In mid-latitudes from 50° to 60° Fah., according to the condition of the surface soil. The increase of temperature downward is also variable, due to the nature and structure of the soil and rocks, the rate varying from 50 to 65 feet in depth for each degree of rise in the thermometer.

(5525) P. J. L. says: I wish to experiment with a hot water radiator for heating a room, and wish to know what kind of the following metals will give off the most heat, cast iron, steel, or copper, with hot water at 212°. Also, what amount of radiator surface is needed for a room $12 \times 12 \times 9$, both for water and steam, and what quantity of water would radiator hold? What degree of heat would be shown on surface of radiator? Would it be possible to heat a radiator of the required size with a center draught lamp or with a gas burner? A. A copper radiator will be the most efficient in heating surface. Your room will require 12 square feet of heating surface for either hot water or low pressure steam. The capacity depends upon the plan of construction. The outside surface should be from 210° to 211° Fah. A large lamp or gas stove will heat the radiator.

(5526) C. P. asks: 1. How can a magnetized watch be demagnetized? Is there any machine for doing same, and where can I get description of it? A. A strong horseshoe magnet is required for demagnetizing watches. See an article on this subject in Sci-ENTIFIC AMERICAN SUPPLEMENT, No. 668. would be the size of the smallest boiler to generate enough steam for working the steam turbine described in No. 17 of this journal, at the rate of 30,000 revolutions? A. A 25 horse power boiler might produce the number of revolutions you mention.

(5527) E. E. asks if it would be possible to read messages that were being transmitted through an ocean cable by inductive means, after grappling the cable and lifting it to the deck of a vessel. A. We think this would be impossible, on account of the use of a very weak current in the cable for transmitting messages and the ability of the metallic protecting covering of the cable to absorb practically all of the inductive impulses.

(5528) P. G. asks: 1. What would be the power of dynamo described in SCIENTIFIC AMERICAN SUPPLEMENT, No. 161, if changed into a motor? A. About one man power, if supplied with sufficient watts. 2. What different connections are made to change a dynamo into a motor? A. No changes are requisite. The size of wire for winding depends on the potential that is available. 3. Would current enough to run a 6 candle power lamp run the above motor? A. It might run it if the motor was well constructed, but with very little

(5529) A. B. C. says: I have a motor like the one described in Scientific American Supple-

MENT, No. 759, with the exception that the field magnet | Coin-controlled apparatus, R. M. Shaffer...... 508,848 is of the horseshoe style instead of the consequent pole type, as shown in that paper. It runs finely with six cells of plunge battery. I would like to rewind it for use on a 220 volt motor circuit. Should it be wound series or shunt? What size of wire and how many layers should I use on the magnet and armature.? If it could not be wound for that high voltage, could I wind it for 110 volts and run in series with a 110 volt 16 candle power lamp? A. Wind your motor in series, with enough wire to give a safe current at 220 volts. We cannot do the calculation without knowing the size of your motor. If to be used with the lamp, it may be wound with enough No. 26 wire in field and No. 29 in armature to give 110 ohms resistance. In the calculation take the armature as wound in parallel, giving one-quarter the resistance of its

(5530) W. A. M.—For information in regard to sterilizing milk, see Scientific American Sur-PLEMENT, Nos. 811 and 872.

TO INVENTORS.

An experience of forty-four years, and the preparation of more than one hundred thousand applications for patents at home and abroad, enable us to understand the laws and practice on both continents, and to possess unequaled facilities for procuring patents everywhere. A synopsis of the patent laws of the United States and all foreign countries may be had on application, and persons ontemplating the securing of patents, either at home or abroad, are invited to write to this office for prices which are low, in accordance with the times and our extensive facilities for conducting the business. Address MUNN & CO., office Scientific American, 361 Broadway, New York.

INDEX OF INVENTIONS

For which Letters Patent of the United States were Granted

November 14, 1893,

AND EACH BEARING THAT DATE

[See note at end of list about copies of these patents.]

Air broke clack adjuster H Hinckler	508,435 508,450 508,421 508,753	E
Alkalies by electrolysis, process of and apparatus	508,804 508,796 508,637	EEEE
Autographic register, G. M. Morris Autographic register, Morris & Stokes	508,634 508,552 508,553	E
Automatic sight feed lubricator, C. Couse. Axle box, A. H. Sensenig. Axle, etc., pivotal, C. A. Bowen. Axle, vehicle, T. S. Field.	508,566 508,438 508,499 508,876	E
Baker's paddle, E. C. Cox	508,423 508,411 508,703 508,855	E
	508,609 508,586 508,394 508,408	E
Bearing, ball thrust, N. C. Bassett	508,408 508,897 508,787 508,670 508,775	E
Bedstead, W. H. Harrison Bicycle brake attachment, F. T. Snyder.	508,548 508,517 508,490 508,418	E
Billiard games, automatic time check for, C. B. Hopkins Bin. See Flour bin. Block. See Building block. Paving block, Boller. See Steam boiler. Water tube boller.	1	E
Boiler brace, A. F. Huston	508,718 508,790 508,793	E
Bolt cutter, M. D. Luehrs. Bone cutting mill, J. Poulson. Book, record and index, P. Gruber. Bookbinding press, C. Seybold	508,528 508,699 508,847	EEE
BOOKDINGING press, C. Seybold. Boring spherical cavities, device for, J. Riddell Boring tool, J. W. Batcheller Bottle stopper, D. F. Doody Box. See Newspaper lock box. Paper box. Box etc., material for forming, E. T. Kepner Brace. See Boller breae. Rallway rall brace.	508,640 508,803 508,509	EFF
Brace. See Boiler breae. Railway rail brace. See Car brake. Electric brake. Railway brake. Vehicle brake. Brake beam, H. B. Robischung.	500,120	11111
Brick, w. Lenderoth. Brick or tile structures, system of, D. A. Straw	508,531 508,428 508,446	11111
Buckle, W. L. Braddock Buckle, L. B. Prabar Building block, W. O. Myers	508,522 508,675 508,752 508,577	F
Burial robes, former for, O. E. Seaney	508,455 508,400 508,846	F
Butter Stractor, centrifugal, O. Ohlsson	000,190	F F
Call and telephone, combined messenger, G. E.	508,454 508,563 508,477	F G
Cans, lamp filling attachment for oil, J. C. H.	508,730	GG
Car brake, D. N. Cook. Car brake, W. J. Devers. Car coupling, J. E. Ament. Car coupling. Gay & Finke.	508,409 508,872 508,797 508,695	G
Car coupling, R. D. McGee. Car coupling, Pitts & Cowden. Car coupling, G. W. Smillie	508,899 508,527 508,442 508,853	G
Car coupling, F. A. Stevens. Car, elevated railway, J. L. Pope. Car fender, A. L. Clarke. Car beater, E. H. Gold.	508,779 508,631 508,565 508,514	G
Car and air brake coupling, combined, G. Rohrbach. Car brake, D. N. Cook. Car brake, W. J. Devers. Car coupling, J. E. Ament. Car coupling, J. E. Ament. Car coupling, R. D. McGee. Car coupling, R. D. McGee. Car coupling, P. E. Servinger. Car coupling, G. W. Smillie. Car coupling, F. A. Stevens. Car coupling, F. A. Stevens. Car, elevated railway, J. L. Pope. Car fender, A. L. Clarke. Car heating system and apparatus, E. H. Gold. Car heating systems, trap for, E. E. Gold. Car heating systems, trap for, E. E. Gold. Car life-preserving guard, A. Knoblauch. Car lighting system, electric, J. C. Henry. Car, railway, R. L. Piepenbring. Car, switch, railway, T. A. Remsen. Car wheel, D. Hazard. Cars, brake apparatus for electrically propelled, F. O. Blackwell. Cars, etc., fender for electric, C. N. Homan. Cars, means for preventing derailment of, Kirchner & Chase.	508,513 508,569 508,888 508,616	: G
Car platform gate, C. H. Cox. Car, railway, R. L. Piepenbring Car switch, railway, T. A. Remsen. Car wheel, D. Hazard	508,815 508,835 508,837 508,824	GGGGGGGG
F. O. Blackwell	508,673 508,472	G
Card waste transmitter, Robinson & Conley,	508,892 508,488 508,726	G
Case. See Banker's case. Packing case. Razor		I
strop case. Show case. Casket, metallic, Lupfer & Hiser Casting rollers, F. B. Torrey. Cbair, See Dental chair. Rocking chair. Chair, W. H. Fauber. Chicken house, W. H. Putnam. Chuck, drill, A. Woeber. Churn dasher, A. Schuyler. Chute, ash, Stelling & Reetz. Cigar vending machine, Kletzker & Ranz. Cleat for electric wiring, F. A. Duggan. Clock moon dial, E. A. Clark.	508,690 508,529 508,667	H
Churn dasher, A. Schuyler. Chute, ash, Stelling & Reetz. Cigar vending machine, Kletzker & Rana. Cleat for electric wiring, F. A. Duggan.	508,768 508,583 508,725 508,687	I
Clear for electric wiring, F. A. Duggan. Clock moon dial, E. A. Clark. Cloth cutting machines, overhead support for conducting wires of, A. K. Thyll. Clothes drier, H. R. Sheets. Clutch, f iction, Wakefield & Libby. Coll, reactive, E. Thomson.	508,467 508,534 508,772	H
Clutch, f iction, Wakefield & Libby	508,663 508,657	I

Ţ	Coin-controlled apparatus, R. M. Shafer. Collar and hames combined horse, J. Morrison. Coloring matter from tye-wood extracts, obtaining friable. P. Masten. Contact apparatus. E. Thouson Cooking devices. Thouson Cooking the Cooking Cooking Cooking Cooking Cooking. Cooking. Cooking See Car coupling. Car and air brake coupling. See Car coupling. Car and air brake coupling. Fire hose coupling. Hose coupling. Steam-tight coupling. Thill coupling. Coupling. W. H. Hampson Crane. J. Horton Crayon or pencil. A. K. Cross. Cultivator, L. Luppen Cultivator, L. Luppen Cultivator, J. Macphail Current motor alternating, Kelly & Chesney Current transformer, W. H. Hornberger Currents means for regulating multiphase, E. W. Rice, Jr.	508,848 508,483
1	ing friable, P. T. Austen	508,592 508,651 508,759
	Cooking utensil. G. H. Nicholls	508,831 508,863 508,842
	Coupling. See Car coupling. Car and air brake coupling. Fire hose coupling. Hose coupling.	508,431
	Coupling, W. H. Hampson Crane, J. Horton	508,765 508,476
	Cultivator, A. Hodgson. Cultivator, L. Luppen Cultivator, L. Macnheil 508 433	508,712 508,481 508,434
	Current motor, alternating, Kelly & Chesney Current transformer, W. H. Hornberger Currents, means for regulating multiphase. E.	508,721 508,422
	W. Rice, Jr Cut-out, electric, E. Thomson Cut-out, safety, O. Offrell. Cutter. See Band cutter. Bolt cutter. Paper cutter. Twine cutter.	508,638 508,652 508,629
	Cutting gauge and marker, combined, A. A. Wal-	-000
	die. Gycles, fiexible and collapsible mud guard for, M. F. Taintor. Cyclometer, C. H. Clawson Cyclometer actuating device, C. H. Clawson. Damper governor, G. C. Hicks. Decorative films, roll for holding and applying, W. H. Coe. Dental apparatus, theostat for controlling elec- trically-concreted J. P. B. Visito.	508,453 508,782 508,405
	Cyclometer actuating device, C. H. Clawson Damper governor, G. C. Hicks Decorative films, roll for holding and applying	508,406 508,709
	W. H. Coe. Dental apparatus, rheostat for controlling electrically-operated, J. P. B. Fiske. Dental chair, T. N. Clark. Dental chair, T. N. Clark. Dental impression tray, H. A. Burlingame. Deodorizing hydrocarbon oils, A. Kayser. Die. See Machine die. Die, M. G. Fuller.	508,869 508,692
	Dental chair, T. N. Clark. Dental impression tray, H. A. Burlingame. Deodorizing hydrocarbon oils, A. Kayser	508,564 508,677 508,479
	Die. See Machine die. Die. M. G. Fuller	508,694
	Die. See Machine die. Die. M. G. Fuller. Die, M. G. Fuller. Direct-acting engine, J. G. Leyner. Dish drainer, bread board, and cutting board, combined, J. D. Johnston. Display table, W. Macnamar. Display tay, F. A. Gruebel. Distance and altitude instrument, W. H. Pratt. Dolls, making, Scott & Seymour. Door, fexible, F. Jefts. Door, fexible, F. Jefts. Door, opener, electric, H. T. Johnson. Dranght equalizer, J. W. Steinmetz. Draining board for bars. E. Neely. Drapery fastering device, W. P. Miller. Draver pull, G. Halds.	508,885
	Display tray, F. A. Gruebel. Distance and altitude instrument, W. H. Pratt Dolls. making. Scott. & Seymour	508,700 508,556 508,770
	Door bolt, D. D. Reeves. Door, flexible, F. Jefts. Door opener, electric, H. T. Johnson.	508,635 508,720 508,518
	Draught equalizer, J. W. Steinmetz. Draining board for bars, E. Neely Drapery fastening device, W. P. Miller	508,778 508,740 508,735
	Drawer pull, J. G. Hallas. Dredging machine, hydraulic, J. W. Sackett Drier. See Clothes drier.	508,878 508,76 6
	Earth carrier, J. J. Wishard. Egg containing cases, apparatus for rotating, J. H. Rowley	508,589 508,589
	Bowley Electric arc disrupter, W. B. Potter Electric brake, E. B. Skinner Electric circuit indicating apparatus, E. Thom-	508,806 508,632 508,851
	Electric circuits, stand for controlling, E. R.	508,662 508,626
	Knowles. Electric circuits, switch box for controlling, Knowles & Park. Electric conductor, underground, J. C. Henry. Electric current meter detector, E. Thomson. Electric distribution, E. W. Rice, ir. Electric distribution system, W. S. Moody. Electric distribution system, E. W. Rice, Jr. Electric elevator, A. T. Chase. Electric generator, W. S. Hill Electric generator, W. S. Hill Electric lighting system, E. Thomson. Electric lighting system, E. Thomson. Electric lighting system, E. Thomson. Electric machine or motor, dynamo, E. Thomson Electric machines, brush holder for dynamo, E. R. Knowles. Electric machines, conductor for dynamo, Reist & Fiske. Electric machines, machine for boring out the standards and field magnets of dynamo, J. Riddell. Electric meter, E. Thomson.	508,625 508,613
	Electric current meter detector, E. Thomson Electric distribution, E. W. Rice, Jr Electric distribution system, W. S. Moody	508,660 508,838 508,898
	Electric distribution system, E. W. Rice, Jr Electric elevator, A. T. Chase. Electric generator, W. S. Hill.	508,839 508,680 508,880
	alternate current, W. Stanley, Jr. Electric lighting system, E. Thomson. Electric lighting system, T. A. Willard	508,493 508,647
	Electric machine or motor, dynamo, E. Thomson Electric machines, brush holder for dynamo, E. R. Knowles	508,658 508 624
	Electric machines, conductor for dynamo, Reist & Fiske. Electric machines, machine for boring out the	508,636
	standards and field magnets of dynamo, J. Riddell Electric meter, E. Thomson	508,639 508,661
	Kiddell. Electric meter, E. Thomson. Electric motors, fluid pressure device for control- ling, Parshall & Darley, Jr. Electric transformer, E. Thomson. Electrical condenser, J. F. Kelly Electrical contact making device, W. F. Z. De- sant.	508,630 508,655 508,887
	Electrical contact making device, W. F. Z. Desant.	508,871 508,646
	Sant Section of the Control of the C	508,646 508,688 508,650
	vator. Elevator controller, electric, J. P. B. Fiske Elevator controlling mechanism, T. W. Eaton Emery or corundum wheel, safety, W. S. Shipe Engine. See Direct-acting engine. Gas engine. Pressure engine. Pumping engine. Rotary	
	Engine. See Direct-acting engine. Gas engine. Pressure engine. Pumping engine. Rotary	000,110
	Engines, automatic safety stop for, A. J. Bates Engines, igniting apparatus for gas, G. E. Hoyt	508,671 508,618
	Engines, automatic safety stop for, A. J. Bates Engines, igniting apparatus for gas, G. E. Hoyt	508,671 508,618
	engines, automatic safety stop for, A. J. Bates Engines, igniting apparatus for gas, G. E. Hoyt Engraving chuck, Eaton & Fargo. Eraser, blackboard, J. Haggerty. Extervapor motor, P. De Susini Excavator, F. H. Schulte. Extension table, R. Mainardi. Extractor. See Butter extractor. Stump ex-	508,671 508,618 508,606 508,704 508,447 508,437 508,628
	engines, automatic safety stop for, A. J. Bates Engines, igniting apparatus for gas, G. E. Hoyt Engraving chuck, Eaton & Fargo. Eraser, blackboard, J. Haggerty. Extervapor motor, P. De Susini Excavator, F. H. Schulte. Extension table, R. Mainardi. Extractor. See Butter extractor. Stump ex-	508,671 508,618 508,606 508,704 508,447 508,437 508,628
	engines, automatic safety stop for, A. J. Bates Engines, igniting apparatus for gas, G. E. Hoyt Engraving chuck, Eaton & Fargo. Eraser, blackboard, J. Haggerty. Extervapor motor, P. De Susini Excavator, F. H. Schulte. Extension table, R. Mainardi. Extractor. See Butter extractor. Stump ex-	508,671 508,618 508,606 508,704 508,447 508,437 508,628
	engines, automatic safety stop for, A. J. Bates. Engines, igniting apparatus for gas, G. E. Hoyt Engraving chuck, Eaton & Fargo. Eraser, blackboard, J. Haggerty. Ether vapor motor, P. De Susini Excavator, F. H. Schulte. Extension table, R. Mainardi. Extractor. See Butter extractor. Stump extractor. Eyeglass guard, G. Bausch (r). Face plate jaw, J. N. Skinner. Fan motor, W. S. Hill. Fender. See Car fender. Fence, W. N. Lane. Fence and tightener, wire, C. H. Brunk. Fence machine, hand, J. H. Pivonka. Fillet, T. C. Belding. Filter, J. M. Skinner. Fire secape, E. A. Couch.	508,671 508,618 508,606 508,704 508,447 508,437 508,628 11,389 508,533 508,710 508,889 508,465 508,399 508,440 508,684
	engines, automatic safety stop for, A. J. Bates. Engines, igniting apparatus for gas, G. E. Hoyt Engines, igniting apparatus for gas, G. E. Hoyt Engines, igniting apparatus for gas, G. E. Hoyt Engines, igniting chuck, Eaton & Fargo. Eraser, blackboard, J. Hagserty. Eher vapor motor, P. De Susini Extensior, F. H. C. Mainardi. Extensior, F. H. C. Mainardi. Extensior See Butter extractor. Stump extensions are parted in the extractor. Eyeglass quard, G. Bausch (r). Face plate jaw, J. N. Skinner. Fan motor W. S. Hill. Fender. See Car fender. Fence and tightener, wire, C. H. Brunk. Fence and tightener, wire, C. H. Brunk. Filler, T. C. Belding. Filter, J. M. Skinner. Fire hose coupling, Sackett & Pfetsch. Fireproof construction, Crittenden & Emery, Fireproof construction, Crittenden & Emery.	508,671 508,618 508,606 508,407 508,437 508,437 508,528 11,389 508,533 508,710 508,628 508,805
	engines, automatic safety stop for, A. J. Bates. Engines, igniting apparatus for gas, G. E. Hoyt Engraving chuck, Eaton & Fargo. Eraser, blackboard, J. Haggerty. Ether vapor motor, P. De Susini Excavator, F. H. Schulte. Extension table, R. Mainardi. Extractor. See Butter extractor. Stump extractor. Eyeglass guard, G. Bausch (r) Face plate jaw, J. N. Skinner. Fan motor, W. S. Hill. Fender. See Car fender. Fence, W. N. Lane. Fence and tightener, wire, C. H. Brunk. Fence machine, hand, J. H. Pivonka. Fillet, T. C. Belding. Filter, J. M. Skinner Fire secape, E. A. Couch. Fire hose coupling, Sackett & Pfetsch. Fireproof construction, Crittenden & Emery. Fish net sinker, J. S. Coey.	508,671 508,616 508,606 508,704 508,437 508,437 508,628 11,289 508,533 508,710 508,889 508,435 508,564 508,636 508,638 508,638 508,638
	engines, automatic safety stop for, A. J. Bates. Engines, igniting apparatus for gas, G. E. Hoyt Engraving chuck, Eaton & Fargo. Eraser, blackboard, J. Haggerty. Ether vapor motor, P. De Susini Excavator, F. H. Schulte. Extension table, R. Mainardi. Extractor. See Butter extractor. Stump extractor. Eyeglass guard, G. Bausch (r) Face plate jaw, J. N. Skinner. Fan motor, W. S. Hill. Fender. See Car fender. Fence, W. N. Lane. Fence and tightener, wire, C. H. Brunk. Fence machine, hand, J. H. Pivonka. Fillet, T. C. Belding. Filter, J. M. Skinner Fire secape, E. A. Couch. Fire hose coupling, Sackett & Pfetsch. Fireproof construction, Crittenden & Emery. Fish net sinker, J. S. Coey.	508,671 508,616 508,606 508,704 508,437 508,437 508,628 11,289 508,533 508,710 508,889 508,435 508,564 508,636 508,638 508,638 508,638
	engines, automatic safety stop for, A. J. Bates. Engines, igniting apparatus for gas, G. E. Hoyt Excavator, F. H. Schulte Extension table, R. Mainardi. Extension table, R. Mainardi. Extractor. See Butter extractor. Stump extractor. Egglass guard, G. Bausch (r) Explain garder, G. Bausch (r) Extension for gas garder, G. Bausch (r) Explain garder, G. H. Brunk Explict, J. M. Lane. Fence, W. N. Lane. Frence machine, hand, J. H. Pivonka Explict, J. G. Belding. Explication for garder, G. Belding. Explain gas, G. E. Hold Explain gas, G. E. Fickett. Explain gas, G. E. Pickett. Finge balls to the border of textile fabrics, machine for attaching, R. A. Swoboda. Fruit washing and cleaning apparatus, D. E. Barton.	508,671 508,616 508,606 508,704 508,637 508,437 508,437 508,533 508,710 508,839 508,710 508,849 508,840
	engines, automatic safety stop for, A. J. Bates. Engines, igniting apparatus for gas, G. E. Hoyt Engraving chuck, Eaton & Fargo. Eraser, blackboard, J. Haggerty. Ether vapor motor, P. De Susini Excavator, F. H. Schulte. Extension table, R. Mainardi. Extractor. See Butter extractor. Stump extractor. Eyeglass guard, G. Bausch (r). Face plate jaw, J. N. Skinner. Fan motor, W. S. Hill. Fender. See Car fender. Fence, W. N. Lane. Fence and tightener, wire, C. H. Brunk. Fence machine, hand, J. H. Pivonka. Fillet, T. C. Belding. Filter, J. M. Skinner Fire secape, E. A. Couch. Fire hose coupling, Sackett & Pfetsch. Fireproof construction, Crittenden & Emery. J. Beard. Flour bin and sieve, G. C. Sberman. Folding gate, E. Fickett. Fringe balls to the border of textile fabrics, machine for attaching, R. A. Swoboda. Fruit washing and cleaning apparatus, D. E. Barton. Evenace. See Boiler furnace.	508,671 508,618 508,606 508,606 508,447 508,427 508,528 11,289 568,533 508,710 508,465 508,369 508,369 508,684 508,840 508,681 508,681 508,463 508,463 508,463 508,463 508,463 508,463 508,664 508,660
	engines, automatic safety stop for, A. J. Bates. Engines, igniting apparatus for gas, G. E. Hoyt Engraving chuck, Eaton & Fargo. Eraser, blackboard, J. Haggerty. Ether vapor motor, P. De Susini Excavator, F. H. Schulte. Extension table, R. Mainardi. Extractor. See Butter extractor. Stump extractor. Eyeglass guard, G. Bausch (r). Face plate jaw, J. N. Skinner. Fan motor, W. S. Hill. Fender. See Car fender. Fence, W. N. Lane. Fence and tightener, wire, C. H. Brunk. Fence machine, hand, J. H. Pivonka. Fillet, T. C. Belding. Filter, J. M. Skinner Fire secape, E. A. Couch. Fire hose coupling, Sackett & Pfetsch. Fireproof construction, Crittenden & Emery. J. Beard. Flour bin and sieve, G. C. Sberman. Folding gate, E. Fickett. Fringe balls to the border of textile fabrics, machine for attaching, R. A. Swoboda. Fruit washing and cleaning apparatus, D. E. Barton. Evenace. See Boiler furnace.	508,671 508,618 508,606 508,606 508,447 508,427 508,528 11,289 568,533 508,710 508,465 508,369 508,369 508,684 508,840 508,681 508,681 508,463 508,463 508,463 508,463 508,463 508,463 508,664 508,660
	engines, automatic safety stop for, A. J. Bates. Engines, igniting apparatus for gas, G. E. Hoyt Engines, igniting apparatus, G. Earon. Extension table, R. Mainardi. Extractor. See Butter extractor. Stump extractor. Eyeglass guard, G. Bausch (r) Face plate jaw, J. N. Skinner. Fan motor, W. S. Hill Fender. See Car fender. Fence, W. N. Lane. Fence and tightener, wire, C. H. Brunk. Fence machine, band, J. H. Pivonka. Fillet, T. C. Belding. Filter, J. M. Skinner. Fire escape, E. A. Couch. Fire pose coupling, Sackett & Pfetsch. Fireproof construction, Crittenden & Emery, Fish net sinker, J. S. Coey. Floor-cloth, machine for the manufacture of, W. J. Beard. Flour bin and sieve, G. C. Sherman Folding gate, E. Pickett. Fringe balls to the border of textile fabrics, machine for attaching, R. A. Swoboda Fruit washing and cleaning apparatus, D. E. Barton. Furnace. See Boiler furnace. Ore roasting and calcining furnace. Furniture, adjustable support for school, T. R. Roulstone. Furniture, adjustable support for school, T. R. Fuse plug, H. C. West. Gauge. See Cutting gauge. Game apparatus, C. O. Moore. Game apparatus, A. M. Quilck	508,671 508,618 508,606 508,606 508,706 508,447 508,437 508,637 508,533 508,710 508,895 508,805 508,805 508,804 508,844 508,844 508,844 508,865 508,865 508,865 508,865 508,865 508,865 508,865 508,864
	engines, automatic safety stop for, A. J. Bates. Engines, igniting apparatus for gas, G. E. Hoyt Engines, igniting apparatus, G. Earon. Extension table, R. Mainardi. Extractor. See Butter extractor. Stump extractor. Eyeglass guard, G. Bausch (r) Face plate jaw, J. N. Skinner. Fan motor, W. S. Hill Fender. See Car fender. Fence, W. N. Lane. Fence and tightener, wire, C. H. Brunk. Fence machine, band, J. H. Pivonka. Fillet, T. C. Belding. Filter, J. M. Skinner. Fire escape, E. A. Couch. Fire pose coupling, Sackett & Pfetsch. Fireproof construction, Crittenden & Emery, Fish net sinker, J. S. Coey. Floor-cloth, machine for the manufacture of, W. J. Beard. Flour bin and sieve, G. C. Sherman Folding gate, E. Pickett. Fringe balls to the border of textile fabrics, machine for attaching, R. A. Swoboda Fruit washing and cleaning apparatus, D. E. Barton. Furnace. See Boiler furnace. Ore roasting and calcining furnace. Furniture, adjustable support for school, T. R. Roulstone. Furniture, adjustable support for school, T. R. Fuse plug, H. C. West. Gauge. See Cutting gauge. Game apparatus, C. O. Moore. Game apparatus, A. M. Quilck	508,671 508,618 508,606 508,606 508,706 508,447 508,437 508,637 508,533 508,710 508,895 508,805 508,805 508,804 508,844 508,844 508,844 508,865 508,865 508,865 508,865 508,865 508,865 508,865 508,864
	engines, automatic safety stop for, A. J. Bates. Engines, igniting apparatus for gas, G. E. Hoyt Engines, igniting apparatus for gas, G. E. Hoyt Engines, igniting apparatus for gas, G. E. Hoyt Engines, igniting chuck, Baton & Fargo. Eraser, blackboard, J. Haggerty. Ether vapor motor, F. De Susini Excavator, F. H. Schulte Extension table, R. Mainardi. Fender. See Car fender. Fender. See Car fender. Fender. See Car fender. Fenee, W. N. Lane. Fenee, W. N. Lane. Fenee machine, hand, J. H. Pivonka. Fillet, T. C. Belding. Fiter, J. M. Skinner Fre escape, E. C. Get. Fire poof construction, Crittenden & Emery. Fire proof construction, Crittenden & Emery. Fish net sinker, J. S. Coey. Fish net sinker, J. S. Coey. Fish ret sinker, J. S. Sherman. kolding gate, E. Pickett. Fringe balls to the border of textile fabrics, machine for attaching, R. A. Swoboda. Fruit washing and cleaning apparatus, D. E. Barton. Furnace. See Roiler furnace. Ore roasting and calcining furnace. Furniture, adjustable support for school, T. R. Roulstone. Roulstone. Game apparatus, C. C. Moore. Game apparatus, C. C. Moore. Game apparatus, W. D. Pickens. Game apparatus, W. D. Pickens. Game apparatus, W. D. Pickens. Game apparatus, L. M. Aluck Game apparatus, L. H. H. Engelman. Gas engine. Von Oechelhaeueser & Junkers.	508,671 508,618 508,604 508,700 508,447 508,437 508,437 508,533 508,710 508,533 508,710 508,634 508,644 508,644 508,644 508,644 508,646 508,664 508,664 508,664 508,681 508,680
	engines, automatic safety stop for, A. J. Bates. Engines, igniting apparatus for gas, G. E. Hoyt Engines, igniting apparatus for gas, G. E. Hoyt Engines, igniting apparatus for gas, G. E. Hoyt Engines, igniting chuck, Baton & Fargo. Eraser, blackboard, J. Haggerty. Ether vapor motor, F. De Susini Excavator, F. H. Schulte Extension table, R. Mainardi. Fender. See Car fender. Fender. See Car fender. Fender. See Car fender. Fenee, W. N. Lane. Fenee, W. N. Lane. Fenee machine, hand, J. H. Pivonka. Fillet, T. C. Belding. Fiter, J. M. Skinner Fre escape, E. C. Get. Fire poof construction, Crittenden & Emery. Fire proof construction, Crittenden & Emery. Fish net sinker, J. S. Coey. Fish net sinker, J. S. Coey. Fish ret sinker, J. S. Sherman. kolding gate, E. Pickett. Fringe balls to the border of textile fabrics, machine for attaching, R. A. Swoboda. Fruit washing and cleaning apparatus, D. E. Barton. Furnace. See Roiler furnace. Ore roasting and calcining furnace. Furniture, adjustable support for school, T. R. Roulstone. Roulstone. Game apparatus, C. C. Moore. Game apparatus, C. C. Moore. Game apparatus, W. D. Pickens. Game apparatus, W. D. Pickens. Game apparatus, W. D. Pickens. Game apparatus, L. M. Aluck Game apparatus, L. H. H. Engelman. Gas engine. Von Oechelhaeueser & Junkers.	508,671 508,618 508,604 508,700 508,447 508,437 508,437 508,533 508,710 508,533 508,710 508,634 508,644 508,644 508,644 508,644 508,646 508,664 508,664 508,664 508,681 508,680
	engines, automatic safety stop for, A. J. Bates. Engines, igniting apparatus for gas, G. E. Hoyt Engines, igniting apparatus for gas, G. E. Hoyt Engines, igniting apparatus for gas, G. E. Hoyt Engines, igniting chuck, Baton & Fargo. Eraser, blackboard, J. Haggerty. Ether vapor motor, F. De Susini Excavator, F. H. Schulte Extension table, R. Mainardi. Fender. See Car fender. Fender. See Car fender. Fender. See Car fender. Fenee, W. N. Lane. Fenee, W. N. Lane. Fenee machine, hand, J. H. Pivonka. Fillet, T. C. Belding. Fiter, J. M. Skinner Fre escape, E. C. Get. Fire poof construction, Crittenden & Emery. Fire proof construction, Crittenden & Emery. Fish net sinker, J. S. Coey. Fish net sinker, J. S. Coey. Fish ret sinker, J. S. Sherman. kolding gate, E. Pickett. Fringe balls to the border of textile fabrics, machine for attaching, R. A. Swoboda. Fruit washing and cleaning apparatus, D. E. Barton. Furnace. See Roiler furnace. Ore roasting and calcining furnace. Furniture, adjustable support for school, T. R. Roulstone. Roulstone. Game apparatus, C. C. Moore. Game apparatus, C. C. Moore. Game apparatus, W. D. Pickens. Game apparatus, W. D. Pickens. Game apparatus, W. D. Pickens. Game apparatus, L. M. Aluck Game apparatus, L. H. H. Engelman. Gas engine. Von Oechelhaeueser & Junkers.	508,671 508,618 508,604 508,700 508,447 508,437 508,437 508,533 508,710 508,533 508,710 508,634 508,644 508,644 508,644 508,644 508,646 508,664 508,664 508,664 508,681 508,680
	engines, automatic safety stop for, A. J. Bates. Engines, igniting apparatus for gas, G. E. Hoyt Engines, igniting apparatus for gas, G. E. Hoyt Engines, igniting apparatus for gas, G. E. Hoyt Engines, igniting chuck, Baton & Fargo. Eraser, blackboard, J. Haggerty. Ether vapor motor, F. De Susini Excavator, F. H. Schulte Extension table, R. Mainardi. Fender. See Car fender. Fender. See Car fender. Fender. See Car fender. Fenee, W. N. Lane. Fenee, W. N. Lane. Fenee machine, hand, J. H. Pivonka. Fillet, T. C. Belding. Fiter, J. M. Skinner Fre escape, E. C. Get. Fire poof construction, Crittenden & Emery. Fire proof construction, Crittenden & Emery. Fish net sinker, J. S. Coey. Fish net sinker, J. S. Coey. Fish ret sinker, J. S. Sherman. kolding gate, E. Pickett. Fringe balls to the border of textile fabrics, machine for attaching, R. A. Swoboda. Fruit washing and cleaning apparatus, D. E. Barton. Furnace. See Roiler furnace. Ore roasting and calcining furnace. Furniture, adjustable support for school, T. R. Roulstone. Roulstone. Game apparatus, C. C. Moore. Game apparatus, C. C. Moore. Game apparatus, W. D. Pickens. Game apparatus, W. D. Pickens. Game apparatus, W. D. Pickens. Game apparatus, L. M. Aluck Game apparatus, L. H. H. Engelman. Gas engine. Von Oechelhaeueser & Junkers.	508,671 508,618 508,604 508,700 508,447 508,437 508,437 508,533 508,710 508,533 508,710 508,634 508,644 508,644 508,644 508,644 508,646 508,664 508,664 508,664 508,681 508,680
	engines, automatic safety stop for, A. J. Bates. Engines, igniting apparatus for gas, G. E. Hoyt Excavator, F. H. Schulte Extension table, R. Mainardi. Extension table, R. Mainardi. Extension table, R. Mainardi. Extractor. See Butter extractor. Stump extractor. Eyeglass guard, G. Bausch (r). Eyeglass guard, S. E. Brunk Eyeglass guard, J. N. Skinner. Enne machine helmg, J. H. Pivonka Eyence and tightener, wire, C. H. Brunk Eyence machine helmg, J. H. Pivonka Eyelse helmg, J. H. Pivonka Eyelse helmg, J. H. Eyench, Eyelse helmg, J. H. Eyelse, G. E. Sherman. Folding gate, E. Pickett Eyelse helmg, J. Beard. Floor-cloth, machine for the manufacture of, W. J. Beard. Flour bin and sieve, G. C. Sherman. folding gate, E. Pickett. Eyelse helms, J. E. Barton Eyelse helmg, R. A. Swoboda Eyrut washing and cleaning apparatus, D. E. Barton Eyelse for gauge, See Cutting gauge. Grane apparatus, C. Moore. Game apparatus, W. D. Pickens. Game apparatus, W. D. Pickens. Game apparatus, W. D. Pickens Game apparatus, W. D. Pickens Game apparatus, Engle & Thompson Garden tool, combined, S. M. Alexander. Garment supporting bracket, J. J. Bisel. Gas burner, natural, H. H. Engelman. Gas engine, Von Oechelhaeuser & Junkers. Gate, See Car platform gate. Folding gate. Sidding gate. Gate, G. H. Aylworth. Gaes, Gass rolling machinery, P. V. Peltier. Glass mould, R. W. Blaze. Glass rolling machinery, P. V. Peltier. Glass surfaces, producing colors on, J. C. Duntze. Glass mould, R. W. Blaze. Glove fas	508,671 508,618 508,604 508,604 508,604 508,608
	engines, automatic safety stop for, A. J. Bates. Engines, igniting apparatus for gas, G. E. Hoyt Excavator, F. H. Schulte Extension table, R. Mainardi. Extension table, R. Mainardi. Extension table, R. Mainardi. Extractor. See Butter extractor. Stump extractor. Eyeglass guard, G. Bausch (r). Eyeglass guard, S. E. Brunk Eyeglass guard, J. N. Skinner. Enne machine helmg, J. H. Pivonka Eyence and tightener, wire, C. H. Brunk Eyence machine helmg, J. H. Pivonka Eyelse helmg, J. H. Pivonka Eyelse helmg, J. H. Eyench, Eyelse helmg, J. H. Eyelse, G. E. Sherman. Folding gate, E. Pickett Eyelse helmg, J. Beard. Floor-cloth, machine for the manufacture of, W. J. Beard. Flour bin and sieve, G. C. Sherman. folding gate, E. Pickett. Eyelse helms, J. E. Barton Eyelse helmg, R. A. Swoboda Eyrut washing and cleaning apparatus, D. E. Barton Eyelse for gauge, See Cutting gauge. Grane apparatus, C. Moore. Game apparatus, W. D. Pickens. Game apparatus, W. D. Pickens. Game apparatus, W. D. Pickens Game apparatus, W. D. Pickens Game apparatus, Engle & Thompson Garden tool, combined, S. M. Alexander. Garment supporting bracket, J. J. Bisel. Gas burner, natural, H. H. Engelman. Gas engine, Von Oechelhaeuser & Junkers. Gate, See Car platform gate. Folding gate. Sidding gate. Gate, G. H. Aylworth. Gaes, Gass rolling machinery, P. V. Peltier. Glass mould, R. W. Blaze. Glass rolling machinery, P. V. Peltier. Glass surfaces, producing colors on, J. C. Duntze. Glass mould, R. W. Blaze. Glove fas	508,671 508,618 508,604 508,604 508,604 508,608
	engines, automatic safety stop for, A. J. Bates. Engines, igniting apparatus for gas, G. E. Hoyt Excavator, F. H. Schulte Extension table, R. Mainardi. Extension table, R. Mainardi. Extension table, R. Mainardi. Extractor. See Butter extractor. Stump extractor. Eyeglass guard, G. Bausch (r). Eyeglass guard, S. E. Brunk Eyeglass guard, J. N. Skinner. Enne machine helmg, J. H. Pivonka Eyence and tightener, wire, C. H. Brunk Eyence machine helmg, J. H. Pivonka Eyelse helmg, J. H. Pivonka Eyelse helmg, J. H. Eyench, Eyelse helmg, J. H. Eyelse, G. E. Sherman. Folding gate, E. Pickett Eyelse helmg, J. Beard. Floor-cloth, machine for the manufacture of, W. J. Beard. Flour bin and sieve, G. C. Sherman. folding gate, E. Pickett. Eyelse helms, J. E. Barton Eyelse helmg, R. A. Swoboda Eyrut washing and cleaning apparatus, D. E. Barton Eyelse for gauge, See Cutting gauge. Grane apparatus, C. Moore. Game apparatus, W. D. Pickens. Game apparatus, W. D. Pickens. Game apparatus, W. D. Pickens Game apparatus, W. D. Pickens Game apparatus, Engle & Thompson Garden tool, combined, S. M. Alexander. Garment supporting bracket, J. J. Bisel. Gas burner, natural, H. H. Engelman. Gas engine, Von Oechelhaeuser & Junkers. Gate, See Car platform gate. Folding gate. Sidding gate. Gate, G. H. Aylworth. Gaes, Gass rolling machinery, P. V. Peltier. Glass mould, R. W. Blaze. Glass rolling machinery, P. V. Peltier. Glass surfaces, producing colors on, J. C. Duntze. Glass mould, R. W. Blaze. Glove fas	508,671 508,618 508,604 508,604 508,604 508,608
3	engines, automatic safety stop for, A. J. Bates. Engines, igniting apparatus for gas, G. E. Hoyt Excavator, F. H. Schulte Extension table, R. Mainardi. Extension table, R. Mainardi. Extension table, R. Mainardi. Extractor. See Butter extractor. Stump extractor. Eyeglass guard, G. Bausch (r). Eyeglass guard, S. E. Brunk Eyeglass guard, J. N. Skinner. Enne machine helmg, J. H. Pivonka Eyence and tightener, wire, C. H. Brunk Eyence machine helmg, J. H. Pivonka Eyelse helmg, J. H. Pivonka Eyelse helmg, J. H. Eyench, Eyelse helmg, J. H. Eyelse, G. E. Sherman. Folding gate, E. Pickett Eyelse helmg, J. Beard. Floor-cloth, machine for the manufacture of, W. J. Beard. Flour bin and sieve, G. C. Sherman. folding gate, E. Pickett. Eyelse helms, J. E. Barton Eyelse helmg, R. A. Swoboda Eyrut washing and cleaning apparatus, D. E. Barton Eyelse for gauge, See Cutting gauge. Grane apparatus, C. Moore. Game apparatus, W. D. Pickens. Game apparatus, W. D. Pickens. Game apparatus, W. D. Pickens Game apparatus, W. D. Pickens Game apparatus, Engle & Thompson Garden tool, combined, S. M. Alexander. Garment supporting bracket, J. J. Bisel. Gas burner, natural, H. H. Engelman. Gas engine, Von Oechelhaeuser & Junkers. Gate, See Car platform gate. Folding gate. Sidding gate. Gate, G. H. Aylworth. Gaes, Gass rolling machinery, P. V. Peltier. Glass mould, R. W. Blaze. Glass rolling machinery, P. V. Peltier. Glass surfaces, producing colors on, J. C. Duntze. Glass mould, R. W. Blaze. Glove fas	508,671 508,618 508,604 508,604 508,604 508,608
3 3 3	engines, automatic safety stop for, A. J. Bates. Engines, igniting apparatus for gas, G. E. Hoyt Excavator, F. H. Schulte Extension table, R. Mainardi. Exte	508,671 508,616 508,606 508,607 508,617 508,617 508,617 508,618 508,819 508,819 508,819 508,618
2 3 5 0	engines, automatic safety stop for A. J. Bates. Engines, igniting apparatus for gas, G. E. Hoyt Exhervagor, F. H. Schulte Extension table, R. Mainardi. Extractor. See Butter extractor. Stump extractor. Eyeglass guard, G. Bausch (r) Face plate jaw, J. N. Skinner. Fan motor, W. S. Hill. Fender. See Car fender. Fence, W. N. Lane. Fence and tightener, wire, C. H. Brunk. Fence machine, band, J. H. Pivonka. Fillet, T. C. Belding. Filter, J. M. Skinner. Frire escape, E. A. Couch. Fire hose coupling, Sackett & Pfetsch. Fireproof construction, Crittenden & Emery, 508,501 to Fish net sinker, J. S. Coey. Floor-cloth, machine for the manufacture of, W. J. Beard Follow by J. Beard Flour bin and sieve, G. C. Sberman. Folding gate, E. Fickett. Fringe balls to the border of textile fabrics, machine for attaching, R. A. Swoboda. Fruit washing and cleaning apparatus, D. E. Barton. See Boiler furnace. Ore roasting and calcining furnace. Furniture, adjustable support for school, T. R. Roulstone. Fuse plug, H. C. West. Gauge. See Cutting gauge. Game apparatus, A. M. Quick. Garbage, night-soil, etc., apparatus for destroying, Engle & Thompson. Garden tool, combined, S. M. Alexander. Gare apparatus, A. M. Quick. Garbage, night-soil, etc., apparatus for destroying, Engle & Thompson. Garden tool, combined, S. M. Alexander. Gas burner, natural, H. H. Engelman. Gas engine, Von Oechelhaeuser & Junkers. Gate. See Car platform gate. Folding gate. Silding gate. Gase, Jester & Alexander. Gear, driving, J. F. Guild. Generator. See Electric generator. Glass mould, R. W. Blaze. Glass rolling machinery, P. V. Peltier. Glassware, snap for holding, T. C. Steimer. Glove fastener, W. B. H. Dowse. Grate atjachment, J.	508,671 508,618 508,606 508,606 508,607 508,628 11,289 568,533 508,819 508,684 508,684 508,684 508,684 508,684 508,684 508,684 508,686 508,688 508,688 508,688 508,688 508,688 508,688 508,688 508,688 508,688 508,688 508,688 508,688
25 09783	engines, automatic safety stop for A. J. Bates. Engines, igniting apparatus for gas, G. E. Hoyt Exhervagor, F. H. Schulte Extension table, R. Mainardi. Extractor. See Butter extractor. Stump extractor. Eyeglass guard, G. Bausch (r) Face plate jaw, J. N. Skinner. Fan motor, W. S. Hill. Fender. See Car fender. Fence, W. N. Lane. Fence and tightener, wire, C. H. Brunk. Fence machine, band, J. H. Pivonka. Fillet, T. C. Belding. Filter, J. M. Skinner. Frire escape, E. A. Couch. Fire hose coupling, Sackett & Pfetsch. Fireproof construction, Crittenden & Emery, 508,501 to Fish net sinker, J. S. Coey. Floor-cloth, machine for the manufacture of, W. J. Beard Follow by J. Beard Flour bin and sieve, G. C. Sberman. Folding gate, E. Fickett. Fringe balls to the border of textile fabrics, machine for attaching, R. A. Swoboda. Fruit washing and cleaning apparatus, D. E. Barton. See Boiler furnace. Ore roasting and calcining furnace. Furniture, adjustable support for school, T. R. Roulstone. Fuse plug, H. C. West. Gauge. See Cutting gauge. Game apparatus, A. M. Quick. Garbage, night-soil, etc., apparatus for destroying, Engle & Thompson. Garden tool, combined, S. M. Alexander. Gare apparatus, A. M. Quick. Garbage, night-soil, etc., apparatus for destroying, Engle & Thompson. Garden tool, combined, S. M. Alexander. Gas burner, natural, H. H. Engelman. Gas engine, Von Oechelhaeuser & Junkers. Gate. See Car platform gate. Folding gate. Silding gate. Gase, Jester & Alexander. Gear, driving, J. F. Guild. Generator. See Electric generator. Glass mould, R. W. Blaze. Glass rolling machinery, P. V. Peltier. Glassware, snap for holding, T. C. Steimer. Glove fastener, W. B. H. Dowse. Grate atjachment, J.	508,671 508,618 508,606 508,606 508,607 508,628 11,289 568,533 508,819 508,684 508,684 508,684 508,684 508,684 508,684 508,684 508,686 508,688 508,688 508,688 508,688 508,688 508,688 508,688 508,688 508,688 508,688 508,688 508,688
2 35 25 0973357	engines, automatic safety stop for A. J. Bates. Engines, igniting apparatus for gas, G. E. Hoyt Exhervagor, F. H. Schulte Extension table, R. Mainardi. Extractor. See Butter extractor. Stump extractor. Eyeglass guard, G. Bausch (r) Face plate jaw, J. N. Skinner. Fan motor, W. S. Hill. Fender. See Car fender. Fence, W. N. Lane. Fence and tightener, wire, C. H. Brunk. Fence machine, band, J. H. Pivonka. Fillet, T. C. Belding. Filter, J. M. Skinner. Frire escape, E. A. Couch. Fire hose coupling, Sackett & Pfetsch. Fireproof construction, Crittenden & Emery, 508,501 to Fish net sinker, J. S. Coey. Floor-cloth, machine for the manufacture of, W. J. Beard Follow by J. Beard Flour bin and sieve, G. C. Sberman. Folding gate, E. Fickett. Fringe balls to the border of textile fabrics, machine for attaching, R. A. Swoboda. Fruit washing and cleaning apparatus, D. E. Barton. See Boiler furnace. Ore roasting and calcining furnace. Furniture, adjustable support for school, T. R. Roulstone. Fuse plug, H. C. West. Gauge. See Cutting gauge. Game apparatus, A. M. Quick. Garbage, night-soil, etc., apparatus for destroying, Engle & Thompson. Garden tool, combined, S. M. Alexander. Gare apparatus, A. M. Quick. Garbage, night-soil, etc., apparatus for destroying, Engle & Thompson. Garden tool, combined, S. M. Alexander. Gas burner, natural, H. H. Engelman. Gas engine, Von Oechelhaeuser & Junkers. Gate. See Car platform gate. Folding gate. Silding gate. Gase, Jester & Alexander. Gear, driving, J. F. Guild. Generator. See Electric generator. Glass mould, R. W. Blaze. Glass rolling machinery, P. V. Peltier. Glassware, snap for holding, T. C. Steimer. Glove fastener, W. B. H. Dowse. Grate atjachment, J.	508,671 508,618 508,606 508,606 508,607 508,628 11,289 568,533 508,819 508,684 508,684 508,684 508,684 508,684 508,684 508,684 508,686 508,688 508,688 508,688 508,688 508,688 508,688 508,688 508,688 508,688 508,688 508,688 508,688
	engines, automatic safety stop for A. J. Bates. Engines, igniting apparatus for gas, G. E. Hoyt Exhervagor, F. H. Schulte Extension table, R. Mainardi. Extractor. See Butter extractor. Stump extractor. Eyeglass guard, G. Bausch (r) Face plate jaw, J. N. Skinner. Fan motor, W. S. Hill. Fender. See Car fender. Fence, W. N. Lane. Fence and tightener, wire, C. H. Brunk. Fence machine, band, J. H. Pivonka. Fillet, T. C. Belding. Filter, J. M. Skinner. Frire escape, E. A. Couch. Fire hose coupling, Sackett & Pfetsch. Fireproof construction, Crittenden & Emery, 508,501 to Fish net sinker, J. S. Coey. Floor-cloth, machine for the manufacture of, W. J. Beard Follow by J. Beard Flour bin and sieve, G. C. Sberman. Folding gate, E. Fickett. Fringe balls to the border of textile fabrics, machine for attaching, R. A. Swoboda. Fruit washing and cleaning apparatus, D. E. Barton. See Boiler furnace. Ore roasting and calcining furnace. Furniture, adjustable support for school, T. R. Roulstone. Fuse plug, H. C. West. Gauge. See Cutting gauge. Game apparatus, A. M. Quick. Garbage, night-soil, etc., apparatus for destroying, Engle & Thompson. Garden tool, combined, S. M. Alexander. Gare apparatus, A. M. Quick. Garbage, night-soil, etc., apparatus for destroying, Engle & Thompson. Garden tool, combined, S. M. Alexander. Gas burner, natural, H. H. Engelman. Gas engine, Von Oechelhaeuser & Junkers. Gate. See Car platform gate. Folding gate. Silding gate. Gase, Jester & Alexander. Gear, driving, J. F. Guild. Generator. See Electric generator. Glass mould, R. W. Blaze. Glass rolling machinery, P. V. Peltier. Glassware, snap for holding, T. C. Steimer. Glove fastener, W. B. H. Dowse. Grate atjachment, J.	508,671 508,618 508,606 508,606 508,607 508,628 11,289 568,533 508,819 508,684 508,684 508,684 508,684 508,684 508,684 508,684 508,686 508,688 508,688 508,688 508,688 508,688 508,688 508,688 508,688 508,688 508,688 508,688 508,688
2 3 25 09783577 4	engines, automatic safety stop for, A. J. Bates. Engines, igniting apparatus for gas, G. E. Hoyt Excavator, F. H. Schulte Extension table, R. Mainardi. Extractor. See Butter extractor. Stump extractor. Ereglass guard, G. Bausch (r) Ereglass guard, G. H. Brunk Erence, W. N. Lane. Erence, W. N. Lane. Erence, W. M. Lane. Erence, E. Holden, G. H. Erence, E. Holden, E. Erence, E.	508,671 508,618 508,606 508,606 508,607 508,628 11,289 568,533 508,819 508,684 508,684 508,684 508,684 508,684 508,684 508,684 508,686 508,688 508,688 508,688 508,688 508,688 508,688 508,688 508,688 508,688 508,688 508,688 508,688

Horseshoe, W. C. Edge. 568, 568, 568, 568, 568, 568, 568, 568,	350	
Ironing board or cylinder, for ironing machines, 1962, 582, 1962. See Petergains jack. 1962. See Peter	Horseshoe, W. C. Edge	18,903
Ironing board or cylinder, for ironing machines, 1962, 582, 1962. See Petergains jack. 1962. See Peter	Hossis 99. Hose coupling, G. Ferlinden. 50. Hose banger, G. A. Tower 50. House. See Chicken house. 50. Hydraulic elevator, T. W. Eaton 50. Hydraulic elevator, T. W. Eaton 50.	18,448 18,786
Ironing board or cylinder, for ironing machines, 1962, 582, 1962. See Petergains jack. 1962. See Peter	vice for A. J. McArthur. 50 ce, means for cutting, L. Daft 50 ncubator, E. W. Andrews 50 ncubator, E. J. Bray 50	18,808 18,808
Jar of bottle receiver, R. Good. Stitchen uneals, B. Hilse, Lewis. Kittchen mensil, B. Hilse, Lewis. Knitting machine, circular, E. J. Franck. Knitting machine, circular, E. J. Franck. Knitting machine, dijustable support for the cloth-wheels and burr wheels of rotary, E. Vermilyes. Lamen and the commendation of the commendation of the cloth-wheels and burr wheels of rotary, E. Vermilyes. Lamen commendation of the commendation of the cloth of the cl	nculator, J. M. H. Sponder ndicator. See Speed indicator. nsulating composition, E. Thomson	8,653
Knitting machine, circular, E. J. Franck. Knitting machine, circular, E. J. Franck. Knitting machines, and justable support for the Overmilyeaes and burr wheels of rotary, E. Laces, apparatus for pointing and punching shoe, Laces, apparatus for pointing and punching shoe, Laces, apparatus for pointing and punching shoe, Ladder, L. D. Craig. Lamp, electric bicycle, G. Mayr. Lamp, electric are, E. Thomson Candescent electric, Burnett & Doane. Lamps, apparatus for treating filaments for in- candescent electric, Burnett & Doane. Thomson for the streating filaments for in- candescent electric, Burnett & Doane. Thomson for the streating filaments for in- candescent electric, Burnett & Doane. Thomson for the streating filaments for in- candescent electric, Burnett & Doane. Thomson for the streating filaments for in- candescent electric, Burnett & Doane. Thomson for the streating filaments for in- candescent electric, Burnett & Doane. Thomson filaments for in- candescent electric, Burnett & Doane. Thomson filaments for in- candescent electric are, E. R. Knowles Lamps, stand for testing electric are, E. R. Knowles Lamps, stand for testing electric are, E. R. Lantern, F. Whiting Lantern, F. Whitin	ar or bottle receiver. R. Good	
Laces, apparatus or pointing and puneming snoe, Ladder, L. D. Craig. Lander L. D. Craig. Lamb, electric bicycle, G. Mayr. Lamp, electric arc, E. Thomson. Lamp, electric bicycle, G. Mayr. Sex. Sex. Sex. Sex. Sex. Sex. Sex. Sex.	Knitting machine, circular, E. J. Franck	18,512
Lamps, stand for testing electric are, E. R. Knowles, Sh. (Antern, F. Whiting. Sh. (Antern, Feberder, F. A. Smith. Sh. (Antern, F. Sh.	Laces, apparatus for pointing and punching snoe,	18.816
Lamps, stand for testing electric are, E. R. Knowles, Sh. (Antern, F. Whiting. Sh. (Antern, Feberder, F. A. Smith. Sh. (Antern, F. Sh.	Lamp, electric bicycle, G. Mayr	10,000
Lighting device, hydrocarbon, F. A. Cody. A. Swan. Lighting device, hydrocarbon, F. A. Cody. Sos. 21 Lighting device, hydrocarbon, F. A. Cody. Sos. 21 Lighting device, hydrocarbon, F. A. Cody. Sos. 22 Lighting device, hydrocarbon, F. A. Cody. Sos. 23 Lighting device, hydrocarbon, F. A. Cody. Sos. 26 Lighting device, hydrocarbon, F. A. Cody. Sos. 26 Lighting device, hydrocarbon, F. A. Cody. Sos. 26 Load lifter and carrier, T. H. Butcher. Locomotive fire kindling apparatus, J. McNaughton. Son. & Land. Lubricator, Mowrer & Jordan. Machine dle, A. Vuillier. Sos. 36 Marbet cover, Hickey & Norris. Sos. 36 Marbet, M	Thomson)8,623)8,496
Lighting device, hydrocarbon, F. A. Cody. A. Swan. Lighting device, hydrocarbon, F. A. Cody. Sos. 21 Lighting device, hydrocarbon, F. A. Cody. Sos. 21 Lighting device, hydrocarbon, F. A. Cody. Sos. 22 Lighting device, hydrocarbon, F. A. Cody. Sos. 23 Lighting device, hydrocarbon, F. A. Cody. Sos. 26 Lighting device, hydrocarbon, F. A. Cody. Sos. 26 Lighting device, hydrocarbon, F. A. Cody. Sos. 26 Load lifter and carrier, T. H. Butcher. Locomotive fire kindling apparatus, J. McNaughton. Son. & Land. Lubricator, Mowrer & Jordan. Machine dle, A. Vuillier. Sos. 36 Marbet cover, Hickey & Norris. Sos. 36 Marbet, M	Antern pinion, A. Junghans 50, Lantern, reflector, F. A. Smith. 50, Latch, 1. J. Gray 50, Latch and lock combined, A. Linsmayer. 50, Latch and lock combined, A. Linsmayer. 50, Latch madula, expension, I. G. Lonkins. 50	18,776 18,541 18,890
Lighting device, hydrocarbon, F. A. Cody Sec. 21 Lighting device, hydrocarbon, F. A. Cody Lighting device, hydrocarbon, F. A. Cody Lighting arrester. E. Thomson. 568,61 Liquid meter, F. Shippen. 100 Liquid meter, F. Bluther. 100 Liquid meter, Bluther. 100 Liquid meter. 1	Level, spirit, H. O. Risse 5. Lever and locking mechanism therefor, M. J. Todd 5. Light. See Search light.)8,762
Locomotive fire kindling apparatus, J. McNaugh John Stern Stern bolder, L. W. Milliken. 508,36 Lubricator, Mowrer & Jordan W. Milliken. 508,46 Lubricator, Mowrer & Jordan W. Milliken. 508,46 Machine de, A. Vuillier. Magnet coil and manufacturing same, field, Johnson & Haskins. Magnet coil and manufacturing same, field, Johnson & Haskins. Magnet coils, connector for electro, M. O. Southworth. Magnetic permeameter, Knap & Sprong. 508,47 Manhole cover, Hickey & Norris Marble, manufacturing artificial, Majewski & Beyenbach. Marble, manufacturing artificial, Majewski & Beyenbach. Marble, manufacturing artificial, Majewski & Beyenbach. Mechanical movement, A. G. Brewer. 508,67 Metal tie and nut lock, J. P. Warner. 508,66 Meter. See Electric meter. Liquid meter. Mill. See Bone cutting mill. Stamp mill. Windmill. Mine trap door, Herth & Bonenberger. 508,87 Mould skim gate, W. A. James. 508,87 Mould skim gate, W. A. James. 508,80 Mould skim gate, W. A. James. 508,80 Mould skim gate, W. A. James. 508,70 Newspaper word box. Manping bats an apparatus therefor, forming specific particular and	Lighting circuits, branch block for incancescent, A. Swan. Lighting device, hydrocarbon, F. A. Cody. Lighting arrester, E. Thomson. Liquid meter, F. Shippen	18,644 18,812 16,648 18,774
Lubricator, Nowrer & Jordan. Machine die, A. Vuillier. Magnet coil and manufacturing same, field, Johnson & Haskins. Magnet coils, connector for electro, M. O. Southson, Magnet C. Southson, M. G. Brewer. Mill. See Bone cutting mill. Stamp mill. Windmill. Mine trap door, Herth & Bonenberger. Mill. See Bone cutting mill. Stamp mill. Windmill. Mine trap door, Herth & Bonenberger. Mill. See Bone cutting mill. Stamp mill. Windmill. Mine trap door, Herth & Bonenberger. Mould Stim gate, W. A. James. Motor. See Current motor. Ether vapor motor. Fan motor. Railway motor. Muzzle, J. Helliz. Mapping bats and apparatus therefor, forming and sticking, W. A. Bagilin. Southson, Mapping bats and apparatus therefor, forming and sticking, W. A. Bagilin. Southson, M. See, M. Southson, M	Load lifter and carrier, T. H. Butcher)8,882)8,866
Magnet coils, connector for electro, M. O. Southworth worth several services of the several several services of the several several services of the several	Lubricator, Mowrer & Jordan	18,485 18,789
Mechanical movement, A. G. Brewer. Motal tie and nut lock, J. P. Warner. Meter. See Electric meter. Liquid meter. Mill. See Bone cutting mill. Stamp mill. Wind- mill. See Glass mould. Sand mould. Mine trap door, Herth & Bonenberger	Magnet coils connector for electro M () South-	08,643 08,827 08,841
Mine trap door, Herth & Bonenberger	Marble, manufacturing artificial, Majewski & Beyenbach. 50 Mechanical movement, A. G. Brewer. 55 Metal tie and nut lock, J. P. Warner. 50 Meter. See Electric meter. Louid meter.	08,73 1 08,676
Motor. See Current motor. Ether vapor motor. Fan motor. Railway motor. Fan motor. Railway motor. Muzzle, J. Heing. Angaping bats and apparatus therefor, forming and sticking, W. A. Bagiln	Mine trap door, Herth & Bonenberger 50	
Pegging jack, C. O. Bjorkander. Pencil, addition, A. M. Grubbs. Fencil holder, G. W. Washburn. Fencil sharpener, A. Fornander. Fencil sharpener, A. Fornander. Fencil sharpener, A. Fornander. Fendulum mercurial compensation, S. Riefler. Sos, 76 Fendulum, mercurial compensation, S. Riefler. Sos, 76 Finance and Finance an	Motor Sac Current motor Ether vanor motor)8,856 08,884
Pegging jack, C. O. Bjorkander. Pencil, addition, A. M. Grubbs. Fencil holder, G. W. Washburn. Fencil sharpener, A. Fornander. Fencil sharpener, A. Fornander. Fencil sharpener, A. Fornander. Fendulum mercurial compensation, S. Riefler. Sos, 76 Fendulum, mercurial compensation, S. Riefler. Sos, 76 Finance and Finance an	Muzzle, J. Heinz. 5 Napping bats and apparatus therefor, forming and sticking. W. A. Baglin. 5 Newspaper holder, W. Schweitzer. 5	08.050
Pegging jack, C. O. Bjorkander. Pencil, addition, A. M. Grubbs. Fencil holder, G. W. Washburn. Fencil sharpener, A. Fornander. Fencil sharpener, A. Fornander. Fencil sharpener, A. Fornander. Fendulum mercurial compensation, S. Riefler. Sos, 76 Fendulum, mercurial compensation, S. Riefler. Sos, 76 Finance and Finance an	Newspaper lock box, E. J. Colby. Newspaper wrapping machine, L. C. Crowell. 5 Nut lock, H. P. Brown. 5 Nut lock, Harmon & Faber. 5 Nut lock, W. M. Reed. 5	
Pegging jack, C. O. Bjorkander. Pencil, addition, A. M. Grubbs. Fencil holder, G. W. Washburn. Fencil sharpener, A. Fornander. Fencil sharpener, A. Fornander. Fencil sharpener, A. Fornander. Fendulum mercurial compensation, S. Riefler. Sos, 76 Fendulum, mercurial compensation, S. Riefler. Sos, 76 Finance and Finance an	Dil can, T. Schirrmacher. 5. Dre roasting and calcining furnace, R. C. Greer. 5. Packing case, E. A. Turner. 5. Panorama, balloon, C. G. Rodeck. 5. Paper box, J. J. Hoffman 508,570, 5.	08,451 08.763
Pegging jack, C. O. Bjorkander. Pencil, addition, A. M. Grubbs. Fencil holder, G. W. Washburn. Fencil sharpener, A. Fornander. Fencil sharpener, A. Fornander. Fencil sharpener, A. Fornander. Fendulum mercurial compensation, S. Riefler. Sos, 76 Fendulum, mercurial compensation, S. Riefler. Sos, 76 Finance and Finance an	Paper boxes, machine for making, C. R. Bannihr. 58 Paper cutter, rotary, H. L. Mellor	
Pianoforte action, J. Greener	Paring fruit or vegetables, machine for, E. J. Lewis 5 Paving block, H. Brunson 5 Pegging jack, G. O. Bjorkander 5 Pencil addition A. M. Grubbs 5	08,729 08,537 08,862
Pianoforte action, J. Greener	Pencil holder, G. W. Washburn 59 Pencil sharpener, A. Fornander. 59 Pendulum escapement, S. Riefler 59 Pendulum, mercurial compensation, S. Riefler 59 Piano action. J. F. Conover 59	08,693 08,760
Press. See Baling press. Bookbinding press. Hay press. Pressure engine, fluid, R. A. Parke 508,52 Printing machine, W. M. D. Turton 508,53 Printing machine, W. M. D. Turton 508,53 Printing press web feeding device, J. L. Cox. 508,81 Printing show bills or similar articles, F. G. Annison 508,71 Pulley line hanger, H. Reichwein 508,73 Pulping engine, G. Miller 508,73 Pump, air, W. C. Whitacre 508,83 Pump, duplex rotary force, I. P. Lambing 508,73 Punch and stamp, combined ticket, W. S. Eiseman 508,83 Quicksand, method of and apparatus for handling or controlling, C. Horton 508,71 Rack, See Rotating rack	Pianoforte action, J. Greener	08,416 08,540 08,598
Press. See Baling press. Bookbinding press. Hay press. Pressure engine, fluid, R. A. Parke 508,52 Printing machine, W. M. D. Turton 508,53 Printing machine, W. M. D. Turton 508,53 Printing press web feeding device, J. L. Cox. 508,81 Printing show bills or similar articles, F. G. Annison 508,71 Pulley line hanger, H. Reichwein 508,73 Pulping engine, G. Miller 508,73 Pump, air, W. C. Whitacre 508,83 Pump, duplex rotary force, I. P. Lambing 508,73 Punch and stamp, combined ticket, W. S. Eiseman 508,83 Quicksand, method of and apparatus for handling or controlling, C. Horton 508,71 Rack, See Rotating rack	Pile, iron or steel, A. Hooven Pipe threading machine, F. W. Smith, Jr508,581, 59 Planing machine, J. S. Graham Planter, corn, L. C. Evans. 50 Planter, corn, L. C. Evans.	NS 881
Press. See Baling press. Bookbinding press. Hay press. Pressure engine, fluid, R. A. Parke 508,52 Printing machine, W. M. D. Turton 508,53 Printing machine, W. M. D. Turton 508,53 Printing press web feeding device, J. L. Cox. 508,81 Printing show bills or similar articles, F. G. Annison 508,71 Pulley line hanger, H. Reichwein 508,73 Pulping engine, G. Miller 508,73 Pump, air, W. C. Whitacre 508,83 Pump, duplex rotary force, I. P. Lambing 508,73 Punch and stamp, combined ticket, W. S. Eiseman 508,83 Quicksand, method of and apparatus for handling or controlling, C. Horton 508,71 Rack, See Rotating rack	& Whipple. Splow, sulky, S. E. Calif. Spoket or bag, hanging, I. A. Margesson. Spoketal note, E. A. Curley. Splows and splow of the control o	08,893
Pulley line hanger, H. Reichwein 508,73 Pulping engine, G. Miller 508,73 Pump, air, W. C. Whitacre 508,93 Pump, duplex rotary force, I. P. Lambing 508,57 Punch and stamp, combined ticket, W. S. Eiseman 600,000 Quicksand, method of and apparatus for handling or controlling, C. Horton 608,71 Rack, See Rotating rack 100,000 Rack, See Rotating rack 100,000 Rack 500,000 R		
man	Printing machine, W. M. D. Turton. 58 Printing press web feeding device, J. L. Cox. 58 Printing show bills or similar articles, F. G. Annison. 59 Profiling machine, G. E. Hunter. 59	08,814
Quicksand, method of and apparatus for handling or controlling, C. Horton	runch and stamp, combined ticket, w.s. Eise-	
Rail joint, J. Schuler 508,58 Rails, apparatus for unloading and distributing, 508,50 H. W. Byers 508,80 Railway brake, electric, A. De Bovet 508,50 Railway, electric, J. C. Henry 508,71 Railway, electric, Z. D. C. Henry 508,61 Railway motor, electric, E. D. Priest 508,63 Railway rail brace, D. Markley 508,73 Railway rail splice, A. McHugh 508,90 Railway switch, V. Cruser 508,41 Railway switch, V. Cruser 508,41 Railway switch, V. Cruser 508,41 Railway track cleance, electric, H. O'Connor 508,72 Railway trolley, electric, J. Chase 508,58 Railway trolley, electric, J. Chase 508,58 Railway trolley, electric, S. D. Field 508,52 Railway trolley, electric, W. H. Knicht 508,52	Quicksand, method of and apparatus for handling or controlling, C. Horton	08,714
Railway, electric, J. C. Henry 598,71 Railway, elevated, L. Johnston 598,47 Railway motor, electric, E. D. Priest 598,58 Railway rail brace, D. Markley 598,58 Railway rail splice, A. McHugh 588,59 Railway switch, V. Cruser 598,51 Railway switch, V. Cruser 598,41 Railway switch, V. Cruser 598,41 Railway track cleaner, electric, H. O'Connor 598,74 Railway trolley, electric, N. C. Bassett 598,52 Railway trolley, electric, J. Chase 598,53 Railway trolley, electric, S. D. Field 598,53 Railway trolley, electric, W. M. Knicht 598,52	Rail joint, J. Schuler. 5 Rails, apparatus for unloading and distributing, H. W. Byers. 5 Railway brake, electric, A. De Bovet. 5 Railway conduit, electric, A. J. Robertson. 5 Railway conduit, electric, A. J. Robertson. 5	08,580 08,868 08,805 08,578
Railway spike, J. L. Gage. 508,87 Railway switch, V. Cruser. 508,41 Railway switch, electric, E. M. Bentley. 508,67 Railway track cleaner, electric, H. O'Connor. 508,76 Railway trolley, electric, N. C. Bassett. 58,86 Railway trolley, electric, J. Chase. 508,53 Railway trolley, electric, S. D. Field. 508,33 Railway trolley, electric, W. H. Knicht. 508,83	Railway, electric, J. C. Henry. 5 Railway, electric, J. Dohnston 5 Railway motor, electric, E. D. Priest. 5 Railway rail brace, D. Markley. 5 Railway rail splice A McHuch 5	08,615 08,478 08,633 08,575 08,575
Railway trolley, electric, J. Chase	Railway spike, J. L. Gage. 5 Railway switch, V. Cruser 5 Railway switch, electric, E. M. Bentley 5 Railway track cleaner, electric, H. O'Connor 5 Railway track cleaner, electric, M. Cassatt 5 Railway track cleaner, electric N. C. Bassatt 5	08,877 08,413 08,672 08,743
Railways, converter system for electric, C. S. Bradley 508 80	Railway trolley, electric, J. Chase. 58 Railway trolley, electric, S. D. Field. 58 Railway trolley, electric, W. H. Knight. 58 Railways, converter system for electric, C. S. Bradley.	,.03 08,538 08,539 08,622
Rake. See Hay rake. Ratchet wrench, M. D. Schaller	Refrigerator, Kroenke & Bindewald 5. Refrigerator weighing and registering attachment, W. B. Dickson 5. Register. See Autographic register. Resawing machine. Graham & Kane 5.	.5,520 08,507 08,515
Resin, manufacture of, K. L. Etheridge 508,60 Rheostat, J. B. Blood 508,77 Rocking chair, S. Chambers 508,40 Roofing, C. E. Pope 508,75 Rotary engine, W. S. Petty 508.55	Kesin, manuracture of, R. L. Etheridge. 5 Rheostaf, J. B. Blood. 5 Rocking chair, S. Chambers. 5 Roofing, C. E. Pope. 5 Rotary engine, W. S. Petty. 5	ux,608 08,674 08,403 08,751 08,555
Rotating rack for holding robes, etc., F. G. Wood 568,45 Rubber boot, O. P. Hurd 568,58 Safe, E. Meyers 568,59 Safe locks, method of and apparatus for controll- ing and utilizing concussion and applying it	Rotating rack for holding robes, etc., F. G. Wood 5 Rubber boot, O. P. Hurd. 5 Safe, E. Meyers. 5 Safe locks, method of and apparatus for controli- ing and utilizing concussion and applicable.	18,459 08,619 08,895
Rotating rack for holding robes, etc., F. G. Wood 508,45 Rubber boot, O. P. Hurd 508,61 Safe, E. Meyers 508,89 Safe locks, method of and apparatus for controlling and utilizing concussion and applying it to, M. A. Dalton 508,90 Sand mould, S. J. Adams 508,50 Saw, crosscut, B. F. Moss 508,50 Saw weight, R. S. Judson 508,50 Saw diling device, G. A. Kennedy 508,78 Saw handle, E. Andrews 508,79 Scraper, E. J. Davy 508,70 Screwdriver, S. S. Hand 508,70 Screwdriver, S. S. Hand 508,70 Sorew machine, automatic, O. P. Briggs 508,86	to, M. A. Dalton	08,902 08,590 08,546 08,484 08,792
Saw handle, E. Andrews. 508,79 Scraper, E. J. Davy. 508,85 Screwdriver, S. S. Hand. 508,70 Screw machine, automatic, O. P. Briggs. 508,86	Saw handle, E. Andrews. 5 Scraper, E. J. Davy. 5 Screwdriver, S. S. Hand 5 Screw machine, automatic, O. P. Briggs. 5	08,798 08,685 08,706 08,864

	2 cicuit	**
77	Search light, A. L. Rohrer Separator, Wheelan & Jessup Sewing machine, G. H. Colley Sewing machine, D. Howell Shade hanger, window, J. A. Thompson Shatt, structural hollow, Johnson & Stowe. Sheet metal can, F. H. Palmer Shoulder brace, W. H. Horn. Show case or rack, E. F. Spencer. Show tray for dri ed fruit, W. R. M. Tortat. Shutter closer and fastener, J. K. Christy Sifter, ash, Lewis & Ross. Skate truck, roller, C. G. Hoerle. Skating rink, artificial ice, T. L. Rankin. Sliding gate, H. Withey. Slate, drawing, A. K. Cross. Slate dressing or planing machine, T. J. Ruch Snow sweeper, N. C. Bassett. Soap, manufacturing toilet, T. C. Stearns. Soap suspension attachment, C. A. Breul. Spectacles, M. F. Wickliffe.	508,642
ខ	Separator, Wheelan & Jessup	508,792 508,600
8	Sewing machine, D. Howell	508,715 508,783
8	Shaft, structural hollow, Johnson & Stowe Sheet metal can. F. H. Palmer	508,826 508,554
0	Shoulder brace, W. H. Horn	508,713 508,445
9	Show tray for dried fruit, W.R. M. Tortat	508,449 508,404
9 8	Sifter, ash, Lewis & Ross	508,728 508,617
2	Skating rink, artificial ice, T. L. Rankin	508,755 508,666
3	Slate, drawing, A. K. Cross	508,468 508,579
9	Snow sweeper, N. C. Bassett	508,668 508,777
5	Soap suspension attachment, C. A. Breul. Spectacles, M. F. Wickliffe. Speed indicator for shafting, W. F. Dial. Speed recorder, J. C. Henry. Spindle support, J. H. Northrop. Spokeshave, H. D. Lanfair. Stamp, hand, C. H. Burgess. Stamp mill and amalgamator, Carter & Bell. Stand. Stamp.	508,809
9	Speed recorder, J. C. Henry	508,614 508,749
2	Spokeshave, H. D. Lanfair	508,427 508,865
2	Stamp mill and amalgamator, Carter & Bell Stand. See Umbrella stand.	508,679
35	Stave bending machine, J. Deters	508,506 508,532
6	Steam-tight coupling, L. M. Rouse	508,765 508,708
ñ	Stand. See Umbreila stand. Stave bending machine, J. Deters. Steam boiler, D. Rousseau. Steam-tight coupling, L. M. Rouse. Steam trap, M. Hey. Steam trap, R. R. Leitch. Stocking supporter, O. Huff Stone, machine for sawing blocks of, A. Jeansaume.	508,727 508,883
8	Stone, machine for sawing blocks of, A. Jean-saume	508,825
i9	Stove heating, J. Wilson.	508,794
23	Stove or Turnace, H. C. Hornish	508,874
)6)1	Sugar by synthesis, manufacture of crystallizable, I. E. Pellegrini	500,401
6 6	Sulky, W. A. Galbraith	508,415 508,707
100	Switch. See Car switch. Electric snap switch. Railway switch.	000,101
15 32	Stone, machine for sawing blocks of, A. Jean- saume. Stove grate, F. Will. Stove, heating, J. Wilson. Stove or furnace, H. C. Hornish. Stove present of the same store of crystallizable. J. E. Pellegrini. Sulky, W. A. Galbraith. Switch. See Car switch. Electric snap switch. Railway switch. Switch See Car switch. Electric snap switch. Railway switch. Switchboard, multiple, M. G. Kellogg (r). Switchboard, multiple, M. G. Kellogg (r). Switchboard, multiple, M. G. Kellogg (r). Switchboard and switch school of the same shaped. Synchronism, device for indicating, C. F. Scott. Table. See Display table. Extension table. Table and writing cabinet, combined, J. Danner. Tack driving machine, G. A. Stiles Tack plumber's, W. H. Evory. Tacking machine, hand, C. W. King. Tea pot, coffee pot, etc., F. Mann. Telephone, electric, E. Noriega. Thill coupling, J. R. Mikesell. Thill coupling, J. R. Perkins. Tie. See Metal tie. Time recorder, workman's, M. M. Zellers.	508,840
34	11,386 to Switchboard, power station, Rohrer & Mansfield	11,388 508,641
14	Table. See Display table. Extension table.	500.489
2	Tack driving machine, G. A. Stiles	508,780
4	Tacking machine, hand, C, W. King Tea pot, coffee pot, etc., F, Mann	508,547 508,828
62 66	Telephone, electric, E. Noriega Telephone transmitter, E. Noriega	508,830 508,829
39	Thill coupling, J. R. Mikesell	508,896 508,526
50 35 39	Tie. See Metal tie. Time recorder, workman's, M. M. Zellers	508,461
20	Tire, pneumatic, Kirk & Hosford.	508,621
13	Tire, pneumatic, C. F. Pease	508,746
11	Tire, wheel, C. A. Gildemeyer	508,610 508,738
71 31	Tongs, pipe, H. Alexander Toy, J. L. Tate	508,591 508,558
76 54	Tie. See Metal tie. Time recorder, workman's, M. M. Zellers. Tire, bicycle, F. White. Tire, pneumatic, Kirk & Hosford. Tire, pneumatic, G. F. A. Kitchen. Tire, pneumatic, C. F. Pease. Tire, rubber, Buck & Volger Tire, wheel, C. A. Gildemeyer. Tongs for drawing skelps, W. McCracken. Tongs, pipe, H. Alexander. Toy, J. L. Tate. Track sanding apparatus, C. W. Sherburne, 508,849, Transformers, cooling, E. Thomson. Trap. See Steam trap.	508,850
	Transformers, cooling, E. Thomson. Trans. See Steam trap. Trolley lines, construction of, G. Q. Seaman. Tug hook, D. H. Langan. Typine cutter, W. K. Kennard. Typewriting machine type cleaner, A. G. MacGregor Umbrella, folding, F. M. Hunt. Umbrella frame, A. R. Peppin. Umbrella frame, A. R. Peppin. Umbrella stand, J. Danner. Valve gear, W. B. Waterman Valve gear, W. B. Waterman Valve operating device for wash basins, bathtubs, etc., discharge, J. H. Stevens. Valve, steam, J. N. Murphy. Valve, steam oylinder relief, W. H. Bailey. Vehicle brake, P. J. Hanley Vehicle brake, P. J. Oe Witt Vehicle running gear, W. R. Maxwell. Velocipede car, D. W. Brunton Velocipede pedal, T. Broadbent Violin P. Donnelly Violin bow, Noble & Street. Vise for milling machines or planers, V. W. Mason, Jr.	508,771
79	Tug hook, D. H. Langan Twine cutter, W. K. Kennard	508,521 508,424
23 56	Typewriting machine type cleaner, A. G. MacGregor	508,904
34 34	Umbrella, folding, F. M. Hunt Umbrella frame, A. R. Peppin	508,717 508,436
	Valve, J. R. Branden	508,464
19	Valve mechanism, air brake, T. H. Haberkorn Valve operating device for wash basins bath-	508,702
59 69	tubs, etc., discharge, J. H. Stevens Valve, steam, J. N. Murphy	508,585 508,486
70 67 02	Valve, steam cylinder relief, W. H. Bailey Vehicle brake, P. J. Hanley	508,593 508,612
23 57 67	Vehicle brake, S. E. Odell	508,832 508,414
42	Velocipede car, D. W. Brunton	508,500 508,569
51 63	Violin. P. Donnelly	508,508 508,741
71 94 76	Velocipade pedal, T. Broadent. Violin, P. Donnelly. Violin bow, Noble & Street. Vise for milling machines or planers, V. W. Mason, Jr. Wagon, rupning geer, E. E. Henderson.	508,732
05	Wagon running gear, E. E. Henderson Wardrobe fixture, J. J. Bisel	508,420 508,596
Õĩ	Washing machine, J. Reed	508,756
29 37 32	Vise for milling machines or planers, V. W. Mason, Jr. Wagon running gear, E. E. Henderson. Wardrobe fixture, J. J. Bisel. Warehouse, grain storage, D. R. Bowker. Washing machine, J. Reed. Watch, stem winding and setting, C. H. Bagley Water for bathing, etc., device for mixing hot and cold, J. H. Stevens. Waterproofing and airproofing inflatable textile	508 384
17	Waterproofing and airproofing inflatable textile fabrics. S. Curlin	508,818
91 93 60	and coid, J. H. Stevens Waterproofing and airproofing inflatable textile fabries, S. Curlin Water tube boiler, W. Cowles Weather strip, R. H. Cutler Wheel. See Car wheel. Whiffletree, E. J. Smith Whiffletrees antirattler for T. F. McKenne	508,410 508,504
30 13	Wheel. See Car wheel. Whiffletree, E. J. Smith	508,444
16 10	windmill, W. B. Collins	508,683 508,683
98	Wire connector, G. A. Trumbull	508,587 508 498
02 31	Wire ropeway grip, D. A. Byers. Wire stretcher, P. Loudenberg	508,810 508,891
32 16 38	Wood graining machine, A. Glacomini	508,696 508,875
94	Wheel. See Car wheel. Whiffletree, E. J. Smith. Whiffletrees, antirattler for, T. F. McKenna. Windmill, W. B. Collins. Windmill, G. B. Snow Wire connector, G. A. Trumbull. Wire reel carrier, F. C. Kilpstein. Wire ropeway grip, D. A. Byers. Wire stretcher, P. Loudenberg. Wood graining machine, A. Glacomini. Wood surfaces, finishing, M. D. Fernanzo. Woodworking tool, L. S. Crittenden. Wrench. See Ratchet wrench. Wrench, H. H. Kendrick.	508,412
11 93	Wrench, H. H. Kendrick	ou8,519
201	DESIGNS.	
30	Proped loof C C Poor	99 009

Bread loaf, C. C. Roes. Corset, W. W. Gould.	22,88
Corset, W. W. Gould	22,88
Corset. D. H. Warner	22.88
Hub runner, J. E. Hobbs	22,91
Stove, heating, G. O. Bergstrom	22,91
Stove, lamp, J. F. Myers	22,91
Wall paper, C. Booze22,885 to	22,90
i İ	

TRADE MARKS. Beer, lager, Ruff Brewing Company...... 23,805

Canned fruits and vegetables, Turin Canning and	
Pickling Company	O
Cement, English Portland, National Building Sup-	
ply Company	3
ply Company	1
ply Company	4
ply Company	7
Corsets, E. Schweinburg	4
Fountains, brooders, and incubators for poultry,	
G. S. Singer	9
Fruit, pie, W. H. Marvin & Company 23,80	Š
Kraut, C. Schopp & Company	2
Liniments, C. Protextor	ő
Meat and compounds thereof, extracts of, Valen-	1
tine's Meat-Juice Company	L
Oils, lubricating, F. Shumpp	
Pharmaceutical or dietetical compounds, Farben-	
fabriken, vormals Fr. Bayer & Company 23,82	3
Pills, plasters, lozenges, and a remedy for coughs,	
B. A. Hertsch	ı
Plasters, liniments, ointments, medicated candy,	
and remedies for coughs, cholera, and head-	
ache, Wilkins & Beckner 23,82	5
Printing presses, Liberty Machine Works 23,82	3
Paints and compositions for protecting iron struc-	
tures from corrosion, Wailes, Dove & Com-	
pany	7
Paints, vehicle, J. C. Weaver 23,81	3
Remedies, certain named, E. M. Beals 23.82	ı
Remedies, certain named, F. P. Cummings 23,82	2
Scouring and polishing preparations, Schulz &	
Phili pp)
Soap, L. I. Buroughs 23,81	3
Soda, dissolved washing, A. Stromberg & Com-	
pany	Э
Suppositories, R. E. Harris & Company 23,82	7
Whisky, P. R. Hentz & Company	3

A printed copy of the specification and drawing of any patent in the foregoing list, or any patent in print issued since 1863, will be furnished from this office for 25 cents. In ordering please state the name and number of the patent desired, and remit to Munn & Co., 361 Broadway, New York.

Canadian patents may now be obtained by the inventors for any of the inventions named in the foregoing list, provided they are simple. at a cost of \$40 each. If complicated the cost will be a little more. For full instructions address Munn & Co., \$61 Broadway, New York. Other foreign patents may also be obtained.

Advertisements.

ORDINARY RATES.

Inside Page, each insertion - - 75 cents a line Back Page, each insertion - - - \$1.00 a line For some classes of Advertisements, Special and Higher rates are required.

The above are charges per agate line—about eight words per line. This notice shows the width of the line, and is set in agate type. Engravings may head advertisements at the same rate per agate line, by measurement, as the letter press. Advertisements must be received at Publication Office as early as Thursday morning to appear in the following week's issue.



IMPROVED LATHES MODERN DESIGNS Also Foot Lathes, Tools and Supplies. Catalogue Free

Sebastian Lathe Co. 120-122 Culvert Street Oincinnati, onio.



SCIENTIFIC AMERICAN SUPPLE-MENT. Any desired back number of the SCIENTIFIC AMERICAN SUPPLEMENT can be had at this office for 10 cents. Also to be had of newsdealers in all parts of the country.





One-eighth to Two h. p. Upright, Horizonta, and Marine. Illustrated booklet sent free on receipt of stump. Gas Engine and Dynamo Castinga. Small Boilers. Experimental work for inventors.

A. J. WEED & SON, 106 Liberty St., NEW YORK



The AUTOGRAPHIC REGISTER.

A Labor-Saving Business System. Enforcing Honesty and Accuracy. Chicago Autographic Register Co. 150 E. Monroe Street, CHICAGO, ILL. Send for catalogue & price list.

Scientific Book Catalogue


RECENTLY PUBLISHED.

Our new catalogue containing over 100 pages, including works on more than fifty different subjects. Will be

mailed free to any address on application.

MUNN & CO., Publishers Scientific American, 361 Broadway, New York.

Shingle, Heading, and Stave Mill Machinery and Veneer Cutting. Send for Cat. A.



Handle Machinery for Turning Handles for Brooms, Axes, etc. Send for Cat. B. Wood Pulp Machinery. Send for Cat. C.

Lockport, N. Y.

INVENTORS, ATTENTION!

We want meritorious Household Utensils and patented novelties to introduce. Inventors are invited to correspond with us.

W. H. KERMAN & CO., NAPOLEON, OHIO.

RAND DRILLCo 23 PARK PLACE NEW YORK A.

HYPNOTISM: its Uses and Abuses. The scibook, just out, \$1.00. 100 page pamphlet, 10c. Address PROF. ANDERSON, S. A. 11, 182 State St., CHICAGO.

The Remington Typewri



As Perfect in Design and Construction as Original Ingenuity, Long Experience, and Constant Improvement can make a Writing Machine. It is Simple, Well Made, Practical, Durable, Easy to Learnand to Operate.

Wyckoff, Seamans & Benedict, ³²⁷ Broadway, New York.

IF YOU HAVE ANY SMALL ARTICLES in Brass or Iron that you want manufactured in quantities, write to THE Jones Bros. Elec-TRIC Co., 28-30-32 West Court St., Cin'ti, O.

NICKEL **ELECTRO-PLATING** Apparatus and Material.

Hanson & Van Winkle Co.
Newark. N. J.
81 Liberty St. N. Y.
23 S. Canal Street,
Chicago.

Parsons Horological Institute. earn the Watch Trade

Engraving and Jewelry Work.

Circular free. PARSONS, IDE & CO.

302 Bradley Ave., PEORIA, ILL.



VANDUZEN SJEAM PUMP THE BEST IN THE WORLD.


Pumps Any Kind of Liquid.

Always in Order, never Clogs nor freezes. Every Pump Guaranteed.

10 SIZES.

200 to 12000 Gallons per Hour. Cost \$7 to \$75 each. Address ` THE VANDUZEN & TIFT CO.,


LIGHTNING CONDUCTORS. - A valuable and exhaustive paper giving Reynold's instructions for erecting and testing lightning rods. Contained in SCIENTIFIC AMERICAN SUFPLEMENT, No. 906. Price 10 cents. To be had at this office and from all newsdealers.



If you want the best Lathe and Drill



MAGIC LANTERNS WANTED AND FOR SALE
HARBACH & CO. 809 Filbert St. Phila, Pa.



THE "OLIN" GAS AND GASOLINE ENGINES, FROM 1 TO 10 HORSE POWER, FOR ALL POWER PURPOSES.

THE OLIN GAS ENGINE CO., 222 CHICAGO STREET, BUFFALO, NEW YORK.



PERFORATORS OF ALL METALS

For Cotton, Oil and Rice Mills, Sugar Houses, Distilleries. Phosphate and Fertilizer Works, Mining and Concentrating, Gas and Water Works, Elevators, Threshers, Separators, Corn Shellers, and all kinds of Grain Cleaning Machinery. Heavy steel and Iron Plates and Cylinders for Screening Ore, Coal, Stone. For Filters, Strainers, Ventilators, Oil, Gas and Vapor Stoves and all special purposes. Special sizes for Coffee Cleaning and Roasting Machinery. Perforated Tin and Brass.

The Harrington & King Perforating Co., Chicago, and 284 Pearl St., N.Y

Founded by Mathew Carey, 1785.

HENRY CAREY BAIRD & CO.

Industrial Publishers, Booksellers, and Importers, S10 Walnut St., Philadelphia, Pa., U. S. A. EF Our new and Revised Caralogue of Practical and Scientific Books. 88 pages, 8vo, and our other Catalogues and Circulars, the whole covering every branch of Sci-ence applied to the Arts, sent free and free of postace to any one in any part of the world who will furnish his



NOTICE.

MINISTRY OF PUBLIC WORKS.

CAIRO, EGYPT.

The Egyptian Government puts up to adjudication the construction and working of a tramway line of narrow gauge from Mansourah to Menzaleh and Matarieh, with its branch lines, on the conditions of the act of concession and the specification, copies of which will be forwarded to those who apply for them by letter adressed to the Minister of Public Works, Cairo, Egypt.

Officis will be received at this Ministry up to noon on the condition of the condition

STEREOPTICONS. AGIC LANTERNS AND CESSORIES, SEND FOR CATALOGUE TO CHAS BESELER MAKER 218 CENTRE ST.

Order and Subscribe to FOREIGN PERIODICALS

for next year, please send for estimate to G. E. STECHERT, S10 Broadway, N. Y., Importer of Books and Periodicals. Branches.—Leipzig, London, Paris.

GATES ROCK & ORE BREAKER



Capacity up to 200 tons per hour. Has produced more ballast, road metal, and broken more ore than all other Breake's combined. Builders of High Grade Mining Machinery. Send for Catalogues. GATES IRON WORKS, 50 C So. Clinton St., Chicago 136 C, Liberty Street, New York, 237 C, Franklin St., Boston, Mass

WANTED—A manufacturer of Bright Cold-Rolled Steel wishes to correspond with parties owning or controlling patented novelties which could be manufactured out of this material.

Address J. G., Box 773, New York.



ALUMINUM @ SKATES



Mosher's Aluminum Racer. Patent applied for. Runner of the best tool steel 1-16 inch thick, 17½ inches long. Aluminum top is polished. Will not rust, warp or split. Is lighter, stronger and handsomer than wood. This skate is of same model with which I made the fastest official time on record. Sent to any address, c. o. d., for \$6 per pair. Address
S. D. MOSHER, Storm King, Dutchess Co., N. Y.



STEEL TYPE FOR TYPEWRITERS



Stencils, Steel Stamps, Rubber and Metal Type Wheels, Dies, etc.
Model and Experimental Work.
Small Machinery, Novelties, etc., manufactured by special contract.
New York Stencil Wks. 100 Nassau St., N.Y

ARAGON PROJECTION LANTERN

The only Electric Lamp for Direct or Alternating Current.

A perfectly steady silvery white light, holding position in the optical centre automatically. Can be seen operating in our Dark Room. Correspondence solicited.

QUEEN & CO., Inc., Philadelphia, Pa., U.S.A.



66665



Fine Calf Dress Shoes, \$3.50, \$4.00 and \$5.00.

Very Stylish.
Policemen's, Farmers' and Letter Carriers' \$3.50
Shoe. Three Soles, Extension Edge.
\$2.50 and \$2.00 Shoes for General Wear. Extra

Value.

Boys and Youths wear the \$2.00 and \$1.75 School Shoe.
For Ladies, \$3.00, \$2.50 and \$2.00 Shoes. Best Dongola. W. L. Douglas Shoes are made of the best material, in all the latest styles, and sold by shoe dealers everywhere.

Do You Wear Them?
W. L. Douglas' name and price is stamped on the bottom before they leave the factory, to protect you against high prices. Doing the largest advertised shoe business in the world we are contented with a small profit, knowing that the extra value put in W. L. Douglas Shoes will give a continuous increase to our business. The dealer who sells you unstamped shoes makes the price to suit himself. He will charge you from \$4 to \$5 a pair for shoes of the same quality as W. L. Douglas \$3 Shoe. The stamped name and price system is the best for you, because it guarantees full value by the manufacturer, for the money paid, and saves thousands of dollars annually to those who wear W. L. Douglas Shoes.

If you wish to economize in your footwear it will pay you to examine W. L. Douglas Shoes when next in need. Sent by Mail, Postage Free, when dealers cannot supply you. Take no substitute. Send for Catalogue with full instructions how to order by mail.

Address W. L. DOUGLAS, Box 551, Brockton, Mass.



ROBERT H. INGERSOLL & BRO., 65 CORTLANDT ST., NEW YORK CITY.



ICE-HOUSE AND COLD ROOM.—BY R. G. Hatfield. With directions for construction. Four engravings. Contained in SCIENTIFIC AMERICAN SUP-PLEMENT, No. 59. Price 10 cents. To be had at this office and from all newsdealers.



The distribution of your power is as important as its application. I know a good deal about the economical distribution of power. Perhaps I could give you a few pointers. Inquiries answered free, catalogues sent free. Catalogues: A, woodworking mach'y; B, mach'y for crass, ivory, horn, etc.; C, shaft'g, pulleys, hangers, etc. P. PRYIBIL, 488-500 W. 41st St., NEW YORK.

SIR RICHARD OWEN.—A SKETCH of the life and labors of this great English naturalist, accompanied with his portrait. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, NO. 909. Price 10 cents. To be had at this office and from all newsdealers.



ENGINES OIL The Shipman Automatic Steam Engine 1, 2, 4, 6 and 8 HORSE POWER, SINGLE. 8 and 22 HORSE POWER, COMPOUND. 1 Insurance Not Affected.

STATIONARY AND MARINE. For All Small Power Work, SHIPMAN ENGINE CO. 200 Summer St., Boston, Mass.



MAKE YOUR- MECHANICAL ENGINEER OR DRAUGHTSMAN; Or qualify to take charge of or to superintend the manufacture of machinery, by devoting your idle hours to Home Study by the method of THE CORRESPOND-ENCE SCHOOL OF MECHANICS. Scranton. Pa. To begin, students need only know how to read and write. Moderate charges. Send for FREE Circular.



The Orguit Comp'y Leading Lithographers w. B. ORCUIT, GENL. Mar. Corresp'd'ce Solicited. Chicago.

E IS DEAD






VELOCITY OF ICE BOATS. A COL lection of interesting letters to the editor of the Si
TIFIC AMERICAN on the question of the speed of boats, demonstrating how and why it is that these sail faster than the wind which propels them. Illust with 10 explanatory diagrams. Contained in SCIEN AMERICAN SUPPLEMENT, No. 214. Price 10 of To be had at this office and from all newsdealers.



98u **USE GRINDSTONES**?

The CLEVELAND STONE CO. 2d Floor, Wilshire, Cleveland, O.



A NIDEAL STUB PEN-Esterbrook's Jackson Stub, No. 442

A specially EASY WRITER, a GOOD INK HOLDER and a DELIGHT to those who use a STUB PEN. ASK YOUR STATIONER FOR THEM. Price, \$1.00 per gross. THE ESTERBROOK STEEL PEN CO., 26 John St., New York.



HE GRIFFIN

A perfect pulverizer of all refractory substances by either the wet or dry process. It works better and at less expense than any other Mill, and is conceded to be the only perfect pulverizing Mill manufactured.

For FREE Illustrated Pamphlet address BRADLEY FERTILIZER CO., 92 STATE ST. BOSTON.



Rubber Rolls and Wheels.

er Wringing Machines, Drying and Ventilating All styles of Trucks made to order. Catalogues GEORGE P. CLARK, Box L. Windsor Locks. Conn.



\$10.00 to \$50.00 per night. A light and proness. Magic Lanterns and Views of popular subjects. Catalogues on application. Part I Optical, Mathematical, 3 Meteorological, 4 Magic Lanterns, etc. L. MANASSE, SS Madison Street, Chicago, Ill.



THE MODERN MARINE BOILER BY A. B. Willits, U.S.N. Description of the principal features of the boilers of the United States man-of-war New York, with a plea to inventive minds for the production of a type of boiler which shall do away with the necessity of the present enormously large and heavy shells, and present a lighter substitute that will perform the duties of both envelope and heating surface conjointly. Contained in SCIENTIFIC AMERICAN SUP-PLEMENT, NO. \$70. Price 10 cents. To be had at this office and from all newsdealers.





"ECONOMY IS WEALTH." Agents wanted to sell the Improved Hn II Typewriter. The only standard machine made for a reasonable price. Prints all languages. Interchangeable type.

Address N. TYPEWRITER CO.
611 Washington Street Boston, Mass.
Mention Scientific American,

NOW READY!

Fourteenth Edition of

Experimental Science



REVISED AND ENLARGED. 120 Pages and 110 Superb Cuts added.

The unprecedented sale of this work sacws conclusively that it is the book of the age for teachers, students, experimenters, and all others who desire a general knowledge of Physics or Natural Philosophy.

In the new matter contained in the last edition will be found the Scientific Use of the Phonograph, the curious optical illusion known as the Anorthoscope, together with other new and interesting optical Illusions, the Optical Projection of Opaque Objects, new experiments in Projection, Iridescent Glass, some points in Photography, including Hand Cameras, Cane Cameras, etc.; Systems of Electrical Distribution, Electrical Tocker, Electrical Chimes, How to Color Lantern Sildes, Study of the Stars, and a great deal of other new matter which will prove of interest to scientific readers.

840 pages, 782 fine cuts, substantially and beautifully bound. Price in cloth, by mail, \$4. Half morocco, \$5.

MUNN & CO., Publishers, Office of the SCIENTIFIC AMERICAN, 361 BROADWAY, NEW YORK.

Advertisements.

ORDINARY RATES.

Inside Page, each insertion, - 75 cents a line Back Page, each insertion, - - \$1.00 a line For some classes of Advertisements, Special and Higher rates are required.

The above are charges per agate line—about eight words per line. This notice shows the width of the line, and is set in agate type. Engravings may head advertisements at the same rate per agate line, by measurement, as the letter press. Advertisements must be received at Publication Office as early as Thursday morning to appear in the following week's issue.

COLD FORGED PRODUCT.

Patented Nov. 11, 1890; Oct. 20, 1891.



Is stiffer and stronger than a common bolt. The fluted shank prevents the bolt from turning in the rim and tire.

COLD **FORGED** MACHINE SCREWS STOVE BOLTS LOCK CAP SCREWS SIDE KNOB SCREWS THREADED WIRES

AMERICAN SCREW COMPANY, PROVIDENCE, R. I.



WILL RUN YOUR
SEWING MACHINE
and other Light Machinery.
A week's work done in a day.
No Plumbing Required.
Delivered free on receipt of price. For Printing Presses, Lathes, Grindstones, Coffee Mills, Ice Cream freezers, Churns, Christmas Gardens, Washing Machines, etc., No. 2, price \$10.


THE BOLCIANO WATER MOTOR CO. 414 Water Street, Baltimore, Md.

Eastman Kodak Company,

Rochester, N. Y

NITTING MACHINERY 🕾 Knitted underwear is in vogue. The best achinery for its manufacture, such as SHIRT MACHINES, SLEEVERS, BAR STITCH MACHINES, etc.,

are made by SCOTT & WILLIAMS, 2077 E. Cumberland Street, Established 1865. Philadelphia, Pa., U. S. A.



Mounted and on Sills, for deep or shallow wells, with steam or horse power.

Send for Catalogue.

Williams Brothers ITHACA, N. Y.

The American Bell Telephone Company 125 MILK ST., BOSTON, MASS.

This Company owns the Letters Patent No. 186,787, granted to Alexander Graham Bell, January 30, 1877, the scope of which has been defined by the Supreme Court of the United States in the following terms:

"The patent itself is for the mechanical structure of an electric telephone to be used to produce the electrical action on which the first patent rests. The third claim is for the use in such instruments of a diaphragm, made of a plate of iron or steel, or other material capable of inductive action; the fifth, of a permanent magnet constructed as described, with a coil upon the end or ends nearest the plate; the sixth, of a sounding box as described; the seventh, of a speaking or hearing tube as described for conveying the sounds; and the eighth, of a permanent magnet and plate combined. The claim is not for these several things in and of themselves, but for an electric telephone in the construction of which these things or any of them are used."

This Company also owns Letters Patent No. 463,569, granted to Emile Berliner, November 17, 1891, for a Combined Telegraph and Telephone; and controls Letters Patent No. 474,231, granted to Thomas A. Edison, May 3, 1892, for a Speaking Telegraph, which cover fundamental inventions and embrace all forms of microphone transmitters and of carbon telephones.

FOR SALE

Electric Launches

Fluted Tire Bolt Used at the World's Fair, can be had at

~A BARGAI

As good as new when delivered to purchaser. Their Design and Finish cannot be improved upon. Apply without delay to

ELECTRIC LAUNCH & NAVIGATION CO.

44 BROAD STREET, NEW YORK.

THE FISHER **Patent Steam Pump Governors** For Steam Pumps Working under Pressure and the FISHER PATENT GRAVITY GOVERNORS For Steam Pumps filling elevated open tanks, are the most positive and durable devices made for the purpose. REDUCING VALVES. Send for circulars and testimonials. FISHER GOVERNOR CO., 201 S. 1st Avenue, - Marshalltown, Iowa.

SAWS Wanted 50,000 Sawyers SAWS and Lumbermen to SAWS and Lumbermen to SAWS send us their full address for a copy of Emarson's Book of SAWS, new 1838 edition. We are first to introduce NATURAL Was for heating and tempering Saws with Wonderful effect upon improving their quality and toughness, enabling us to reduce prices. Address EMERSON, SMITH & CO. (Limited). Beaver Falls, Pa.

AMATEUR PHOTOGRAPHERS.

Finish your own photos, on Celerite Paper. Requires ocxperience, long washings or expensive solutions, Entirely new process. Samples and full particulars free, CELERITE PAPER CO., cor. 26th and State Streets, Gerald Building, Chicago, Ili.

piler Coverings, Millboard, Roofing, Building Felt, Liquid Paints, Etc. H. W. JOHNS MFG. CO., 87 Maiden Lane, N.Y.





The Comptometer



52 to 56 Illinois St.,

CHICAGO.

BRANCH OFFICE:

No. 54 Franklin Street, NEW YORK.

Save time, avoid mistakes and do not ruin their nerves It is operated by keys, like a typewriter, and performs addition, multiplication, division, interest, etc., etc.

ccountants who use

First Nat'l Bank, Brownsville, Texas, writes: "The Comptometer purchased of you has taken the place of one clerk in this office."

Brotherhood Wine Co., New York City, writes: "We would not be with out them if they cost twice as much."

Felt & Tarrant Mfg. Co.

McElveen Furniture Co., Ltd., Pittsburgh, Pa., writes: "In all the two years in which we have used it we have never known it to fail."

Brainard Co-Operative Building & Loan Association, Brainard, Minn., writes: "It is of more importance in a business office than a typewriter."

Supt. St. Lawrence State Hopital, Ogdensburg, New York, writes: "We could not get along without it except with the aid of an additional clerk."

ELECTRIC LIGHTING WE MAKE A SPECIALITY OF INSTALLING ISOLATED ELECTRIC LIGHTING PLANTS FROM 10 to 1000 LAMPS COLUMBIAN MEG. CO. BINGHAMTON N.Y.

COPYRIGHTS.

CAN I OBTAIN A PATENT? For a prompt answer and an honest opinion, write to MUNN & CO., who have had nearly fifty years' experience in the patent business. Communications strictly confidential. A Handbook of Information concerning Patents and how to obtain them sent free. Also a catalogue of mechanical and scientific books sent free. Patents taken through Munn & Co. receive special notice in the Scientific American, and thus are brought widely before the public without cost to the inventor. This splendid paper, issued weekly, elegantly illustrated, has by far the largest circulation of any scientific work in the world. \$3 a year. Specimen copies sent free.

Building Edition, monthly, \$2.50 a year. Single copies, 25 cents. Every number contains beautiful plates, in colors, and photographs of new houses, with plans, enabling builders to show the latest designs and secure contracts. Address MUNN & CO., New York, 361 Broadway.

WORLD'S COLUMBIAN EXPOSItion. A very valuable and comprehensive paper on the subject, giving full descriptions and illustrations of the various exhibition buildings and portraits of the officials and members of the English and French commissions. With 32 illustrations, Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No.910. Price 10 cents. To be had at this office and from all newsdealers.





"IMPROVEMENT THE ORDER OF THE AGE."

The Smith Premier Typewriter Embodies the most Progressive Mechanical Principles. All the Essential Features Greatly Perfected. Perfect and Permanent Alignment. Easiest Running, and Nearly Sflent. All type cleaned in Ten Seconds without Soiling the Hands.

The Smith Premier Typewriter Co., Syracuse, N. Y., U. S. A. We have 20 branch offices in the principal cities throughout the United States.

ELECTRIC ** NOTORS FOR MILLS, FACTORIES, SHOPS, ETC. Our Electric Motors received the Highest Awards at the World's Fair. Write for our Illustrated Folder.

GENERAL ELECTRIC COMPANY,

PRINCIPAL SALES OFFICES.

Street New York | 620 Atlantic Avenue. Boston, Mass. 175 Adams Street Chicago, III. 509 Arch Street Philadelphia, Pa. dRace Streets Chicago, III. 509 Arch Street Street St. Paul, Minn. le Building Atlanta, Ga. | 1333 F Street, N.W. Washington, D. C. Street San Francisco, Cal. | Masonic Temple Denver, Col. Denver, Col. Dense outside the U.S. transacted by Thomson Houston Lateral Res. 180 Acc. 180 44 Broad Street 173 and 175 Adams Street... Fifth and Race Streets... Equitable Building... 15 First Street.... All business outside the U.S. transacted by Thomson-Houston International Electric Co. 44 Broad St. New York

CASH PAID for all kinds of good Second-hand lrou and Wood-Working Machinery. Address W. P. DAVIS, ROCHESTER, N. Y.

INVENTORS I Don't order goods or get a model made until you write us. We can help you. H. H. Franklin Mfg. Co., Onondaga St., Syracuse, N. Y.

OIL WELL SUPPLY GO. 91 & 92 WATER STREET, PITTSBURG, PA. Manufacturers of everything needed for

ARTESIAN WELLS for either Gas, Oil, Water, or Mineral Tests
Boilers, Engines, Pipe, Cordage,
Drilling Tools, etc. Illustrated
catalogue, price lists, and discount sheets on request.

PATENT FOR SALE.

The Aeberly Cattle Stall Device for the enhancement of comfort and cleanliness of milk cattle. Is simple, durable, and can easily be adjusted to almost any crib. The U. S., Great Britain and Canada letters patent for sale. M. SCHEMBRI, 396 Van Buren St., St. Paul, Minn.



THE Motor of 19th Century Can be used any place, to do any work, and by any one. No Boiler! No Steam! No Ashes! No Gauges! No Engineer! A perfectly safe Motor for all places and purposes. Cost of operation about one cent an hour to each indicated horse pour. er. For circulars, etc., addres CHARTER GAS ENGINE CO. P. O. Box 148. Sterling. III

SCIENTIFIC EXPERIMENTS. - DE-SCHENTER C EAFEMMENTS.— DEscription of some simple and easily performed scientific experiments. Foucault's pendulum, exchange of water and wine, the bird in the cage, the five-pointed star, the sum of the angles of a triangle, surface of the sphere, with 6 illustrations. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, NO. 875. Price 10 cents. To be had at this office and from all newsdealers.

AGENTS WANTED FOR FINE TOOLS INEVERYSHOP. CATALOGUE C.H.BESLY& CO.
CHICAGO, ILL.U.S.A.

THE

S GLEMHONG A MORRICAN

ESTABLISHED 1845.

The Most Popular Scientific Paper in the World Only \$3.00 a Year. Including Postage. Weekly-52 Numbers a Year.

Weekty-52 Numbers a Year.

This widely circulated and splendidly illustrated paper is published weekly. Every number contains sixteen pages of useful information and a large number of original engravines of new inventions and discoveries, representing Engineering Works, Steam Machinery, New Inventions, Novelties in Mechanics, Manufactures, Chemistry, Electricity Telegraphy, Photography, Architecture, Agriculture, Horticulture, Natural History etc. Complete list of patents each week.

Terms of Subscription.—One copy of the SCIEN-

TIFIC AMERICAN will be sent for one year—52 numbers—postage prepaid, to any subscriber in the United States, Canada, or Mexico, on receipt of three dollars by the

publishers; six months, \$1.50; three months, \$1.00. (!ubs.—Special rates for several names, and to Post Masters. Write for particulars.

The safest way to remit is by Postal Order, Draft, or Express Money Order. Money carefully placed inside of envelopes, securely sealed, and correctly addressed, seldom goes astray, but is at the sender's risk. Address all letters and make all orders, drafts, etc., payable to

MUNN & (10 ., 361 Broadway, New York.

тне

Scientific American Supplement

This is a separate and distinct publication from THE SCIENTIFIC AMERICAN, but is uniform therewith in size, every number containing sixteen large pages full of engravings, many of which are taken from foreign papers and accompanied with translated descriptions. The SCIENTIFIC AMERICAN SUPPLEMENT is published weekly, and includes a very wide range of contents. It presents the most recent papers by eminent writers in all the principal departments of Science and the Useful Arts, embracing Biology, Geology, Mineralogy, Natural History, Geography, Archæology, Astronomy Chemistry, Electricity, Light, Heat, Mechanical Engineering, Steam and Railway Engineering, Mining, Ship Building, Marine Engineering, Photography, Technology, Manufacturing Industries, Sanitary Engineering, Agriculture, Horticulture, Domestic Economy, Biography, Medicine, etc. A vast amount of fresh and valuable information

obtainable in no other publication.

The most important Engineering Works, Mechanisms and Manufactures at home and abroad are illustrated and described in the SUPPLEMENT.

Price for the SUPPLEMENT for the United States. Canada, and Mexico, \$5.00 a year; or one copy of the SCIENTIFIC AMERICAN and one copy of the SUPPLE-MENT, both mailed for one year to one address for \$7.00. Single copies, 10 cents. Address and remit by postal order express money order, or check.

MUNN & CO., 361 Broadway, New York.

Building Edition.

THE SCIENTIFIC AMERICAN ARCHITECTS AND BUILDERS' EDITION is issued monthly. \$2.50 a year. Single copies, 25 cents. Thirty-two large quarto pages. forming a large and splendid Magazine of Architecture, richly adorned with elegant plates in colors, and with other fine engravings; illustrating the most interesting examples of modern architectural construction and allied subjects.

A special feature is the presentation in each number of a variety of the latest and best plans for private residences, city and country including those of very moderate cost as well as the more expensive. Drawings in perspective and in color are given, together with Plans, Descriptions, Locations, Estimated Cost, etc.

The elegance and cheapness of this magnificent work have won for it the Largest Circulation of any Architectural publication in the world. Sold by all news dealers. \$2.50 a year. Remit to

MUNN & CO., Publishers. 361 Broadway, New York.

PRINTING INKS.

The SCIENTIFIC AMERICAN is printed with CHAS. ENEU JOHNSON & CO.'S INK, Tenth and Lomoard Sts., Philadelphia, and 47 Rose St., opp. Duane, New York